UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Executive Engineer

NOTE

Ref: UH/ENGG/UE/2024-25/ Date: 24.04.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **29.04.2025 at 12.00 P.M. in the Office of the University Works Department.** Hence, All the contractors are requested to remind the following details: -

Submission of Quotations: 29.04.2025 at 12.00 PM

Opening of Quotations: 29.04.2025 at 3.00 PM

S. No	Name of the work	Estimated Cost Rs.
1	**Maintenance of Building: - "Providing and fixing kitchen platform and kitchen wash basin in canteen near CIS Building" in UoH Campus.**	**RS. 47,775/-**

Sd/-
EXECUTIVE ENGINEER A/C

Name of work: Maintenance of Building: -"Providing and fixing kitchen platform and kitchen wash basin in canteen near CIS Building" in UoH Campus.

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	8.2.2.1	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size,approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite stone slab colour black, Cherry/Ruby red. Area of slab upto 0.50 sqm.	2.94	Sqm	Figure: Rs_____ Words: // Rupees_____ _____	
2	17.10.2.1	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required : Kitchen sink without drain board. 610x510 mm bowl depth 200 mm. Make: Nilkanth/ AMC/ Cobra/ Nirali, Diamond/ Hindware.	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	

3/a	18.7.2	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.: Internal work - Exposed on wall. 20 mm nominal outer dia. Pipes. Make: Supreme/ Ashirvad/ Finolex /Prince /Astral	10.00	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
3/b	18.7.3	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. : Internal work - Exposed on wall. 25 mm nominal outer dia .Pipes. Make: Supreme/ Ashirvad/ Finolex /Prince /Astral	10.00	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
4	18.13.1	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete : 25 to 40 mm nominal bore.	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
5	18.53.1	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 : 15mm nominal bore. Make: Jaquar/ Parko/ Marc/ Hindware/ Parryware/ Kingston.	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
6	18.78	Making chases up to 7.5x7.5 cm in walls including making good and finishing with matching surface after housing G.I. pipe etc.	1.00	Rmt	Figure: Rs_____ Words: Rupees_____ _____	

7	18.79	Making hole up to 20x20 cm and embedding pipes up to 150 mm diameter in masonry and filling with cement concrete 1:3:6 (1 cement: 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)including disposal of malba.	1.00	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
8	12.41.1	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. (i)Single socketed pipes. 75 mm diameter. Make: Supreme/ Finolex/ Prince/ Astral.	19.00	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
9/a	12.42.3.1	Providing and fixing on wall face unplasticised - PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipes conforming to IS 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Single tee with door. 75x75x75 mm. Make: Supreme/ Finolex/ Prince/ Astral.	2.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
9/b	12.42.5.1	Providing and fixing on wall face unplasticised - PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipes conforming to IS 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Bend 87.5°. 75 mm bend. Make: Supreme/ Finolex/ Prince/ Astral.	2.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
10	12.43.1	Providing and fixing unplasticised -PVC pipe clips of approved design to unplasticised - PVC rain water pipes by means of 50x50x50 mm hard wood plugs, screwed with M.S. screws of required length, including cutting brick work and fixing in cement mortar 1:4 (1 cement : 4 coarse sand) and making good the wall etc. complete. 75 mm.	2.00	Each	Figure: Rs_____ Words: Rupees_____ _____	

11	2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	0.18	Cum	Figure: Rs_____ Words: Rupees_____ _____	
12/a	4.1.10A	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 manufactured sand derived from Recycled Concrete Aggregate (RCA) : 10 graded stone aggregate 40 mm nominal size including Recycled Aggregate (RA))	0.32	Cum	Figure: Rs_____ Words: Rupees_____ _____	
12/b	4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand(zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources).	1.20	Cum	Figure: Rs_____ Words: Rupees_____ _____	
13	6.2.2	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand).	0.17	Cum	Figure: Rs_____ Words: Rupees_____ _____	
14	13.11	18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement: 5 coarse sand) finished with a top layer 6mm thick cement plaster 1:6 (1 cement: 6 fine sand).	1.60	Cum	Figure: Rs_____ Words: Rupees_____ _____	

		Less Rebate Offered if any_____ **Net Amount _____** **Net Amount in words_____**

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor **Executive Engineer**

Terms & Conditions:

1. The work should be completed within Fifteen(15) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period 6 (six) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/VAT no.
12. TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Executive Engineer

CC to:

1. Executive Engineer
2. A.E. Sub-Division (C-)
3. S O (Works & Bills),
4. Finance & Account
5. O.C.,
6. D.B.,