Name of work: Maintenance of Building: - Replacement of water lines in T I 03 & 05 wash rooms at Ladies Hotel -II ” in UoH Campus.						
1) The estimate amount is inclusive of GST. **2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**						
SCHEDULE OF QUANTITIES						
S. No	**D.S.R.No.**	**Description of item**	**Qty**	**Unit**	**Rate in figures & Rate in words**	**Amount**
1	18.7	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold-water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall			Figure: Rs_____ Words: Rupees_____ _____	
1/a	18.7.3	25 mm nominal outer Dia. Pipes.	40.0	Rmt		
1/b	18.7.2	20 mm nominal outer Dia. Pipes.	80.00	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
	15.44.1	15 mm to 40 mm nominal bore				
2	18.18	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete:	15.00	Each	Figure: Rs_____ Words:	

	18.18.3	25mm nominal bore			Rupees_____ _____	
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ Net Amount _____ Net Amount in words_____				
1) The estimate amount is inclusive of GST. 2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.						
Signature of the Contractor Executive Engineer						

Terms & Conditions:

1. The work should be completed within thirty (30) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 ½ % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period 1 (One) year from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/VAT no.
12. WCT (5%)/TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Executive Engineer

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,