UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Executive Engineer

NOTE

Ref: UH/ENGG/UE/2024-25/ Date: 04-06-2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **06.06.2025 at 12.00 P.M. in the Office of the University Works Department.**

Hence, All the contractors are requested to remind the following details: -

Submission of Quotations: 06.06.2025 at 12.00 PM

Opening of Quotations: 06.06.2025 at 3.00 PM

S. No	Name of the work	Estimated Cost Rs.
1	**Maintenance of Buildings - "Replacement of CPVC pipe lines from terrace to wash rooms in centre for Psychology Building and Replacement of doors at A-29 Quarter" in UoH Campus.**	**RS. 49,940/-**

EXECUTIVE ENGINEER A/C

Name of work :- Maintenance of Buildings - "Replacement of CPVC pipe lines from terrace to wash rooms in centre for Psychology Building and Replacement of doors at A-29 Quarter" in UoH Campus.						
1) The estimate amount is inclusive of GST. **2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**						
SCHEDULE OF QUANTITIES						
S. No	**D.S.R.No.**	**Description of item**	**Qty**	**Unit**	**Rate in figures & Rate in words**	**Amount**
1	15.44	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge :			Figure: Rs_____ Words: Rupees_____ _____	
	15.44.1	15 mm to 40 mm nominal bore	20.00	Rmt		
2	18.9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings. This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge : External work	20.00	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
a	18.9.2	20 mm nominal outer dia. Pipes.			Figure: Rs_____ Words: Rupees_____ _____	
b	18.9.3	25mm nominal outer dia. Pipes.	20.00	Rmt		

3	18.13	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete :				
	18.13.1	25 to 40 mm nominal bore	4.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
4	18.76	Cutting holes up to 30x30 cm in walls including making good the same:				
	18.76.1	With common burnt clay F.P.S. (non modular) bricks.	4.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
5	18.18	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete :			Figure: Rs_____ Words: Rupees_____ _____	
	18.18.3	25 mm nominal bore	2.00	Each		
6	15.12	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :			Figure: Rs_____ Words: Rupees_____ _____	
	15.12.1	Of area 3 sq. metres and below	3.0	Each		
7	19.21	Making connection of drain or sewer line with existing manhole including breaking into and making good the walls, floors with cement concrete 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) cement plastered on both sides with cement mortar 1:3 (1 cement : 3 coarse sand) finished with a floating coat of neat cement and making necessary channels for the drain etc. complete :				

	19.21.2	For pipes 250 to 300 mm diameter	5.70	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
8	9.96	Providing and fixing aluminium sliding door bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with nuts and screws etc. complete :				
	9.96.1	300x16 mm	6.0	Each	Figure: Rs_____ Words: Rupees_____ _____	
9	9.97	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :				
	9.97.4	150x10 mm	6.0	Each	Figure: Rs_____ Words: Rupees_____ _____	
10	9.100	Providing and fixing aluminium handles ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :			Figure: Rs_____ Words: Rupees_____ _____	
	9.100.1	125 mm	6.0	Each		
11	13.62	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade:	13.65	Sqm	Figure: Rs_____ Words: Rupees_____ _____	

	13.62.1	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture.				
12	9.1	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).	0.05`	cum	Figure: Rs_____ Words: Rupees_____ _____	
	9.1.1	Second class teak wood				
13	14.85	Taking out existing wooden door shutter, repair by cutting, painting etc. and refixing of repaired door shutters to existing door frames, including replacement of hinges with screws, etc. as required, all complete as per the direction of the Engineer-in-charge.	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
14	14.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-harge.	4.80	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
	14.1.1	With cement mortar 1:4 (1 cement : 4 fine sand).				
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ **Net Amount _____** **Net Amount in words_____**				

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor **Executive Engineer A/c.**

Terms & Conditions:

1. The work should be completed within thirty (15) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period Six (06) Months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/GST no.
12. GST (18%) will be levied wherever applicable.

Executive Engineer A/c.

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,