UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Executive Engineer

NOTE

Ref: UH/ENGG/UE/2024-25/ Date: 04-06-2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **09.06.2025 at 12.00 P.M. in the Office of the University Works Department.**

Hence, All the contractors are requested to remind the following details: -

Submission of Quotations: 09.06.2025 at 12.00 PM

Opening of Quotations: 09.06.2025 at 3.00 PM

S. No	Name of the work	Estimated Cost Rs.
1	**Name of work: Maintenance of Building: - Providing internal painting, Renovation of wash room and providing tiles to room No. 116 dept. Of Anthropology at Building" in UoH Campus.**	**RS. 49,970/-**

EXECUTIVE ENGINEER A/C

Name of work: Maintenance of Building: - Providing internal painting, Renovation of wash room and providing tiles to room No. 116 dept. Of Anthropology at SSS Building" in UoH Campus.

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R. No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	13.81	Distempering with 1st quality acrylic distemper (ready mixed) having VOC (Volatile Organic Compound) content less than 50 gram/ litre, of approved brand and of required shade and colour complete to give and even shade.			Figure: Rs_____ Words: Rupees_____ _____	
	13.81.1	Old work (one or more coats)	73.30	Sqm		
2	13.88	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete 2	36.65	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
3	13.99	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :			Figure: Rs_____ Words: Rupees_____ _____	
	13.99.1	One or more coats on old work.	17.00	Sqm		
4	15.23	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.	2.70	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
	15.23.1	For thickness of tiles 10 mm to 25 mm				
5	14.83	Hacking of CC flooring including cleaning for surface etc. complete as per direction of the Engineer-in-Charge.	13.60	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
6	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting,	0.85	cum	Figure: Rs_____ Words: Rupees_____	

		unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.			_____	
7	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	4.1.3	1:2:4 (1 cement: 2 coarse sand(zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	0.85	cum	Figure: Rs_____ Words: Rupees_____ _____	
8	11.38	Providing and laying Ceramic glazed floor tiles of size 300x300 mm(thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @3.3kg/sqm including pointing the joints with white cement and matching pigments etc., complete.	17.85	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
9	17.2	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings andfixtures complete, including cutting and making good the walls and floors wherever required :				
	17.2.1	W.C. pan with ISI marked white solid plastic seat and lid	1.00	sssss	Figure: Rs_____ Words: Rupees_____ _____	
10	18.21	Providing and fixing uplasticised PVC connection pipe with brass unions :				
	18.21.2	45 cm length	2.00	Each	Figure: Rs_____ Words: Rupees_____ _____	

	18.21.2.2	20 mm nominal bore				
11	18.53	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 :				
	18.53.1	15mm nominal bore	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
12	22.25	Providing and applying crystalline mortar by mixing in the ratio of 4.5 : 1 (4.5 parts crystalline mortar : 1 part water) for the treatment of faulty construction joints, cracks, tie rod holes and spalled & honeycombed surface of RCC underground structures like basement, water tanks, bridge deck etc. to ensure water tightness. The crystallie mortar shall conform to the EN 1504-3 having compressive strength Class R4 > 45 MPa and adhesive bond strength Class R3 > 1.5 MPa. The work shall be carried out all complete as per specification and the direction of the Engineer-In-Charge. The product performance shall carry guarantee for 10 years against any leakage.				
	22.25.1	For sealing cracks and faulty construction joints, routed out/making U-shape groove size 25x25mm and then primed the area with integral crystalline slurry @0.05kg/ running metre and while the surface is tacky filled the groove upto surface with crystalline mortar @1.50kg/ running metre. Once crystalline mortar is touch dry then finally applied two coats of integral crystalline slurry @0.05kg/running meter per coat.	3.10	Rmt	Figure: Rs_____ Words: Rupees_____ _____	

13	17.32	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing :				
	17.32.2	Rectangular shape 453x357 mm	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
14	14.85	Taking out existing wooden door shutter, repair by cutting, painting etc. and refixing of repaired door shutters to existing door frames, including replacement of hinges with screws, etc. as required, all complete as per the direction of the Engineer-in-charge.	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
15	MR	Supply and fixing of two-way tap of 15mm Dia (Make: Jaquar/ Plumber)	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
16	MR	Supply and fixing of C.P Health Faucet of 15mm Dia (Make: Jaquar/ Plumber)	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ **Net Amount _____** **Net Amount in words_____**				

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor **Executive Engineer A/c.**

Terms & Conditions:

1. The work should be completed within thirty (30) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 ½ % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period Six Months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/VAT no.
12. WCT (5%)/TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Executive Engineer A/C.

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,