UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Executive Engineer

NOTE

Ref: UH/ENGG/UE/2024-25/ Date: 09-06-2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **13.06.2025 at 12.00 P.M. in the Office of the University Works Department.**

Hence, All the contractors are requested to remind the following details: -

Submission of Quotations: 13**.06.2025 at 12.00 PM**

Opening of Quotations: 13**.06.2025 at 3.00 PM**

S. No	Name of the work	Estimated Cost Rs.
1	**Name of work: Maintenance of Building: - Replacement of EWC and washroom doors in D-42 Quarter" in UoH Campus.**	**RS. 34,670/-**

Name of work: Maintenance of Building: - Replacement of EWC and washroom doors in D-42 Quarter " in UoH Campus.

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	15.23	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.			Figure: Rs_____ Words: Rupees_____ _____	
	15.23.1	For thickness of tiles 10 mm to 25 mm	1.65	Sqm		
2	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	1.00	cum	Figure: Rs_____ Words: Rupees_____ _____	
3	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	4.1.3	1:2:4 (1 cement: 2 coarse sand(zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	0.30	cum	Figure: Rs_____ Words: Rupees_____ _____	
4	11.37A	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle	1.65	Sqm	Figure: Rs_____ Words: Rupees_____ _____	

		green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kgper sqm including pointing the joints with white cement mixed with pigment of matching shade complete.				
5	14.82	Dismantling W.C. Pan of all sizes including disposal of dismantled materials i/c malba all complete as per directions of Engineer-in- Charge.	1.00	No.	Figure: Rs_____ Words: Rupees_____ _____	
6	17.2	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings andfixtures complete, including cutting and making good the walls and floors wherever required :	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
	17.2.1	W.C. pan with ISI marked white solid plastic seat and lid				
	18.21.2	45 cm length				
	18.21.2.2	20 mm nominal bore				
7	18.53A	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 :	3.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
	18.53.1	15mm nominal bore				

8	18.76	Cutting holes up to 30x30 cm in walls including making good the same:					
	18.76.1	With common burnt clay F.P.S. (non modular) bricks	2.00	Each	Figure: Rs_____ Words: Rupees_____ _____		
9	18.53.1	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 : 15mm noinal bore	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____		
10	18.21	Providing and fixing uplasticised PVC connection pipe with brass unions :	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____		
	18.21.1.1	15 mm nominal bore					
11	18/17.60	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors :					
	17.60.1	100 mm inlet and 100 mm outlet					
	17.60.1.2	Sand Cast Iron S&S as per IS: 1729.	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____		

12	12.41	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.				
	12.41.1	75 mm diameter	3.00	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
	12.41.2	110 mm diameter	3.00	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
13	12.42	Providing and fixing on wall face unplasticised - PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipes conforming to IS 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion.				
A)	12.42.5	Bend 87.5°				
	12.42.5.1	75 mm bend	2.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
	12.42.5.2	110 mm bend	2.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
14	21/18.7	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints				

		complete as per direction of Engineer in Charge. : Internal work - Exposed on wall				
	18.7.2	20 mm nominal outer dia. Pipes.	10	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
15	22/18.13	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete :	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
	18.13.1	25 to 40 mm nominal bore				
16	23/15.12	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :	2.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
	15.12.1	Of area 3 sq. metres and below				
17	25/9.120	Providing and fixing factory made panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19 mm x 19 mm for styles and 15x15 mm for top & bottom rails. M.S. frame shall have a coat of steel primers of approved make and manufacture. M.S. frame covered with 5 mm thick heat moulded PVC 'C' channel of size 30mm thickness, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on both side forming styles and 5 mm thick, 95 mm wide PVC sheet out of which 75 mm shall be tapered in 45 degree on the inner side to form top and bottom rail and 115 mm wide PVC sheet out of which 75 mm shall				

		be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided both side of the panel. 10 mm (5 mm x 2) thick, 20 mm wide cross PVC sheet be provided as gap insert for top rail & bottom rail, paneling of 5 mm thick both side PVC sheet to be fitted in the M.S. frame welded/ sealed to the styles & rails with 7 mm (5 mm+2 mm) thick x 15 mm wide PVC sheet beading on inner side, and joined together with solvent cement adhesive. An additional 5 mm thick PVC strip of 20 mm width is to be stuck on the interior side of the 'C' Channel using PVC solvent adhesive etc. complete as per direction of Engineer-in-charge, manufacturer's specification & drawing.				
	9.120.2	30 mm thick pre laminated PVC door shutters	3.15	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
18	26/9.97	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :				
	9.97.4	15x10mm	4.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
19	27/9.100	Providing and fixing aluminium handles ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :				
		125 mm	4.00	Each	Figure: Rs_____	

					Words: Rupees_____ _____	
20	MR	Providing and fixing of C.P Health faucet Make:CERA	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ **Net Amount** _____ **Net Amount in words**_____				

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor **Executive Engineer**

Terms & Conditions:

1. The work should be completed within thirty (30) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 ½ % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period 1 (One) year from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/VAT no.
12. WCT (5%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

Executive Engineer

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,