UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Executive Engineer

NOTE

Ref: UH/ENGG/UE/2024-25/ Date: 09-06-2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **13.06.2025 at 12.00 P.M. in the Office of the University Works Department.**

Hence, All the contractors are requested to remind the following details: -

Submission of Quotations: 13**.06.2025 at 12.00 PM**

Opening of Quotations: 13**.06.2025 at 3.00 PM**

S. No	Name of the work	Estimated Cost Rs.
1	**Name of work :- Maintenance of Buildings- " Providing waterproofing work for balcony at Quarter No. A-53 " in UoH Campus.**	**RS. 49,963/-**

Name of work :- Maintenance of Buildings- " Providing waterproofing work for balcony at Quarter No. A-53 " in UoH Campus.

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	MR	Providing waterproofing on terrace with epoxy grouting internal walls injection grouting and external walls crack cutting crack filling. OPERATIONS : a) The Entire old terrace area for which the waterproofing has to be done will be cleaned with air blower b) All the tiles joints groove cutting with cutting machine i.e. "V" groove shape c) Grooves are cleaning with air blower d) Applying Nitobond SBR Latex "Fosroc" with brush. e) Applying epoxy grout "FOSROC"	90.00	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
2	MR	**External Wall Waterproofing :** a) Cracks cutting with cutting machine b) Applying air blower machine c) Applying Nitobond SBR Latex Fosroc d) Crack filling with Asian Crack Seal	10.00	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
3	MR	**Internal Walls Injection Grouting :** a) Drilling points every running feet at leakage spot area b) Applying Nozzle with FOSROC Rendroc plug c) Applying pressure grouting with FOSROC "Cebex 100"	30.00	EACH	Figure: Rs_____ Words: Rupees_____ _____	
					Total Amount in figures Rs	

		Less Rebate Offered if any_____ **Net Amount** _____ **Net Amount in words**_____
1) The estimate amount is inclusive of GST. **2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**		
Signature of the Contractor		**Executive Engineer A/c**

Terms & Conditions:

1. The work should be completed within thirty (7) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 ½ % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period 1 Six Months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/VAT no.
12. WCT (5%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

Executive Engineer A/c

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,