UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Assistant Engineer

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 03.07.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **07.07.2025 at 12.00 P.M. in the Office of the University Works Department.** Hence, All the contractors are requested to remind the following details: -

Submission of Quotations: 07.07.2025 at 12.00 PM

Opening of Quotations: 07.07.2025 at 3.00 PM

S. No	Name of the work	Estimated Cost Rs.
1	Supply and fixing of impellers to 5 HP Pump motor near food court and Lifting and lowering for borewell motor at GT building & excavation work with HDPE pipe line oil joints at VC lodge in U.O.H Campus:– Reg.	**RS. 45,238/-**

p

Assistant Engineer (E)

Name of Work: - Supply and fixing of impellers to 5 HP Pump motor near food court and Lifting and lowering for borewell motor at GT building & excavation work with HDPE pipe line oil joints at VC lodge in U.O.H Campus:–Reg.

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount	D.S.R./MR
1	Supply removing and refixing of submersible motor pump Impellers.	42	Each	Figure:Rs_____ Words:Rupees_____ _____		MR
2	Lifting and Lowering submersible motor pump with HDPE pipe up to 300ft depth by borewell machine etc as required.	300	ft	Figure:Rs_____ Words:Rupees_____ _____		MR
3	Supply and making oil joints for 63mm dia HDPE pip with suitable S.S nipple and nut bolts etc as required.	2	Each	Figure:Rs_____ Words:Rupees_____ _____		MR
4	Supply and fixing of 3 phase 415v,50HZ electronic motor starter with digital display,single phase & over load protection etc as required. Make :Gelco.	1	Each	Figure:Rs_____ Words:Rupees_____ _____		MR
5	Providing Flanged C.I standard collar suitable for flanges jointing as per requirement up to 100mm dia.	1	Each	Figure:Rs_____ Words:Rupees_____ _____		MR
6	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work)					18.46
6.1	50mm nominal bore	1.00	no	Figure:Rs_____ Words:Rupees_____ _____		18.46.6
7	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. : External work					18.12
7.1	50 mm dia. nominal bore	0.30	meters	Figure:Rs_____ Words:Rupees_____ _____		18.12.6
8	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth up to 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including					2.1
8.1	Pipes, cables etc, not exceeding 80 mm dia.	10	meters	Figure:Rs_____ Words:Rupees_____ _____		2.10.1.1

9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. : Internal work - Exposed on wall					18.7
9.1	25 mm nominal outer dia .Pipes.	18.00	meters	Figure:Rs_____ Words:Rupees_____ _____		18.7.3
10	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete :					18.13
10.1	25 to 40 mm nominal bore	1.00	Each	Figure:Rs_____ Words:Rupees_____ _____		18.13.1
	Sub Total					
	GST @ 18%					
	Total					

Signature of the Contractor **Assistant Engineer**

Terms & Conditions:

1.The contractor/ bidder shall be a registered contractor and should produce definite proof of appropriate class registered by state or central government departments or state/central autonomous bodies or undertakings should submit proof thereof.

2. The work should be completed within Fifteen (15) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the

3. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.

4. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.

5. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.

6. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.

7. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.

8. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.

9. Defect liability period 6 (six) months from the date of completion of the work.

10. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.

11. A.E (E) has to enclose the work completion certificate and user department certificate along with the bill.

12. No quotation will be accepted without PAN/VAT no.

13. TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Assistant Engineer

CC to:

1. A.E. Sub-Division (E)
2. S O (Works & Bills),
3. O.C.,
4. D.B.,