UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 30.07.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **04.08.2025 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 04.08.2025 upto 12.00 PM

Opening of Quotations:- 04.08.2025 at 3.00 PM

S.No	Name of the work	Estimated Cost
1	Maintenance of buildings: Providing and fixing of UPVC windows at B-28 Qtr in UoH campus	Rs. 15,500/-

Sd/-
Executive Engineer A/C

Name of work :- Maintenance of buildings: Providing and fixing of UPVC windows at B-28 Qtr in UoH campus						
1) The Bidder should quote rates inclusive of GST. **2) All the below item rates are all inclusive of GST.**						
SCHEDULE OF QUANTITIES						
S. No	**D.S.R.No.**	**Description of item**	**Qty**	**Unit**	**Rate in figures & Rate in words**	**Amount**
1	15.12	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :	2.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
	15.12.1	Of area 3 sq. metres and below				
2	9.147A	Providing and fixing factory made uPVC glazed/wire mesh windows/doors comprising of lead free uPVC multi-chambered frame, sash and mullion/coupler (where ever required) extruded profiles having minimum wall thickness of 1.70 mm for Series R1 and R2 profiles and 2.10 mm for Series R3 and R4 profiles conforming to EN: 12608 in any shape, colour and design duly reinforced with galvanized mild steel section made of required shape & size as per CPWD Specification	0.72	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
	9.147.A1.1	Using R2 series with frame (40mm & above) x (40mm & above) & sash (25mm & above) x (50mm & above) with zinc alloy (zamak) powder coated touch locks with hook (Height upto 1.2 meter)				
3	9.7	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick :	0.72	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
	a) 9.7.7	Float glass panes				

	9.7.7.2	5.0 mm thick glass panes (weight not less than 12.50 kg/sqm).				
	b) 9.7.8	Fly proof stainless steel grade 304 wire gauge with 0.5 mm dia. wire and 1.4mm wide aperture with matching wood beading	0.72	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
4	21.8	Filling the gap in between aluminium frame & adjacent RCC/ Brick/ Stone work by providing weather silicon sealant over backer rod of approved quality as per architectural drawings and direction of Engineer-in-charge complete.	5.00	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
	21.8.1	Upto 5mm depth and 5 mm width				
5	14.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-harge.	10.00	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
	14.1.1	With cement mortar 1:4 (1 cement : 4 fine sand).				
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ **Net Amount** _____ **Net Amount in words**_____				

Signature of the Contractor

Sd/-
Executive Engineer A/C

Terms & Conditions:

1. The work should be completed within _____ from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any officer superior to him in authority.
4. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
5. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
6. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
7. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
8. TDS (1% or 2%) Labour welfare cess (1%) will be levied wherever applicable.
9. Value of work is inclusive of GST at applicable rate.
10. The GST invoice form should be filled and submitted along with the bill.

Sd/-
Executive Engineer

CC to:
1. A.E. Sub-Division (Civil-I)
2. Office Copy