UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 31.07.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **04.08.2025 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 04.08.2025 upto 12.00 PM

Opening of Quotations:- 04.08.2025 at 3.00 PM

S.No	Name of the work	Estimated Cost
1	Maintenance of buildings: Replacement of water lines in in TG-03 at in Ladies Hostel - IV in UoH campus	Rs. 49,600/-

Sd/-
Executive Engineer A/C

Name of work :- Maintenance of Buildings- "Replacement of water lines in TG-03 at Ladies Hostel-IV" in UoH Campus.						
1) The estimate amount is inclusive of GST. **2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**						
SCHEDULE OF QUANTITIES						
S. No	**D.S.R.No.**	**Description of item**	**Qty**	**Unit**	**Rate in figures & Rate in words**	**Amount**
1	18.9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.	50.00	Rmt	Figures: Rs_____ Words: Rupees_____ _____	
	a) 18.9.3	25mm nominal outer dia Pipes				
	18.9.5	40 mm nominal outer dia Pipes	33.60	Rmt	Figures: Rs_____ Words: Rupees_____ _____	
2	18.6A	Providing and fixing PPR Union	3.00	Each	Figures: Rs_____ Words: Rupees_____ _____	
	18.6A.4	PPR Union 40 mm				
3	18.18	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete :	3.00	Each	Figures: Rs_____ Words: Rupees_____ _____	
	18.18.3	25 mm nominal bore				
4	18.76	Cutting holes up to 30x30 cm in walls including making good the same:	12.00	Each	Figures: Rs_____ Words: Rupees_____ _____	

	18.76.1	With common burnt clay F.P.S. (non modular) bricks.				
5	15.7	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.	0.36	Cum	Figures: Rs_____ Words: Rupees_____ _____	
	15.7.4	In cement mortar				
6	6.4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :	0.36	Cum	Figures: Rs_____ Words: Rupees_____ _____	
	6.4.2	Cement mortar 1:6 (1 cement : 6 coarse sand)				
7	13.12	18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement: 5 coarse sand) and a top layer 6 mm thick cement plaster 1:3 (1 cement : 3 coarse sand) finished rough with sponge.	4.05	Sqm	Figures: Rs_____ Words: Rupees_____ _____	
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ **Net Amount** _____ **Net Amount in words**_____				

Sd/-

Signature of the Contractor **Executive Engineer A/C**

Terms & Conditions:

1. The work should be completed within _____ from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to **deduct 10% of the value of the work billed for towards Security Deposit.** The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. From time to time.
8. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
9. Defect liability period **Six (06) Months** from the date of completion of the work.
10. TDS (1% or 2%) Labour welfare cess (1%) will be levied wherever applicable.
11. Value of work is inclusive of GST at applicable rate.
12. The GST invoice form should be filled and submitted along with the bill.

Sd/-
Executive Engineer (A/C)

CC to:
1. A.E. Sub-Division (Civil-I)
2. Office Copy