UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 04.08.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **07.08.2025 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 07.08.2025 upto 12.00 PM

Opening of Quotations:- 07.08.2025 at 12.00 PM

S.No	Name of the work	Estimated Cost
1	Maintenance of buildings: Filling up the cavities with 1:2:4 Near Garden Area at School of Computer & Information Sciences in UoH campus	Rs. 44,600/-

Sd/-
Executive Engineer A/C

Name of work:- Maintenance of Buildings - Filling up of the Cavities with 1:2:4 at school of computer And Information sciences in UOH Campus						
1) The estimate amount is inclusive of GST. **2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**						
SCHEDULE OF QUANTITIES						
S. No	**D.S.R.No.**	**Description of item**	**Qty**	**Unit**	**Rate in figures & Rate in words**	**Amount**
1	1/15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	29.00	Sqm	Figure: Rs_____ Words: Rupees_____	
2	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	4.1.4	1:2:4 (1 Cement : 2 coarse sand(zone-III) derived from natural sources : 4 graded stone aggregate 40 mm nominal size derived from natural sources).	3.60	Cum	Figure: Rs_____ Words: Rupees_____	
3	13.7	12 mm cement plaster finished with a floating coat of neat cement of mix :	29.00	Sqm	Figure: Rs_____ Words: Rupees_____	
	13.7.1	1:3 (1 cement: 3 fine sand)				
4	4/13.111	Finishing walls with Acrylic Smooth exterior paint of required shade :				
	13.111.1	Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	29.00	Sqm	Figure: Rs_____ Words: Rupees_____	
					Total Amount in figures Rs	

Less Rebate Offered if any_____

Net Amount _____

Net Amount in words_____

Sd/-

Signature of the Contractor **Executive Engineer**

Terms & Conditions:

1. The work should be completed within _____ from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non- rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. From time to time.
8. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
9. Defect liability period Six (06) Months from the date of completion of the work.
10. TDS (1% or 2%) Labour welfare cess (1%) will be levied wherever applicable.
11. Value of work is inclusive of GST at applicable rate.
12. The GST invoice form should be filled and submitted along with the bill.

Sd/-
Executive Engineer (A/C)

CC to:
1. A.E. Sub-Division (Civil-II)
2. Office Copy