UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 07.08.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on 14**.08.2025 at 3.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 14.08.2025 upto 03.00 PM

Opening of Quotations:- 14.08.2025 at 03.00 PM

S.No	Name of the work	Estimated Cost
1	Maintenance of buildings: Applying painting for Rooms 204, 212, 230, 240, 251 & 252 at H Hostel in UoH campus	Rs. 49,999/-

Sd/-
Executive Engineer A/C

Name of work :- **Maintenance of Buildings- "** Maintenance of buildings: Applying painting for Rooms 204, 212, 230, 240, 251 & 252 at H Hostel in UoH campus **" in UoH Campus.**						
1) The estimate amount is inclusive of GST. **2) Comparative statement for Quoted rates shall be based on rates inclusive of14.1 GST.**						
SCHEDULE OF QUANTITIES						
S. No	**D.S.R.No.**	**Description of item**	**Qty**	**Unit**	**Rate in figures & Rate in words**	**Amount**
1	13.81	Distempering with 1st quality acrylic distemper (ready mixed) having VOC (Volatile Organic Compound) content less than 50 gram/ litre, of approved brand and of required shade and colour complete to give and even shade.	86.40	Sqm	Rs_____ Rupees_____ _____	
	13.81.1	Old work (one or more coats)				
2	13.82	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.	287.01	Sqm	Rs_____ Rupees_____ _____	
	13.82.2	Two coats.				
3	13.85	With ready mixed pink or grey primer on wood work (hard and soft wood) having VOC content less than 50 grams/ litre.	28.50	Sqm	Rs_____ Rupees_____ _____	
	13.85.3	With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre.				
4	13.88	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including	28.50	Sqm	Rs_____ Rupees_____ _____	

		necessary repairs to scratches etc. complete				
5	13.99.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work.	37.44	Sqm	Rs_____ Rupees_____ _____	
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ Rupees in Words_____				

Sd/-

Signature of the Contractor **Executive Engineer A/C**

Terms & Conditions:

1. The work should be completed within _____ from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non- rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. From time to time.
8. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
9. Defect liability period Six (06) Months from the date of completion of the work.
10. TDS (1% or 2%) Labour welfare cess (1%) will be levied wherever applicable.
11. Value of work is inclusive of GST at applicable rate.
12. The GST invoice form should be filled and submitted along with the bill.

Sd/-
Executive Engineer (A/C)

CC to:
1. A.E. Sub-Division (Civil-II)
2. Office Copy