UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 07.08.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **14.08.2025 at 3.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 14.08.2025 upto 03.00 PM

Opening of Quotations:- 14.08.2025 at 03.00 PM

S.No	Name of the work	Estimated Cost
1	Maintenance of buildings: Applying of painting & minor repairs GB Singh Maidan for Independence in UoH campus	Rs. 49,762/-

Sd/-
Executive Engineer A/C

Name of work :- Maintenance of Buildings- "Applying of painting & minor repairs GB Singh maidan for Independence Day" in UoH Campus.

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of14.1 GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	14.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-harge.	20.00	Sqm	Rs_____ Rupees_____ _____	
	14.1.1	With cement mortar 1:4 (1 cement : 4 fine sand).				
2	13.112	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade :	86.48	Sqm	Rs_____ Rupees_____ _____	
	13.112.2	Old work (Two or more coats applied @ 1.43 ltr/ 10 sqm) over existing cement paint surface.				
3	13.61	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:	36.00	Sqm	Rs_____ Rupees_____ _____	
	13.61.1	Two or more coats on new work				
4	13.69	Polishing on wood work with ready mixed wax polish of approved brand and manufacture:	25.00	Sqm	Rs_____ Rupees_____ _____	
	13.69.1	New work				

5	16.42	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete.	1.00	Cum	Rs_____ Rupees_____ _____	
6	2.25A	Excavating, supplying and filling of local earth (including royalty) by mechanical transport up to a lead of 5 km, also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc., complete.	18.00	Cum	Rs_____ Rupees_____ _____	
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ **Rupees in Words_____**				

Signature of the Contractor

Sd/-
Executive Engineer A/C

Terms & Conditions:

1. The work should be completed within _____ from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non- rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. From time to time.
8. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
9. Defect liability period Six (06) Months from the date of completion of the work.
10. TDS (1% or 2%) Labour welfare cess (1%) will be levied wherever applicable.
11. Value of work is inclusive of GST at applicable rate.
12. The GST invoice form should be filled and submitted along with the bill.

Sd/-
Executive Engineer (A/C)

CC to:
1. A.E. Sub-Division (Civil-I)
2. Office Copy