UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 20.08.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on 26**.08.2025 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 26.08.2025 upto 12.00 PM

Opening of Quotations:- 26.08.2025 at 12.00 PM

S.No	Name of the work	Estimated Cost
1	Maintenance of buildings: " Replacement of Flush tanks in TG-03,TG-02,T1-03&T1-02 at Ladies Hostel –IV" in UoH Campus	Rs. 49,500/-

Sd/-

Executive Engineer A/C

Name of work :- Maintenanace of Buildings- "Replacement of flush tank in TG-03,TG-02,T1-03&T1-02 at Ladies Hostel-IV" in UoH Campus.						
1) The estimate amount is inclusive of GST. **2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**						
SCHEDULE OF QUANTITIES						
S. No	**D.S.R.No.**	**Description of item**	**Qty**	**Unit**	**Rate in figures & Rate in words**	**Amount**
1	17.2	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :			Rs_____ Rupees_____ _____	
	17.2.1	W.C. pan with ISI marked white solid plastic seat and lid	2.00	Each		
2	17.18	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete.	16.00	Each	Rs_____ Rupees_____ _____	
	17.18.1	10 litre capacity - White				
3	17.29	Providing and fixing 100 mm sand cast Iron grating for gully trap.	48.00	Each	Rs_____ Rupees_____ _____	
4	15.44	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by	108.00	Rmt	Rs_____ Rupees_____ _____	

		mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge :				
	15.44.1	15 mm to 40 mm nominal bore				
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ _____ **in words**_____				

Sd/-

Signature of the Contractor **Executive Engineer**

Terms & Conditions:

1. The work should be completed within _____ from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non- rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. From time to time.
8. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
9. Defect liability period Six (06) Months from the date of completion of the work.
10. TDS (1% or 2%) Labour welfare cess (1%) will be levied wherever applicable.
11. Value of work is inclusive of GST at applicable rate.
12. The GST invoice form should be filled and submitted along with the bill.

Sd/-
Executive Engineer (A/C)

CC to:
1. A.E. Sub-Division (Civil-I)
2. Office Copy