UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 20.08.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on __26**.08.2025 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- __26.08.2025 upto 12.00 PM

Opening of Quotations:- ___26.08.2025 at 12.00 PM

S.No	Name of the work	Estimated Cost
1	Maintenance of buildings: ”Providing and fixing of sanitory fitting in T.G-02&T.1-02 at Ladies Hostel-IV” in UoH campus	Rs. 49,100/-

Sd/-

Executive Engineer A/C

Name of work :- Maintenance of Buildings- "Providing and fixing of Sanitary fittings in T.G-02&T.1-02 at Ladies Hostel-IV" in UoH Campus.

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	18.53	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931	16.00	Each	Rs_____ Rupees_____ _____	
	a) 18.53.1	15mm nominal bore				
2	18.51	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms	12.00	Each	Rs_____ Rupees_____ _____	
	18.51.1	15 mm nominal bore				
3	18.21	Providing and fixing uplasticised PVC connection pipe with brass unions :	24.00	Each	Rs_____ Rupees_____ _____	
	a)18.21.2	45 cm length				

	18.21.2.2	20 mm nominal bore				
4	18.22	Providing and fixing C.P. brass shower rose with 15 or 20 mm inlet :	8.00	Each	Rs_____ Rupees_____ _____	
	18.22.2	150 mm diameter				
5	18.52	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931.	8.00	Each	Rs_____ Rupees_____ _____	
	18.52.1	15mm nominal bore.				
6	17.28	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.	8.00	Each	Rs_____ Rupees_____ _____	
	17.28.2	Flexible pipe				
	17.28.2.1	32 mm dia				
7	17.7	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brasspillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require :	4.00	Each	Rs_____ Rupees_____ _____	
	17.7.4	White Vitreous China Flat back wash basin size 550x400 mm with single 15 mm C.P. brass pillar tap				
8	15.52	Dismantling of flushing cistern of all types (C.I./PVC/Vitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	1.00	Each	Rs_____ Rupees_____ _____	
9	15.45	Dismantling C.I. pipes including excavation	7.50	Rmt	Rs_____	

		and refilling trenches after taking out the pipes, manually/ by mechanical means breaking lead caulked joints, melting of lead and making into blocks including stacking of pipes & lead at site within 50 metre lead as per direction of Engineer-in-charge:			Rupees_____ _____	
	15.45.1	Up to 150 mm diameter				
10	17.2	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required				
	17.2.1	W.C. pan with ISI marked white solid plastic seat and lid	1.00	Each	Rs_____ Rupees_____ _____	
11	17.60	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors :	1.00	Each	Rs_____ Rupees_____ _____	
	17.60.1	100 mm inlet and 100 mm outlet				
	17.60.1.1	Sand Cast Iron S&S as per IS:3889				
12	18.76	Cutting holes up to 30x30 cm in walls including making good the same:	5.00	Each	Rs_____ Rupees_____	

	18.76.1	With common burnt clay F.P.S. (non modular) bricks.			_____	
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ _____ **in words**_____				

Signature of the Contractor

Sd/-
Executive Engineer

Terms & Conditions:

1. The work should be completed within _____ from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non- rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. From time to time.
8. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
9. Defect liability period Six (06) Months from the date of completion of the work.
10. TDS (1% or 2%) Labour welfare cess (1%) will be levied wherever applicable.
11. Value of work is inclusive of GST at applicable rate.
12. The GST invoice form should be filled and submitted along with the bill.

Sd/-
Executive Engineer (A/C)

CC to:
1. A.E. Sub-Division (Civil-I)
2. Office Copy