UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 17.09.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **25.09.2025 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- **25.09.2025 upto 12.00 PM**

Opening of Quotations:- **25.09.2025 at 3.00 PM**

S.No	Name of the work	Estimated Cost
1	Maintenance of buildings: Providing and fixing of water storage tanks for Department of CALTS toilet blocks in Humanities Building in University of Hyderabad campus	Rs. 49,900/-

Sd/-
Executive Engineer A/C

Name of work: "Maintenance of Building: Replacement of CPVC water lines at LH-8" in UoH Campus.						
1) The estimate amount is inclusive of GST. **2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**						
SCHEDULE OF QUANTITIES						
S. No	**D.S.R.No.**	**Description of item**	**Qty**	**Unit**	**Rate in figures & Rate in words**	**Amount**
1	15.44	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge :	12.00	Rmt	Figure Rs_____ Words Rupees_____ _____	
	15.44.1	15 mm to 40 mm nominal bore				
2	18.7	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. : Internal work - Exposed on wall	21.00	Rmt	Figure Rs_____ Words upees_____ _____	
	18.7.2	20 mm nominal outer dia pipes				
	18.7.3	25 mm nominal outer dia pipes	12.00	Rmt	Figure Rs_____ Words Rupees_____ _____	

3	18.75	Providing and fixing PTMT extension nipple for water tank pipe, fittings of approved quality and colour.	4.00	Each	Figure Rs_____ Words Rupees_____ _____	
	18.75.3	25mm nominal bore. Weighing not less than 62 gms.				
4	18.54	Providing and fixing PTMT bib cock of approved quality and colour.	6.00	Each	Figure Rs_____ Words Rupees_____ _____	
	18.54.1	15mm nominal bore, 86 mm long. Weighing not less than 88 gms.				
5	15.23	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 meters lead.	1.50	Sqm	Figure Rs_____ Words Rupees_____ _____	
	15.23.1	For thickness of tiles 10 mm to 25 mm				
6	11.41	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08%and conforming to IS : 15622 , of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) jointing with grey cement slurry @ 3.3kg/sqm including grouting the joints with white cement and matching pigments etc., complete. The tiles must be cut with the zero chipping diamond cutter only. Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and	1.50	Sqm	Figure Rs_____ Words Rupees_____ _____	

		rubber mallet for placing the tiles gently and easily.				
	11.41A.1	Double charge vitrified tile polished finish of size				
	11.41A.1.3	Size of tile 600 X 1200 mm				
		Less Rebate Offered if any_____ **Net Amount _____** **Net Amount in words_____**				

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor

Sd/-
Executive Engineer A/C

Terms & Conditions:

1. The work should be completed within _____ from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any officer superior to him in authority.
4. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
5. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
6. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. From time to time.
7. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
8. TDS (1% or 2%) Labour welfare cess (1%) will be levied wherever applicable.
9. Value of work is inclusive of GST at applicable rate.
10. The GST invoice form should be filled and submitted along with the bill.

Sd/-

Executive Engineer (A/C)

CC to:

1. A.E. Sub-Division (Civil-I)
2. Office Copy