UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 06.10.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **13.10.2025 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 13.10.2025 upto 12.00 PM

Opening of Quotations:- 13.10.2025 at 3.00 PM

S.No	Name of the work	Estimated Cost
1	Maintenance of buildings: Replacement of CPVC water lines at D-47, Providing and fixing of wash basin and CC flooring in wash area in D-42, providing rainwater pipe in D-37 and D-38 and providing and fixing of doors in D-03 & D-41 Qtrs UoH campus	Rs. 47,960.95/-

Sd/-
Executive Engineer

Name of work: Maintenance of Building: -"Replacement of CPVC water lines at D-47, Providing and fixing of wash basin and CC flooring in wash area in D-42, providing rainwater pipe in D-37 and D-38 and providing and fixing of doors in D-03 & D-41 Qtrs**" in the UoH Campus.**						
1) The estimate amount is inclusive of GST. **2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**						
SCHEDULE OF QUANTITIES						
S. No	**D.S.R.No.**	**Description of item**	**Qty**	**Unit**	**Rate in figures & Rate in words**	**Amount**
1	9.21	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters:	3.57	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
	9.21.2	30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws.				
2	9.96	Providing and fixing aluminium sliding door bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with nuts and screws etc. complete :	4.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
	9.96.1	300x16 mm.				
3	9.97.4	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :	2.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
	9.97.4	150x10 mm.				

4	9.100	Providing and fixing aluminium handles ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :	4.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
	9.100.1	125 mm.				
5	13.85	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content.	9.64	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
	13.85.3	With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre.				
6	13.61.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :	9.64	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
		Old work (one or more coat)				
7	15.44	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge :	10.00	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
	15.44.1	15 mm to 40 mm nominal bore				
8	18.7	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. : Internal work - Exposed on wall	30.00	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
	18.7.2	20 mm nominal outer dia. Pipes.				

9	18.75	Providing and fixing PTMT extension nipple for water tank pipe, fittings of approved quality and colour.	3.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
	18.75.3	25mm nominal bore. Weighing not less than 62 gms.				
10	18.54	Providing and fixing PTMT bib cock of approved quality and colour.	5.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
	18.54.1	15mm nominal bore, 86 mm long. Weighing not less than 88 gms.				
11	18.79	Making hole up to 20x20 cm and embedding pipes up to 150 mm diameter in masonry and filling with cement concrete 1:3:6 (1 cement: 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) including disposal of malba.	2.00	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
12	12.41	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.	3.00	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
	12.41.2	110 mm diameter				
13	14.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-charge.	10.00	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
	14.1.1	With cement mortar 1:4 (1 cement : 4 fine sand)				

14	17.7	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
	17.7.1	White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps				
15	15.2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.	0.35	Cum	Figure: Rs_____ Words: Rupees_____ _____	
	15.2.2	Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)				
16	16.42	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete.	0.35	Cum	Figure: Rs_____ Words: Rupees_____ _____	
17	MR	Providing and fixing of WC flush tank with push button and flange plates, fixing accessories Make: Hindware	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
18	MR	Supplying and fixing of CP Health Faucet with all necessary fittings including fitting charges, all taxes etc. Make Hindware	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	

19	MR	Supplying and fixing of wall mixer with all necessary fittings including fitting charges, taxes etc. Make : Hindware	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
20	MR	Supplying and fixing of Angle Cock with all necessary fittings including fitting charges, all taxes etc. Make Hindware	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
21	MR	Supplying and fixing of Pillar Cock with all necessary fittings including fitting charges, all taxes etc. Make Hindware	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
					Total Amount	
		Less Rebate Offered if any_____ **Net Amount _____** **Net Amount in words_____**				

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor

Sd/-
Executive Engineer

Terms & Conditions:

1. The work should be completed within _____ from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to **deduct 10% of the value of the work billed for towards Security Deposit.** The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. From time to time.
8. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
9. Defect liability period **Six (06) Months** from the date of completion of the work.
10. TDS (1% or 2%) Labour welfare cess (1%) will be levied wherever applicable.
11. Value of work is inclusive of GST at applicable rate.
12. The GST invoice form should be filled and submitted along with the bill.

Sd/-
Executive Engineer

CC to:
1. A.E. Sub-Division (Civil-II)
2. Office Copy