UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Assistant Engineer

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 10.10.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **13.10.2025 at 12.00 P.M. in the Office of the University Works Department.** Hence, All the contractors are requested to remind the following details: -

Submission of Quotations by 13.10.2025 at 12.00 PM

Opening of Quotations: 13.10.2025 at 3.00 PM

S. No	Name of the work	Estimated Cost Rs.
1	Supply and laying of 4 x 16sq mm cable at A type Quarter (A-1) in University of Hyderabad Campus. – Reg.	**RS. 49,082 /-**

Assistant Engineer (E)

Name of Work: -Supply and laying of 4 x 16sq mm cable at A type Quarter (A-1) in University of Hyderabad Campus. – Reg.

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount	D.S.R./MR
1	Supply of 4 x 16 Sq mm armoured XPLE insulated Aluminium conductor cable of 1.1 KV grade grade conforming to IS 7098 (part-1) 1988 amended up to Date duly ISI marked etc as required. Make: Finolex/Polycab/Havells.	70	Mtr	Figure:Rs_____ Words:Rupees_____ _____		M.R
2	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground (75 cm below ground level) including excavation, sand cushioning, protective covering and refilling the trench etc as required.					7.2
2.1	Upto 35 sq. mm	65	Mtr	Figure:Rs_____ Words:Rupees_____ _____		7.2.1
3	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL / PVC coundut pipe as required.					7.5
3.1	Upto 35 sq. mm	3	Mtr	Figure:Rs_____ Words:Rupees_____ _____		7.5.1
4	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.					
4.1	32 mm	3	Mtr	Figure:Rs_____ Words:Rupees_____ _____		1.21.3
5	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.					9.1
5.1	4 x 16 sq. mm (28mm)	2	Each	Figure:Rs_____ Words:Rupees_____ _____		9.1.33

6	Supplying and fixing cable route marker with 10 cm X 10 cm X 5 mm thick G.I. plate with inscription there on, bolted /welded to 35 mm X 35 mm X 6 mm angle iron, 60 cm long and fixing the same in ground as required.	10	Each	Figure:Rs_____ Words:Rupees_____ _____		7.10
7	Supplying and fixing following rating, four pole, 415 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.					2.13
7.1	63 amps	1	Each	Figure:Rs_____ Words:Rupees_____ _____		2.13.2
8	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.					Civil DSR 2021 16.13
8.1	Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix) (0.3 X 7 X 0.3 = 0.63)	0.63	cum	Figure:Rs_____ Words:Rupees_____ _____		16.13.1
9	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :					4.1
9.1	1:4:8 (1 Cement : 4 manufactured sand derived from Recycled Concrete Aggregate (RCA) : 8 graded stone aggregate 40 mm nominal size Recycled Aggregate (RA)). (0.3 X 7 X 0.3 = 0.63)	0.63	cum	Figure:Rs_____ Words:Rupees_____ _____		4.1.8A
	GST @ 18%					
	Total					

Signature of the Contractor **Assistant Engineer**

Terms & Conditions:

1.The contractor/ bidder shall be a registered contractor and should produce definite proof of appropriate class registered by state or central government departments or state/central autonomous bodies or undertakings should submit proof thereof.

2. The work should be completed within Fifteen (15) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the

3. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.

4. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.

5. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.

6. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.

7. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.

8. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.

9. Defect liability period 6 (six) months from the date of completion of the work.

10. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.

11. A.E (E) has to enclose the work completion certificate and user department certificate along with the bill.

12. No quotation will be accepted without PAN/VAT no.

13. TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Assistant Engineer

CC to:

1. A.E. Sub-Division (E)
2. S O (Works & Bills),
3. O.C.,
4. D.B.,