UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Executive Engineer
University of Hyderabad
Central University P.O.
Hyderabad 500 046, Ph: 23132304

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 14.10.2025

The Opening of Quotations **(Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **17 .10.2025 at 12.00 P.M.** in the Office of the University Works Department. Hence, All the contractors are requested to remind the following details: -

Submission of Quotations: 17.10.2025 at 12.00 PM
Opening of Quotations: 17.10.2025 at 3.00 PM

S. No	Name of the work	Estimated Cost Rs.
1	**Maintenance of Building :- Re-construction of collapsed compound wall at LH-7 " in UoH Campus**	**Rs. 49,750 /-**

Sd/-
EXECUTIVE ENGINEER

Name of work: Maintenance of Building :- Re-construction of collapsed compound wall at LH-7 ” in UoH Campus.						
1) The estimate amount is inclusive of GST. **2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**						
SCHEDULE OF QUANTITIES						
S.No	**D.S.R.No.**	**Description of item**	**Qty**	**Unit**	**Rate in figures & Rate in words**	**Amount**
1	2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	2.10 Cum	Cum	Figure: Rs_____ Words: Rupees_____ _____	
2	4.1.10A	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 manufactured sand derived from Recycled Concrete Aggregate (RCA) : 10 graded stone aggregate 40 mm nominal size including Recycled Aggregate (RA))	0.30 Cum	Cum	Figure: Rs_____ Words: Rupees_____ _____	
3	7.1.1	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20mm nominal size) upto plinth level with : Cement mortar 1:6 (1 cement : 6 coarse sand).	1.58 Cum	Cum	Figure: Rs_____ Words: Rupees_____ _____	

4	6.4 .2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	2.07 Cum	Cum	Figure: Rs_____ Words: Rupees_____ _____	
5	13.9.2	Cement plaster 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement. 20 mm 20 mm cement plaster	25.20 Sqm	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
6	13.111.1	Finishing walls with Acrylic Smooth exterior paint of required shade : Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface).	32.40 Sqm	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
					Total Amount in figures Rs	

Less Rebate Offered if any_____
Net Amount _____
Net Amount in words_____

Sd/-

Signature of the Contractor **Executive Engineer**

Terms & Conditions:

1. The work should be completed within _____ from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period 6 (six) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/VAT no.
12. TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Sd/-
Executive Engineer

CC to:
1. Executive Engineer
2. A.E. Sub-Division ( )
3 File