UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 27.10.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below

is scheduled to be held on 31**.10.2025 at 12.00 PM** in the Office **of the University**

Works

Department. Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 31.10.2025 upto 12.00 PM

Opening of Quotations:- 31.10.2025 at 3.00 PM

S.No	Name of the work	Estimated Cost
1	Maintenance of Buildings: ”Replacement of doors in room no.238 Ladies Hostel-1,B-10 & B-37 Quarter “ in UoH campus	Rs. 49,350/-

Sd/-

Executive Engineer A/C

Name of work:-Maintenance of Buildings-"Replacement of Doors in Room No. 238, Ladies Hostel-I, B-10 & B-37 Quarter" in UoH Campus.

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S.No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	15.12	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :	4.00	Each	Rs_____ Rupees_____ _____	
	15.12.1	Of area 3 sq. metres and below				
2	26.86	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid door/ window/ Ceosetory windows & other Frames/ Chowkhat comprising of virgin PVC polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice husk/ wheat husk) and nontoxic additives (maximum toxicity index of 12 for 100gms) fabricated with miter joints after applying PVC solvent cement and screwed with full body threaded star headed SS screws having minimum frame density of 750 kg/cum, screw withdrawal strength of 2200 N (Face) & 1100 N (Edge), minimum compressive strength of 58 N/mm2, modulus of elasticity 900 N/mm2 and resistance to spread of flame of Class A category with property of being termite/ borer proof, water/ moisture proof and fire retardant and fixed in position with M.S hold fast/ lugs/ SS dash fasteners of required dia and length complete as per direction of Engineer-In- Charge. (M.S hold fast/ lugs or SS dash fasteners shall be paid for separately). Note: For WPC solid door/ window frames, minus 5mm				

		tolerance in dimensions i.e depth and width of profile shall be acceptable. Variationin profile dimensions on plus side shall be acceptable but no extra payment on this account shall be made. Make: Rajashree, Sintex, Duroplast.	5.10	Rmt	Rs_____ Rupees_____ _____	
	26.86.3	Frame size 50 x 100 mm				
3	26.87	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid plain flush door shutter of required size comprising of virgin polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice husk/ wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) having minimum density of 650 kg/cum and screw withdrawal strength of 1800 N (Face) & 900 N (Edge), minimum compressive strength 50 N/mm2, modulus of elasticity 850 N/mm2 and resistance to spread of flame of Class A category with property of being termite/borer proof, water/ moisture proof and fire retardant and fixing with stainless steel butt hinges of required size with necessary full body threaded star headed counter sunk S.S screws, all as per direction of Engineer-in-charge. (Note: stainless steel butt hinges and necessary S.S screws shall be paid separately). Make: Rajashree, Sintex, Duroplast.	1.89	Sqm	Rs_____ Rupees_____ _____	
	26.87.1	30 mm thick				
4	9.21	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: Make: Kitply, Century, Greenply, Archidply, Kutty.	6.30	Sqm	Rs_____ Rupees_____ _____	

	9.21.2	30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws.				
5	9.96	Providing and fixing aluminium sliding door bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with nuts and screws etc. complete : Make: Hardima/ Everite/ Sigma/ Jyothi.	8.00	Each	Rs_____ Rupees_____ _____	
	9.96.1	300x16 mm				
6	9.97	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete : Make: Hardima/ Everite/ Sigma/ Jyothi.	8.00	Each	Rs_____ Rupees_____ _____	
	9.97.4	150x10 mm				
7	9.100	Providing and fixing aluminium handles ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete : Make: Hardima/ Everite/ Sigma/ Jyothi.	8.00	Each	Rs_____ Rupees_____ _____	
	9.100.1	125 mm				
8	13.62	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade:	14.62	Sqm	Rs_____ Rupees_____ _____	
	13.62.1	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture. Make: ICI Dulux, Asian paints (Apcolite), Berger, Nerolac.				

9	14.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-charge.	20.00	Sqm	Rs_____ Rupees_____ _____	
	14.1.1	With cement mortar 1:4 (1 cement : 4 fine sand).				
10	13.41	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50gram/litre, of approved manufacturer, of required shade and colour complete to achieve even shade and colour: Make: ICI Dulux/ Asian paints (Apcolite)/ Berger/ Nerolac.	25.00	Sqm	Rs_____ Rupees_____ _____	
	13.41.1	New work (two or more coats) over and including water thinnable priming coat with cement primer having VOC content less than 50gram/litre.				
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ _____ **in words**_____				

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor

sd/-
Executive Engineer

Terms & Conditions:

1. The work should be completed within thirty (15) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/GST no.
12. GST(2%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

Sd/-
Executive Engineer

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,