UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 31.10.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on 06**.11.2025 at 12.00 PM** in the Office **of the University Works**

Department. Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 06 .11.2025 upto 12.00 PM

Opening of Quotations:- 06 .11.2025 at 3.00 PM

S.No	Name of the work	Estimated Cost
1	Maintenance of Buildings: ”Providing and fixing wash basin and CPVC water lines at school of chemistry“ in UoH campus	Rs. 37,485/-

Sd/-

Executive Engineer A/C

Name of work :- Maintenanace of Buildings- "Providing and fixing wash basin and CPVC water lines at School of Chemistry" in UoH Campus.

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	17.4	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brasspillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require :	1.00	Each	Rs_____ Rupees_____ _____	
	17.4.4	White Vitreous China Flat back wash basin size 550x400 mm with single 15 mm C.P. brass pillar tap				
2	5.13	Providing, hoisting and fixing up to floor five level precast reinforced cement concrete in small lintels not exceeding 1.5m clear span up to floor five level, including the cost of required centering, shuttering but , excluding the cost of reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand(zone III) : 3 graded stone aggregate 20 mm nominal size).	0.56	Cum	Rs_____ Rupees_____ _____	
3	5.22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.				

	5.22.6	Thermo-Mechanically Treated bars	70.00	Kg	Rs_____ Rupees_____ _____	
4	18.9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.	50.00	Rmt	Rs_____ Rupees_____ _____	
	18.9.1	15 mm nominal outer dia. Pipes.				
5	18.49	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 :	2.00	Each	Rs_____ Rupees_____ _____	
	18.49.1	15 mm nominal bore				
6	18.21	Providing and fixing uplasticised PVC connection pipe with brass unions :	2.00	Each	Rs_____ Rupees_____ _____	
	a)18.21.2	45 cm length				
	18.21.2.2	20 mm nominal bore				
7	17.28	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.	2.00	Each	Rs_____ Rupees_____ _____	
a)	17.28.2	Flexible pipe				
	17.28.2.1	32 mm dia				
8	18.56	Providing and fixing PTMT pillar cock of approved quality and colour.				

	18.56.2	15 mm nominal bore, 125 mm long foam flow, weighing not less than 120 gm	2.00	Each	Rs_____ Rupees_____ _____	
9	12.41	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.	12.00	Rmt	Rs_____ Rupees_____ _____	
	12.41.2	110 mm diameter				
10	12.42	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion.	4.00	Each	Rs_____ Rupees_____ _____	
	a)12.42.3	Single tee with door				
	12.42.3.2	110x110x110 mm				
	b)12.42.5	Bend 87.5°	4.00	Each	Rs_____ Rupees_____ _____	
	12.42.5.2	110 mm bend				
11	18.76	Cutting holes up to 30x30 cm in walls including making good the same:	2.00	Each	Rs_____ Rupees_____ _____	
	18.76.1	With common burnt clay F.P.S. (non modular) bricks.				
					Total Amount in figures Rs	

		Less Rebate Offered if any_____ _____ **in words**_____
1) The estimate amount is inclusive of GST. **2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**		
Signature of the Contractor		**sd/-** **ExecutiveEngineer**

Terms & Conditions:

1. The work should be completed within thirty (15) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/GST no.
12. GST(2%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

Sd/-
Executive Engineer

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,