UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Executive Engineer
University of Hyderabad
Central University P.O.
Hyderabad 500 046, Ph: 23132304

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 01.11.2025

The Opening of Quotations **(Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **06.11.2025 at 12.00 P.M.** in the Office of the University Works Department. Hence, All the contractors are requested to remind the following details: -

Submission of Quotations: 06.11.2025 at 12.00 PM
Opening of Quotations: 06.11.2025 at 3.00 PM

S. No	Name of the work	Estimated Cost Rs.
1	**Maintenance of Building: - "Applying of Internal painting and providing and fixing of cupboard shutters in TF-35 Qtrs" in the UoH Campus.**	**Rs. 31,507 /-**

Sd/-
EXECUTIVE ENGINEER

Name of work :- Maintenance of Buildings- "Applying of internal painting and providing and fixing of cupboard shutters in TF-35 quarters " in UoH Campus.

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	13.82	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.			Figure: Rs_____ Words: Rupees_____ _____	
	13.82.1	One coat.	137.51	Sqm		
2	13.85	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content.				
	13.85.3	With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre.	13.75	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
3	13.88	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	13.75	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
4	13.99	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :			Figure: Rs_____ Words: Rupees_____	
	13.99.1	One or more coats on old work.	14.12	Sqm	_____	

5	9.159	Providing and fixing 25mm thick pre-laminated medium density fibre board exterior grade (Grade-I) IS:14587:1998 marked with one side decorative and other side balancing lamination for cupboard shutters edges to be sealed with PVC edge bending tape 2.00 mm thick of approved brand including ISI marked nickel plated bright finishing M.S. piano hinges conforming to IS:3818 marked with necessary screw etc all complete.	7.56	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
6	9.114	Providing and fixing magnetic catcher of approved quality in cupboard / ward robe shutters, including fixing with necessary screws etc. complete.			Figure: Rs_____ Words: Rupees_____ _____	
	9.114.2	Double strip (horizontal type)	8.00	Each		
7	9.100	Providing and fixing aluminium handles ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :			Figure: Rs_____ Words: Rupees_____ _____	
	9.1001	125 mm	8.00	Each		
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ **Net Amount _____** **Net Amount in words_____**				

Sd/-

Signature of the Contractor **Executive Engineer**

Terms & Conditions:

1. The work should be completed within _____ from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period 6 (six) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/VAT no.
12. TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Sd/-
Executive Engineer

CC to:
1. A.E. Sub-Division ( )
3 File