UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

**NOTE**

Ref: UH/ENGG/UE/2025-26/ Date: 12.11.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **17.11.2025 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

**Submission of Quotations:- 17.11.2025 upto 12.00 PM**

**Opening of Quotations:- 17.11.2025 at 3.00 PM ***

| S.No | Name of the work | Estimated Cost |
|---|---|---|
| 1 | Maintenance of buildings: "Providing water cooler platform at Ladies Hostel-IV entrances'' UoH campus | Rs. 49,200/- |

Sd/-

Executive Engineer A/C

# Name of work :- Maintenanace of Buildings- "Providing Water Cooler platform at Ladies Hostel-IV entrances" in UoH Campus.

**1) The estimate amount is inclusive of GST.**
**2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**

## SCHEDULE OF QUANTITIES

| S. No | D.S.R.No. | Description of item | Qty | Unit | Rate in figures & Rate in words | Amount |
|---|---|---|---|---|---|---|
| 1 | 15.2 | Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. | 0.75 | Cum | Rs_____ Rupees_____ _____ | |
| | 15.2.1 | Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) | | | | |
| 2 | 4.1 | Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : | 0.40 | Cum | Rs_____ Rupees_____ _____ | |
| | a)4.1.3 | 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) | | | | |
| | b)4.1.8 | 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources). | 0.60 | Cum | Rs_____ Rupees_____ _____ | |
| 3 | 6.4 | Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : | 1.55 | Cum | Rs_____ Rupees_____ _____ | |
| | 6.4.2 | Cement mortar 1:6 (1 cement : 6 coarse sand) | | | | |

| | | | | | | |
|---|---|---|---|---|---|---|
| 4 | 13.12 | 18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement: 5 coarse sand) and a top layer 6 mm thick cement plaster 1:3 (1 cement : 3 coarse sand) finished rough with sponge. | 9.75 | Sqm | Rs_____<br>Rupees_____<br>_____ | |
| 5 | 13.18 | Neat cement punning | 9.75 | Sqm | Rs_____<br>Rupees_____<br>_____ | |
| 6 | 17.60 | Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors : | 1.00 | Each | Rs_____<br>Rupees_____<br>_____ | |
| | a)17.60.1 | 100 mm inlet and 100 mm outlet | | | | |
| | 17.60.1.2 | Sand Cast Iron S&S as per IS: 1729 | | | | |
| 7 | 19.4 | Providing and fixing square-mouth S.W. gully trap class SP-1 complete with C.I. grating brick masonry chamber with water tight C.I. cover with frame of 300 x 300 mm size (inside) the weight of cover to be not less than 4.50 kg and frame to be not less than 2.70 kg as per standard design : | 1.00 | Each | Rs_____<br>Rupees_____<br>_____ | |
| | a)19.4.3 | 180x150 mm size P type | | | | |
| | 19.4.3.1 | With best locally available bricks | | | | |
| 8 | 12.41 | Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. | 5.00 | Rmt | Rs_____<br>Rupees_____<br>_____ | |
| | 12.41.2 | 110 mm diameter | | | | |

| | | | | | | |
|---|---|---|---|---|---|---|
| 9 | 12.42 | Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. | 2.00 | Each | Rs_____<br>Rupees_____<br>_____ | |
| | a)12.42.3 | Single tee with door | | | | |
| | 12.42.3.2 | 110x110x110 mm | | | | |
| | b)12.42.5 | Bend 87.5° | 2.00 | Each | Rs_____<br>Rupees_____<br>_____ | |
| | 12.42.5.2 | 110 mm bend | | | | |
| 10 | 18.7 | Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. : Internal work - Exposed on wall | 25.00 | Rmt | Rs_____<br>Rupees_____<br>_____ | |
| | a)18.7.4 | 32 mm nominal outer dia Pipes | | | | |
| 11 | 18.76 | Cutting holes up to 30x30 cm in walls including making good the same: | 3.00 | Each | Rs_____<br>Rupees_____<br>_____ | |
| | 18.76.1 | With common burnt clay F.P.S. (non modular) bricks. | | | | |
| | | | | | **Total Amount in figures Rs** | |

| | | |
|---|---|---|
| | | **Less Rebate Offered if any**_____<br>_____<br>**in words**_____ |

**1) The estimate amount is inclusive of GST.**
**2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**

**Signature of the Contractor**

**sd/-**
**ExecutiveEngineer**

**Terms & Conditions**:

1. The work should be completed within thirty (14) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C- ) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/GST no.
12. GST(2%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

**Sd/-**
**Executive Engineer**

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C- )
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,