UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

**NOTE**

Ref: UH/ENGG/UE/2025-26/ Date: 13.11.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **17.11.2025 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

**Submission of Quotations:- 17.11.2025 upto 12.00 PM**
**Opening of Quotations:- 17.11 .2025 at 3.00 PM**

| S.No | Name of the work | Estimated Cost |
|---|---|---|
| 1 | Maintenance of Buildings: - **Maintenance of Building:- Applying internal painting and CC flooring at D-23 Qtr" in UoH Campus.** | Rs. 15,137/- |

Sd/-
Executive Engineer A/C

**Name of work: Maintenance of Building:- Applying internal painting and CC flooring at D-23 Qtr" in UoH Campus.**

**11) The estimate amount is inclusive of GST.**
**2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**

**SCHEDULE OF QUANTITIES**

| S.No | D.S.R.No. | Description of item | Qty | Unit | Rate in figures & Rate in words | Amount |
|---|---|---|---|---|---|---|
| 1 | 13.82 | Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. | 220.00 | Sqm | Figure: Rs_____<br>Words: Rupees_____<br>_____ | |
| | 13.82.2 | two coat | | | | |
| 2 | 13.99 | Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: | 50.00 | Sqm | Figure: Rs_____<br>Words: Rupees_____<br>_____ | |
| | 13.99.1 | One or more coats on old work | | | | |
| 3 | 4.1 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : | | | | |
| | 4.1.3 | 1:2:4 (1 cement : 2 coarse sand(zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources) | 1.35 | Cum | Figure: Rs_____<br>Words: Rupees_____<br>_____ | |
| | | | | | **Total Amount in figures Rs.** | |

**Signature of the Contractor**

**Sd/-**
**Executive Engineer**

**Terms & Conditions**:

1. The work should be completed within _____ from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
5. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
6. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
7. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
8. A.E (C- ) has to enclose the work completion certificate and user department certificate along with the bill.
9. No quotation will be accepted without PAN/GST no.
10 . WCT (5%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

**Sd/-**
**Executive Engineer**

CC to:

1. A.E. Sub-Division (C- )
2. O.C.