UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 26.11.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on 03.12**.2025 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 03.12**.2025 upto 12.00 PM**
Opening of Quotations:- 03.12**.2025 at 3.00 PM**

S.No	Name of the work	Estimated Cost
1	Maintenance of Buildings: - Providing and laying of CC flooring and MS mesh in SLS canteen at School of Life Sciences in UoH campus	Rs. 49,858/-

Sd/-
Executive Engineer

Name of work:- **Maintenance of Buildings: - Providing and laying of CC flooring and MS mesh in SLS Canteen at School of Life Sciences in UoH campus**

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S.No	D.S.R.No	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	11.3.1	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete.	22.37	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
		40 mm thick with 20 mm nominal size stone aggregate				
2	9.51	Providing and fixing fly proof galvanized M.S. wire gauge to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm all complete.	27.00	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
	9.51.2	With 12 mm mild U beading				
3	9.130	Providing and fixing cup board shutters with 25mm thick veneered particle board IS : 3097 marked exterior grade (Grade I) of approved make including IInd class teak wood lipping of 25mm wide x 12 mm thick with necessary screws and bright finished stainless steel piano hinges complete as per direction of Engineer-in-Charge.	6.30	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
	9.130.1	With decorative veneering on one side and commercial veneering on other side.				
					Total Amount in figures Rs	

Less Rebate Offered if any_____
Net Amount _____
Net Amount in words_____

Signature of the Contractor

Sd/-
Executive Engineer

Terms & Conditions:

1. The work should be completed within _____ from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to **deduct 10% of the value of the work billed for towards Security Deposit.** The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. From time to time.
8. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
9. Defect liability period **Six (06) Months** from the date of completion of the work.
10. TDS (1% or 2%) Labour welfare cess (1%) will be levied wherever applicable.
11. Value of work is inclusive of GST at applicable rate.
12. The GST invoice form should be filled and submitted along with the bill.

Sd/-
Executive Engineer

CC to:

1. A.E. Sub-Division (C-)
2. O.C.