UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 26.11.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on 03.12**.2025 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 03.12**.2025 upto 12.00 PM**
Opening of Quotations:- 03.12**.2025 at 3.00 PM**

S.No	Name of the work	Estimated Cost
1	Maintenance of Buildings: - Providing and fixing WPC wash room doors at C-12 & D-45 Qtr, providing and fixing of ISI marked flush door shutters at E-35 Qtr and providing and fixing of EWC in First Floor toilet T1-07at CIS in UoH campus	Rs. 27,059/-

Sd/-
Executive Engineer

Name of work:- **Maintenance of Buildings: - Providing and fixing WPC wash room doors at C-12 & D-45 Qtr, providing and fixing of ISI marked flush door shutters at E-35 Qtr and providing and fixing of EWC in First Floor toilet T1-07at CIS in UoH campus**

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S.No	D.S.R.No	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :	5.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
		All kinds of soil.				
2	9.21	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters:	1.89	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
	9.21.2	30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws				
3	9.96	Providing and fixing aluminium sliding door bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with nuts and screws etc. complete :	5.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
	9.96.1	300x16 mm				
4	9.97	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :	5.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
	9.97.4	150x10 mm				

5	9.100	Providing and fixing aluminium handles ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :	10.00	Each	Figure: Rs_____ Words: Rupees_____ _____.	
	9.100.1	125 mm				
6	26.87	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid plain flush door shutter of required size comprising of virgin polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice husk/ wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) having minimum density of 650 kg/cum and screw withdrawal strength of 1800 N (Face) & 900 N (Edge), minimum compressive strength 50 N/mm2, modulus of elasticity 850 N/mm2 and resistance to spread of flame of Class A category with property of being termite/borer proof, water/ moisture proof and fire retardant and fixing with stainless steel butt hinges of required size with necessary full body threaded star headed counter sunk S.S screws, all as per direction of Engineer-In- Charge. (Note: stainless steel butt hinges and necessary S.S screws shall be paid separately)	2.60	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
	26.87.1	30 mm thick				
7	14.82	Dismantling W.C. Pan of all sizes including disposal of dismantled materials i/c malba all complete as per directions of Engineer-in-Charge.	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
8	17.2	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever),	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	

		conforming to IS : 7231, with all fittings andfixtures complete, including cutting and making good the walls and floors wherever required :				
	17.2.1	W.C. pan with ISI marked white solid plastic seat and lid				
9	MR	Providing and fixing of CP Health faucet Make: CERA	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
					Total Amount in figures Rs	

Less Rebate Offered if any_____
Net Amount _____
Net Amount in words_____

Signature of the Contractor

Sd/-
Executive Engineer

Terms & Conditions:

1. The work should be completed within _____ from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to **deduct 10% of the value of the work billed for towards Security Deposit.** The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. From time to time.
8. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
9. Defect liability period **Six (06) Months** from the date of completion of the work.
10. TDS (1% or 2%) Labour welfare cess (1%) will be levied wherever applicable.
11. Value of work is inclusive of GST at applicable rate.
12. The GST invoice form should be filled and submitted along with the bill.

Sd/-
Executive Engineer

CC to:

1. A.E. Sub-Division (C-)
2. O.C.