UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2026-27/ .01.2026

Date: 02.01.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **09.01.2026 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations - 09.01.2026 up to 12.00 PM

Opening of Quotations - 09.01.2026 at 3.00 PM

S. No	Name of the work	Estimated Cost
1	Maintenance of Buildings'' Replacement of EWC in second floor washroom no (T.2-02) AT men's hostel-E annex, providing cupboard shutters with frames in Room No-113 at LH-IV' in UoH campus	Rs. 36,573/-

Sd/-
Executive Engineer

Name of work :- Maintenanace of Buildings- "Replacement of EWC in Second floor Washroom no (T.2-02) at Men's Hostel-E Annex, Providing Cupboard shutters with frames in Room No-113 at LH-IV" in UoH Campus.

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	17.2	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :	1.00	Each	Rs_____ Rupees_____	
	17.2.1	W.C. pan with ISI marked white solid plastic seat and lid				
2	17.60	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors :	1.00	Each	Rs_____ Rupees_____ _____	
	a)17.60.1	100 mm inlet and 100 mm outlet				
	17.60.1.2	Sand Cast Iron S&S as per IS: 1729				

3	18.53	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931	1.00	Each	Rs_____ Rupees_____ _____	
	18.53.1	15mm nominal bore				
4	18.58	Providing and fixing PTMT grating of approved quality and colour.	1.00	Each	Rs_____ Rupees_____ _____	
	18.58.1	Circular type.				
	18.58.1.2	125 mm nominal dia with 25 mm waste hole.				
5	18.49	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 :	2.00	Each	Rs_____ Rupees_____ _____	
	18.49.1	15 mm nominal bore				
6	19.21	Making connection of drain or sewer line with existing manhole including breaking into and making good the walls, floors with cement concrete 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) cement plastered on both sides with cement mortar 1:3 (1 cement : 3 coarse sand), finished with a floating coat of neat cement and making necessary channels for the drain etc. complete :	1.00	Each	Rs_____ Rupees_____ _____	
	19.21.1	For pipes 100 to 250 mm diameter				
7	9.1	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia &	0.08	Cum	Rs_____ Rupees_____ _____	

		length (hold fast lugs or dash fastener shall be paid for separately).				
	9.1.1	Second class teak wood				
8	9.159	Providing and fixing 25mm thick pre-laminated medium density fibre board exterior grade (Grade-I) IS:14587:1998 marked with one side decorative and other side balancing lamination for cupboard shutters edges to be sealed with PVC edge bending tape 2.00 mm thick of approved brand including ISI marked nickel plated bright finishing M.S. piano hinges conforming to IS:3818 marked with necessary screw etc all complete.	4.20	Sqm	Rs_____ Rupees_____ _____	
9	9.97	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :	4.00	Each	Rs_____ Rupees_____ _____	
	9.97.4	150x10 mm				
10	9.100	Providing and fixing aluminium handles ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :	4.00	Each	Rs_____ Rupees_____ _____	
	9.100.1	125 mm				
11	9.76	Providing and fixing bright finished brass 100 mm mortice latch and lock	4.00	Each	Rs_____ Rupees_____	

		with 6 levers and a pair of lever handles of approved quality with necessary screws etc. complete.			_____	
12	MR	Supply and fixing of C.P. Two in One tap of 15 mm dia. (Make: Jaquer / Seiko)	1.00	Each	Rs_____ Rupees_____ _____	
13	MR	Supply and fixing of C.P. Health Faucet of 15 mm dia. (Make: Jaquer / Plumber)	1.00	Each	Rs_____ Rupees_____ _____	
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ **_____** **in words_____**				

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor

sd/-
Executive Engineer

Terms & Conditions:

1. The work should be completed within (14) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. No quotation will be accepted without PAN/GST no.
11. GST (2%)/TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Sd/-
Executive Engineer

CC to:

1. A.E. Sub-Division (C-)
2. O.C.