0UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

**NOTE**

Ref: UH/ENGG/UE/2026-27/ .01.2026

Date: 06.01.2026

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **13.01.2026 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

**Submission of Quotations - 13.01.2026 up to 12.00 PM**

**Opening of Quotations - 13.01.2026 at 3.00 PM**

| S. No | Name of the work | Estimated Cost |
|---|---|---|
| 1 | Maintenance of Buildings'' Providing internal painting to faculty rooms in department of communication at S.N. School'' in UoH campus | Rs. 49,600 /- |

Sd/-
Executive Engineer

# Name of work :- Maintenanace of Buildings- "Providing internal painting to Faculty rooms in Department of Communication at S.N School " in UoH Campus.

**1) The estimate amount is inclusive of GST.**

**2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**

## SCHEDULE OF QUANTITIES

| S. No | D.S.R.No. | Description of item | Qty | Unit | Rate in figures & Rate in words | Amount |
|---|---|---|---|---|---|---|
| 1 | 13.81 | Distempering with 1st quality acrylic distemper (ready mixed) having VOC (Volatile Organic Compound) content less than 50 gram/ litre, of approved brand and of required shade and colour complete to give and even shade. | 542.00 | Sqm | Rs_____<br>Rupees_____<br>_____ | |
| | 13.81.1 | Old work (one or more coats) | | | | |
| 2 | 13.88 | Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. Complete | 243.90 | Sqm | Rs_____<br>Rupees_____<br>_____ | |

| | | | | | | |
|---|---|---|---|---|---|---|
| 3 | 13.99 | Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : | 118.00 | Sqm | Rs_____<br>Rupees_____<br>_____ | |
| | 13.99.1 | One or more coats on old work | | | | |
| | | | | | **Total Amount in figures Rs** | |
| | | **Less Rebate Offered if any**_____<br>_____<br>**in words**_____ | | | | |

**1) The estimate amount is inclusive of GST.**
**2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**

**Signature of the Contractor** **sd/-**

**Executive Engineer**

**Terms & Conditions**:

1. The work should be completed within (14) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. No quotation will be accepted without PAN/GST no.
11. GST (2%)/TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

**Sd/-**
**Executive Engineer**

CC to:

1. A.E. Sub-Division (C-)
2. O.C.