0UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2026-27/ .01.2026

Date: 08.01.2026

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **19.01.2026 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations - 19.01.2026 up to 12.00 PM

Opening of Quotations - 19.01.2026 at 3.00 PM

S. No	Name of the work	Estimated Cost
1	Maintenance of Buildings' 'Applying internal painting in room no.248 and replacement of UPVC widow in bathroom (Room No-111) at school of social science'' in UoH campus	Rs. 36,727 /-

Sd/-
Executive Engineer

Name of work :- Maintenanace of Buildings- "Applying internal painting in Room No. 248 and Replacement of UPVC window in bathroom (Room No-111) at School of Social Science" in UoH Campus.

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	15.12	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :	1.00	Each	Rs_____ Rupees_____ _____	
	15.12.1	Of area 3 sq. metres and below				
2	9.147A	Providing and fixing factory made uPVC glazed/wire mesh windows/doors comprising of lead free uPVC multi-chambered frame, sash and mullion/coupler (where ever required) extruded profiles having minimum wall thickness of 1.70 mm for Series R1 and R2 profiles and 2.10 mm				

		for Series R3 and R4 profiles conforming to EN: 12608 in any shape, colour and design duly reinforced with galvanized mild steel section made of required shape & size as per CPWD Specification				
	9.147.A1	Two track two panels sliding window with Aluminium channel for roller track, wool pile, nylon rollers with SS 304 body.				
	9.147.A1.1	Using R2 series with frame (40mm & above) x (40mm & above) & sash (25mm & above) x (50mm & above) with zinc alloy (zamak) powder coated touch locks with hook (Height upto 1.2 meter)	2.25	Sqm	Rs_____ Rupees_____ _____	
3	9.7	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick :	2.10	Sqm	Rs_____ Rupees_____ _____	
	a) 9.7.7	Float glass panes				
	9.7.7.2	5.0 mm thick glass panes (weight not less than 12.50 kg/sqm).				
	b) 9.7.8	Fly proof stainless steel grade 304 wire gauge with 0.5 mm dia. wire and 1.4mm wide aperture with matching wood beading	1.05	Sqm	Rs_____ Rupees_____ _____	

4	21.8	Filling the gap in between aluminium frame & adjacent RCC/ Brick/ Stone work by providing weather silicon sealant over backer rod of approved quality as per architectural drawings and direction of Engineer-in-charge complete.	6.00	Rmt	Rs_____ Rupees_____ _____	
	21.8.1	Upto 5mm depth and 5 mm width				
5	13.82	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.	62.00	Sqm	Rs_____ Rupees_____ _____	
	13.82.2	Two coats				
6	13.88	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	31.00	Sqm	Rs_____ Rupees_____ _____	
7	13.99	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :	8.32	Sqm	Rs_____ Rupees_____ _____	
	13.99.1	One or more coats on old work				
8	14.5	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty:	0.72	Sqm	Rs_____ Rupees_____ _____	
	14.5.1	Float glass panes of nominal thickness 4 mm (weight not less than 10kg/sqm)				

					Total Amount in figures Rs	
		Less Rebate Offered if any_____ _____ **in words**_____				
1) The estimate amount is inclusive of GST. **2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**						
Signature of the Contractor					**sd/-** **Executive Engineer**	

Terms & Conditions:

1. The work should be completed within (14) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. No quotation will be accepted without PAN/GST no.
11. GST (2%)/TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Sd/-
Executive Engineer

CC to:

1. A.E. Sub-Division (C-)
2. O.C.