UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Assistant Engineer

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 10.01.2026

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **13.01.2026 at 12.00 P.M. in the Office of the University Works Department.** Hence, All the contractors are requested to remind the following details: -

Submission of Quotations: 13.01.2026 at 12.00 PM

Opening of Quotations: 13.01.2026 at 3.00 PM

S. No	Name of the work	Estimated Cost Rs.
1	Repairs and replacement of Ball Bearing, rewinding for 48" & 56" Ceiling fans at primary, C-Hostel & Domestic Substation area in Sub-Division-I in UoH Campus-Reg	**RS. 36,887/-**

Assistant Engineer

Name of Work: -Repairs and replacement of Ball Bearing, rewinding for 48" & 56" Ceiling fans at primary, C-Hostel & Domestic Substation area in Sub-Division-I in UoH Campus-Reg

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount	D.S.R./ MR
1	Removal of Existing Bearings from 48"/56" ceiling fans and replacement of 6201/6202 (Top and Bottom) Bearings and Labour charges	56 No's	Each	Figure:Rs_____ Words:Rupees_____ _____		MR
2	Rewinding of "48/56" ceiling fans with 35/36 SWG copper wire including, labour charges and transportation etc., as required.	60 No's	Each	Figure:Rs_____ Words:Rupees_____ _____		MR
3	Supply and fixing of oil condenser Tibcon Mak.2.5 MFD	60 No's	Each	Figure:Rs_____ Words:Rupees_____ _____		MR
	Sub Total					
	Add GST @18%					
	Net Amount					

Signature of the Contractor **Assistant Engineer**

Terms & Conditions:

1.The contractor/ bidder shall be a registered contractor and should produce definite proof of appropriate class registered by state or

2. The work should be completed within Fifteen (15) days from the date of issue of work order. Failure to complete the work within the

3. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
4. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
9. A.E (E) has to enclose the work completion certificate and user department certificate along with the bill.
10. No quotation will be accepted without PAN/VAT no.
11. TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Assistant Engineer