UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2026-27/ .01.2026

Date: 06.02.2026

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **10.02.2026 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations - 10.02.2026 up to 12.00 PM

Opening of Quotations - 10.02.2026 at 3.00 PM

S. No	Name of the work	Estimated Cost
1	Maintenance of Buildings'' Providing and fixing of UPVC Mesh windows, providing and fixing water closet E.W.C pan and wash basin at C-21 Qtrs.'' in UoH campus	Rs. 36,733 /-

Sd/-
Executive Engineer

Name of work: Maintenance of Building: - "Providing and fixing of UPVC Mesh windows ,Providing and fixing water closet E W.C. pan and wash basin at C-21 Qtr." in UoH Campus.

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.
3) The Bidder should intimate GST percentage separately. The GST shall be reimbursed on submission of proof by them.
4) The HSN Code for each item should be indicated.

SCHEDULE OF QUANTITIES

S.No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	9.147.A1.1	Providing and fixing factory made uPVC glazed/wire mesh windows/doors comprising of lead free uPVC multi-chambered frame, sash and mullion/coupler (where ever required) extruded profiles having minimum wall thickness of 1.70 mm for Series R1 and R2 profiles and 2.10 mm for Series R3 and R4 profiles conforming to EN: 12608 in any shape, colour and design duly reinforced with galvanized mild steel section made of required shape & size as per CPWD Specification, uPVC extruded glazing beads, interlocks and Inline sash adaptor (where ever required) of appropriate dimension, EPDM gasket, hardware, SS 304 grade fasteners of minimum 8 mm dia with countersunk head, comprising of matching polyamide PA6 grade sleeve for fixing frame to finished wall as per IS 1367 : Part 1 to 14, plastic packers, plastic caps and necessary stainless steel screws etc. Profile of frame, sash & mullion (if required) shall be mitred cut and fusion welded/mechanically jointed duly sealed at all corners, including drilling of holes for fixing hardware and drainage of water etc. After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod pf approved size and quality, all complete as per approved drawing	1.21	Sqm	Figure: Rs_____ Words: Rupees_____ _____	

		conforming to CPWD specification & direction of Engineer-in-Charge. Note:- Structural design proof checked from a Government Engineering Institute, to be provided by the manufacturer for: (i) Sites with basic wind speed > 45 m/sec as per IS 875 - Part 3 (ii) Sites with structure height more than 20m for all wind speeds. Two track two panels sliding window with Aluminium channel for roller track, wool pile, nylon rollers with SS 304 body. Using R2 series with frame (40mm & above) x (40mm & above) & sash (25mm & above) x (50mm & above) with zinc alloy (zamak) powder coated touch locks with hook (Height upto 1.2 meter)				
2	9.51.2	Providing and fixing fly proof galvanized M.S. wire gauge to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm all complete. With 12 mm mild steel U beading	1.21	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
3	21.8.1	Filling the gap in between aluminium frame & adjacent RCC/ Brick/ Stone work by providing weather silicon sealant over backer rod of approved quality as per architectural drawings and direction of Engineer-in-charge complete. Upto 5mm depth and 5 mm width	6.60	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
4	15.23.1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	1.65	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
5	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground	1	Cum	Figure: Rs_____ Words: Rupees_____ _____	

		or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.				
6	4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.30	Cum	Figure: Rs_____ Words: Rupees_____ _____	
7	11.37A	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kgper sqm including pointing the joints with white cement mixed with pigment of matching shade complete.	1.65	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
8	14.82	Dismantling W.C. Pan of all sizes including disposal of dismantled materials i/c malba all complete as per directions of Engineer-in- Charge.	1	Each	Figure: Rs_____ Words: Rupees_____ _____	
9	17.2.1	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings andfixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid	1	Each	Figure: Rs_____ Words: Rupees_____ _____	
10	18.53A	Providing and fixing C.P. Brass extension nipple (size 15mmx50mm) of approved make and quality as per direction of Engineer-in-charge.	3	Each	Figure: Rs_____ Words: Rupees_____ _____	

11	18.76.1	Cutting holes up to 30x30 cm in walls including making good the same: With common burnt clay F.P.S. (non modular) bricks	2	Each	Figure: Rs_____ Words: Rupees_____ _____	
12	18.53.1	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 : 15mm nominal bore	1	Each	Figure: Rs_____ Words: Rupees_____ _____	
13	18.21.1.1	Providing and fixing uplasticised PVC connection pipe with brass unions : 15 mm nominal bore	1	Each	Figure: Rs_____ Words: Rupees_____ _____	
14	17.60.1.2	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors : 100 mm inlet and 100 mm outlet Sand Cast Iron S&S as per IS: 1729.	1	Each	Figure: Rs_____ Words: Rupees_____ _____	
15	12.41.1	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 75mm diameter	3	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
	12.41.2	110mm diameter	3	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
16	12.42.5.1	Providing and fixing on wall face unplasticised - PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipes conforming to IS 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. bend 87.5	2	Each	Figure: Rs_____ Words: Rupees_____ _____	

	12.42.5.2	110mm bend	2	Each	Figure: Rs_____ Words: Rupees_____ _____	
17	17.7.1	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps	1	Each	Figure: Rs_____ Words: Rupees_____ _____	
18	MR	Providing and fixing of C.P Health faucet Make:Hind ware	1	Each	Figure: Rs_____ Words: Rupees_____ _____	
19	MR	Providing and fixing of C.P Soap tray with necessary accessories Make Hindware	1	Each	Figure: Rs_____ Words: Rupees_____ _____	
20	MR	Providing and fixing of heavy duty stainless steel towel ring. Make: Hindware	1	Each	Figure: Rs_____ Words: Rupees_____ _____	
21	MR	Providing and fixing of brass angle cock with flange Make:Hindware	1	Each	Figure: Rs_____ Words: Rupees_____ _____	
22	MR	Providing and fixing of heavy dusty satin less steel towel rod of length 600mm. Make :Hind ware	3	Each	Figure: Rs_____ Words: Rupees_____ _____	
					Total Amount in figures Rs	

		Less Rebate Offered if any_____ **Net Amount (excluding GST)**_____ **Net Amount in words**_____ **Add GST** _____ **Total Amount (Including GST)** _____ **Total Amount in words** _____

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.
3) The Bidder should intimate GST percentage separately. The GST shall be reimbursed on submission of proof by them.
4) The HSN Code for each item should be indicated.

Signature of the Contractor

sd/-
Executive Engineer

Terms & Conditions:

1. The work should be completed within thirty (14) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. No quotation will be accepted without PAN/GST no.
11. GST(2%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

Sd/-
Executive Engineer

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,