UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

**NOTE**

Ref: UH/ENGG/UE/2026-27/ .01.2026

Date: 06.02.2026

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **10.02.2026 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

**Submission of Quotations - 10.02.2026 up to 12.00 PM**

**Opening of Quotations - 10.02.2026 at 3.00 PM**

| S. No | Name of the work | Estimated Cost |
|---|---|---|
| 1 | Maintenance of Buildings'' Providing and laying the kitchen platform, providing and fixing of cupboards and termite treatment at A-52 Qtrs.'' in UoH campus | Rs. 31,732 /- |

Sd/-
Executive Engineer

**Name of work: Maintenance of Building: - "Providing and laying the kitchen platform, Providing and fixing of cupboards and termite treatment at A-52 Quarter." in UoH Campus.**

**1) The estimate amount is inclusive of GST.**
**2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**
**3) The Bidder should intimate GST percentage separately. The GST shall be reimbursed on submission of proof by them.**
**4) The HSN Code for each item should be indicated.**

**SCHEDULE OF QUANTITIES**

| S.No | D.S.R.No. | Description of item | Qty | Unit | Rate in figures & Rate in words | Amount |
|---|---|---|---|---|---|---|
| 1 | 15.25 | Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead | 2.99 | Sqm | Figure: Rs_____<br>Words: Rupees_____<br>_____ | |
| 2 | 14.1.1 | Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-harge.<br>With cement mortar 1:4 (1 cement : 4 fine sand). | 2.99 | Sqm | Figure: Rs_____<br>Words: Rupees_____<br>_____ | |
| 3 | 8.2.2.1 | Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size,approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.<br>Granite stone slab colour black, Cherry/Ruby red<br>Area of slab upto 0.50 sqm | 2.99 | Sqm | Figure: Rs_____<br>Words: Rupees_____<br>_____ | |

| | | | | | | |
|---|---|---|---|---|---|---|
| 4 | 15.60 | Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. | 0.05 | Cum | Figure: Rs_____<br>Words: Rupees_____<br>_____ | |
| 5 | 8.3.2 | Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge.<br>Granite work | 5.90 | Rmt | Figure: Rs_____<br>Words: Rupees_____<br>_____ | |
| 6 | 2.35.5 | Diluting and injecting chemical emulsion for POST-CONSTRUCTIONAL anti- termite treatment (excluding the cost of chemical emulsion) :<br>Treatment at points of contact of wood work by chemical emulsion Chlorpyriphos/ Lindane (in oil or kerosene based solution) @ 0.5 litres per hole by drilling 6 mm dia holes at downward angle of 45 degree at 150 mm centre to centre and sealing the same. | 18.00 | Rmt | Figure: Rs_____<br>Words: Rupees_____<br>_____ | |
| 7 | 9.158.2 | Providing and fixing in wall lining medium density fibre board IS: 14587:1998 marked, Pre-laminated one side decorative lamination and other side balancing lamination, with necessary fixing arrangement and screws etc. complete<br>18 mm thick. | 2.70 | Sqm | Figure: Rs_____<br>Words: Rupees_____<br>_____ | |
| 8 | 9.100.1 | Providing and fixing aluminium handles ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :<br>125mm | 4 | Each | Figure: Rs_____<br>Words: Rupees_____<br>_____ | |
| 9 | 9.114.2 | Providing and fixing magnetic catcher of approved quality in cupboard / ward robe shutters, including fixing with necessary screws etc. complete.<br>double strip (horizontal type) | 4 | Each | Figure: Rs_____<br>Words: Rupees_____<br>_____ | |

| | | | | | | |
|---|---|---|---|---|---|---|
| 10 | MR | Providing and fixing of Box hinges with necessary Screw /nuts etc. | 4 | Each | Figure: Rs_____<br>Words: Rupees_____ | |
| | | | | | **Total Amount in figures Rs** | |
| | | **Less Rebate Offered if any**_____<br>**Net Amount (excluding GST)**_____<br>**Net Amount in words**_____<br>**Add GST**<br>_____<br>**Total Amount (Including GST)** _____<br>**Total Amount in words** _____ | | | | |

**1) The estimate amount is inclusive of GST.**
**2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**
**3) The Bidder should intimate GST percentage separately. The GST shall be reimbursed on submission of proof by them.**
**4) The HSN Code for each item should be indicated.**

**Signature of the Contractor**

**sd/-**
**Executive Engineer**

**Terms & Conditions**:

1. The work should be completed within thirty (14) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. No quotation will be accepted without PAN/GST no.
11. GST(2%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

**Sd/-**
**Executive Engineer**

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,