UNIVERSITY OF HYDERABAD

{Establishment by the act of the Parliament in 1974}
Gachibowli, Hyderabad

TENDER SCHEDULE FOR THE WORK OF

NAME OF WORK:- "PROVIDING AND LAYING OF DAMAGED DRAIN LINES AT A - (31 TO 37) QUARTERS TO SEPTIC TANK" IN THE UNIVERSITY OF HYDERABAD CAMPUS.

C O N T R A C T O R

ESTIMATED COST Rs. 22,05,700/- (Inclusive of GST)

SANCTION AMOUNT Rs. 22,05,700/-

EMD Rs. 44,114/-

F & A Receipt No. _____ Book No. _____

Time for the Completion of work: 01 Month

FROM _____TO_____

WORK ORDER REFERANCE:

EXPENDITURE CHARGABLE TO:

Bid Submission start date (Online) : 13 .02.2026 up to 3.00 P.M.

Bid Submission close date (Online) : 18 .02.2026 up to 3.00 P.M.

Bid opening date (Online) : 19.02.2026 at 3.00 P.M (Technical Bid)

Date of opening of financial bids of technically qualified bidders will be intimated through Central Public Procurement Portal.

Sd/-
EXECUTIVE ENGINEER A/C

Sd/-
UNIVERSITY ENGINEER

UNIVERSITY OF HYDERABAD
{Establishment by the act of the Parliament in 1974}
Gachibowli, Hyderabad.
University Works Department,
Ph no.040-23132306/040-23101208
E-mail: aet.uohyd@gmail.com

E-TENDER

FOR

NOTICE INVITING TENDER (NIT)

Notice Inviting e-Tender No.	**UH/ENGG/UWD/2025-26/23**
Name of the work	**Name of work :-** "Providing and laying of damaged drain lines at A- (31 to 37) Quarters to Septic Tank" in the University of Hyderabad Campus.
Estimated Cost	**Rs. 22,05,700/- (Inclusive of GST)**
Earnest Money Deposit (EMD)	**Rs. 44,114/- (Through DD or Bank Guarantee)**
Performance Guarantee	**5% of the Tendered value**
Time Allowed	**01Month**
Date of Start of Bid Submission	**13.02.2026 at 3.00 PM**
Last date & Time for Submission of Bids	**18.02.2026 upto 3.00 PM**
Date & Time of Opening of Technical Bids	**19.02.2026 upto 3.00 PM**
Date & Time of Opening of Finance Bids	**Will be intimated to technically qualified bidders in due course of time through Central Public Procurement portal.**
Submission of hard copies of EMD	The original EMD infavour of Finance Officer, UoH should be submitted in the University Works Department, University of Hyderabad, Gachibowli, P.O. Central University, HYDERABAD – 500046 up to 3.00 PM on 19. 02 .2026.

Sd/-
EXECUTIVE ENGINEER A/C

Sd/-
UNIVERSITY ENGINEER

UNIVERSITY OF HYDERABAD

University Works Department

Item Rate Tender Contract for Works

INDEX

S.No	Details	Page
1	Form-J	4-4
2	Check list for Technical eligibility of Tender.	5-5
3	Bank Details from the Contractors.	6-6
4	General Guidelines.	7-7
5	Method of tender application, tender submission and tender opening.	8-9
6	Eligibility criteria and notice inviting tender.	10-16
7	Proforma of Schedules.	17-22
8	Specialised Agencies.	23-28
9	Schedule of Quantities.	29-34

Signature of the Contractor

FORM ‘J’

UNDERTAKING

I/We undertake and confirm that our firm/partnership firm has not been blacklisted by any state/central departments/PSUs/Autonomous bodies and the last 7 years of its operations. Further that, if such information comes to the notice of the department then I/we shall be debarred for bidding in University of Hyderabad in future forever. Also, if such information comes to the notice of University of Hyderabad on any day before date of start of work, the Engineer-in-charge shall be free to cancel the agreement and to forfeit the entire amount of earnest money Deposit/Performance Guarantee.

If further solemnly declare that all the certificates are true to the best of my knowledge.

Signature of Bidder(s) or an authorized Officer of the firm with stamp

Signature of the Contractor

Check list for Technical eligibility of Tender

Sl No	Doc Ref	Description of the Document	Enclosed Yes/No	Remarks
1	NIT Para No 1 Registration of Contractors	CPWD/MES/BSNL/Railway/State PWD(B&R) Autonomous bodies or undertakings.		
2	NIT Para No 1 Eligible Contractors/	Date of validity of enlistment		
3	Details of works completed during last 7 years (Detailed statements to be enclosed)	Not less than 40 % of estimated cost (Three works Civil completed works)		
		Not less than 50 % of estimated cost (Two works of Civil completed works)		
		Not less than 80 % of estimated cost (One work of Civil completed work)		
		(Submit Details of works on which contractor meets specified eligibility criteria)		
4	As per the NIT	The tenderer shall have to furnish an undertaking in prescribed format. (form J)		
5	Annual turnover.	30% of the estimated cost.		

Signature of the Contractor

Details of the Contractor

S.No.	Particulars	
1	Name of the Firm	
2	Name of the Contractor	
3	Contractor Details	
(a)	Mobile	
(b)	E-Mail id	
4	Name of the Bank	
5	Name of the Branch	
6	Account No. (prefix with zeros, if any as given on the cheque book/pass book) {please attach cancelled cheque}	
7	IFSC Code of the Branch	
8	MICR Code	
9	PAN No.	
10	GST No.(if applicable)	

Signature of the Contractor

GENERAL GUIDELINES

1. This book of "General Conditions of Contract" is applicable to both types of tenders i.e." Percentage rate tenders and Item rate tenders". Accordingly, alternative provisions for conditions Nos. 4, 10 & 12 of the General Rules and Directions are given in this book. The appropriate alternatives will be applicable in specific cases depending on whether this is used for percentage rate tender (CPWD-7) or item rate tender (CPWD-8).

2. CPWD-6, Schedules A to F, special conditions/specifications and drawings only will be issued to intending bidders. The HCU-GCC 2016 form will not be issued along with the Tender Documents but the same shall form part of the agreement to be drawn and signed by both parties after acceptance of tender. The HCU-GCC 2016 can be accessed and downloaded from website www.uohyd.ac.in

3. All blanks are confined to Notice Inviting Tender (CPWD-6) and
Schedules A to F.

4. Authority approving the Notice Inviting Tenders (NIT) shall fill up all the blanks in CPWD-6 and in Schedules B to F before issue of Tender Papers.

5. The intending bidders shall quote their rates in Schedule A (Schedule of quantities in CPWD Form 3)

6. The proforma for registers and Schedules A to F are only for information and guidance. These are not to be filled in the Standard Form. The Schedules with all blanks, duly filled, shall be separately issued to all intending tenderers.

Signature of the Contractor

Method of Tender Application, Tender Submission and Tender Opening

The intending bidder must read the terms and conditions of CPWD-6 carefully. He should only submit his bid if he considers himself eligible and he is in possession of submission of all the required documents as per NIT.

The following Technical and Finance bid documents shall be upload simultaneously with scanned copies in e-procurement web site. The tender documents may also be seen at University of Hyderabad website- www.uohyd.ac.in

(A) Technical bid documents

1) The bidders except Micro and Small Medium Enterprises (MSEs) notified under (MSME) Policy (as per Rule 170 of GFR 2017), should pay EMD of 2% of Tendered amount (including GST) should be drawn in favor of "Finance Officer, University of Hyderabad" either in form of Bank Guarantee fixed deposit receipt of a bank/demand draft/banker check of a scheduled bank. The original EMD shall be placed in Envelope-1 and closed using suitable adhesive and shall be dropped in the Tender box before the bid opening date and time. The scanned copy of EMD shall be uploaded on the web site. Bids submitted along with EMD in the prescribed form shall be considered for further evaluation of eligibility Criteria. Bids submitted without EMD shall be summarily rejected. The Technical bid shall contain all the documents scanned and uploaded in the concerned web site, based on which the bidder claim to be eligible as per eligibility criteria prescribed in NIT. Any discloser of finance bid in the technical bid documents will lead to summary rejection of bid.
2) Work experience certificates as per Eligibility criteria.
3) Contract registration certificate issued by State or Central Govt., Departments or state/central autonomous bodies undertaking.
4) PAN card & GST Registration Certificate.
5) Latest Income Tax returns for the consecutive three financial years. Immediately preceding the tender date.
6) Turnover Certificate for the consecutive three financial years. Immediately preceding the tender date duly certified by the Chartered Accountants.
7) Undertaking as per Form "J".
8) Other necessary documents as per Tender documents.

On the due date of opening, the Technical bid of those tenderer who furnished valid EMD will only be opened. On opening of Technical bid, further detailed scrutiny/evaluation will be carried out. During the evaluation of techno commercial bids, the documents furnished by the tenderers will be scrutinized in detail. Any tender, found as not fulfilling the eligibility criteria will be rejected at this stage and such offers will not be considered for further processing. The price bid of only those tenderers who have been qualified during the scrutiny and technical evaluation will be opened separately on a specified date (with due intimation to the qualified bidders) and further processed, as per tender procedure/stipulations.

Signature of the Contractor

Eligibility Criteria and Notice Inviting tender:

(1) The bidder shall be a registered/enlisted contractor and should produce definite proof of registration/enlistment under appropriate class issued registered by state or central government departments or state/central autonomous bodies or undertakings.

(2) Experience Criteria (Eligibility criteria for participation in tendering).

Estimate Cost of the work is **Rs. 22,05,700/-(including of GST)**

(a) Bidders should have satisfactorily completed during last 07 years ending last day of the month prior to the month in which the tenders are invited.

(i) One work of Civil completed works of **80%** of Estimated cost i.e **Rs. 17,64,560/- (including of GST)**

(OR)

(ii) Two works of Civil completed works **each** costing not less **50%** of Estimated cost i.e**. Rs. 11,02,850/- including of GST)**

(OR)

(iii) Three works of Civil completed works **each** costing not less than **40%** of Estimated cost i.e **Rs. 8,82,280/- (including of GST)**Self-Attested copies of experience certificates are to be submitted.

(3) Only work completed and certified by competent authority of the organization will be accepted as Experience Certificate. Certificate not issued in the name of bidder (Contractor) or issued by an authority not competent to issue such certificate will not be accepted.

Mere work order or purchase order etc issued will not qualify for experience.

(3a) The copies of relevant IT returns and Auditor Certified Turnover Certificate for the consecutive three financial years, immediately preceding the tender date. PAN Card, GST Registration certificate should accompany the technical bid.

(4) The contractors who were penalized under clause No (2) of General Conditions of Contract during the last one year in UoH campus works will be disqualified and their Technical /Financial bids will not be accepted.

(5) Should have had average Annual Financial turnover not less than **Rs. 6,61,710/-** i.e., **30%** of the estimated cost of the work during the last three years ending **31st March 2025.**

(6) To become eligible for issue of tender, the tenderer shall have to furnish an undertaking, as perform 'J' of the NIT.

Signature of the Contractor

(7) Agreement shall be drawn with the successful tenderer in the prescribed Form No. CPWD 7/8 which is available in the University of Hyderabad website. Tenderer shall quote his rates as per various terms and conditions of the said form which will form part of the agreement.

(8) The time allowed for carrying out the work is **01Month** from the start date as defined in clause 5 Scheduled "F" or from the first date of handing over of the site, whichever is later, in accordance with phasing if any indicated in the tender document. The site shall be made available as and when required for execution of work.

(9)(a) Tenders shall be accompanied with Earnest money of **2%** of estimated cost put to tender/in the receipt of fixed deposit receipt /demand draft/banker check of a scheduled bank issued in favour of Finance Officer, University of Hyderabad payable at Hyderabad.

(b) Defect liability period of six (06) months after satisfactory completion of work.

(10) The Bidder/contractor, whose tender is accepted, will be required to furnish performance Guarantee of **5%** (Five Percent) of the tendered amount within the period specified in Schedule F. This guarantee shall be in the form of cash (in case guarantee amount is less than Rs. 10,000/-) or Deposit at Call receipt of any scheduled bank/Banker's cheque of any scheduled bank/Demand Draft of any scheduled bank/Pay order of any scheduled bank (in case guarantee amount is less than Rs. 1,00,000/-) Government Securities or Fixed Deposit Receipts or Guarantee Bonds of any Scheduled Bank in accordance with the prescribed form.

In case the contractor fails to deposit the said performance guarantee within the period as indicated in Schedule "F" including the extended period if any, the Earnest Money deposited by the contractor shall be forfeited automatically without any notice to the contractor.

(11) The description of the work is as follows: Copies of other drawing and documents pertaining to the works will be open for inspection by the tenderers at the office of above mentioned officer. Tenderers are advised to inspect and examine the building and its area surroundings and satisfy themselves before submitting their tenders. The tenderer shall be responsible for arranging and maintaining at his own cost all materials, tools & plants, water, required for executing the work unless otherwise services provided for in the contract documents.

Submission of a specific electricity access, facilities for workers and all other tender by a tenderer implies that he has read this notice and all other contract documents and has made himself aware of the scope and specifications of the work to be done.

Signature of the Contractor

(12) The competent authority on behalf of the University of Hyderabad does not bind himself to accept the lowest or any other tender and reserves himself the authority to reject any or all the tenders received without the assignment of any reason. All tenders in which any of the prescribed condition is not fulfilled or any condition including that of conditional rebate is put forth by the tenderer shall be summarily rejected.

(13) Canvassing whether directly or indirectly, in connection with tenderers is strictly prohibited and the tenders submitted by the contractors who resort to canvassing will be liable to rejection.

(14) The University Engineer on behalf of the competent authority of University reserves to himself the right of accepting the whole or any part of the tender and the tenderer shall be bound to perform the same at the rate quoted.

(15) No Engineer of Gazette rank or other Gazetted Officer employed in Engineering or Administrative duties in an Engineering Department of the Government of India is allowed to work as a contractor for a period of one year after his retirement from Government service, without the previous permission of the Government of India in writing.

This contract is liable to be cancelled if either the contractor or any of his employees is found any time to be such a person who had not obtained the permission of the Government of India as aforesaid before submission of the tender or engagement in the contractor's service.

(16) The tender for the works shall remain open for acceptance for a period of **90 days** from the date of opening of tenders/Ninety days from the date of opening of financial bid. If any bidder withdraws his tender before the said period or issue of letter of acceptance, whichever is earlier, or makes any modifications in the terms and conditions of the tender which are not acceptable to the department, then the Government shall, without prejudice to any other right or remedy, be at liberty to forfeit of the said earnest money as aforesaid. Further the tenderer shall not be allowed to participate in the retendering process of the work.

(17) The Contractor should furnish the contact telephone/cell phone numbers of self and their supervisors to the institute. The normal working hours shall be from 9.00 am to 5.30 pm on all seven days of the week but if required, the Contractor should execute the works beyond the normal working hours/ as per the requirement of the institute.

Signature of the Contractor

(18) Contractor's liability for damage caused during installation work and imperfections: if the contractor or his / her workmen or servants shall break, deface, injure or destroy any part of the building in which they may be working or building road, fence, enclose, water pipe, cable, drain, electric or telephone posts or wires, trees, grass, or grasslands or any technical Equipment in the premises on which the work or any part of it as being executed, or if any defect, shrinkage or other faults appear in the work the contractor shall make good at his/ her own expense, or in default, the indenter may get the same rectified and deduct the expense from any amount that may be due or at any time thereafter may become due to the contractor.

(19) The notice inviting Tender shall form part of the contract document. The successful tenderer/contractor, on acceptance of his tender by the Accepting Authority shall within 15 days from the stipulated date of start of the work, sign the contract consisting of: -

a. The Notice Inviting Tender, all the documents including additional conditions, specifications and drawings, Clarifications if any, forming the tender as issued at the time of invitation of tender and acceptance thereof together with any correspondence leading thereto.

b. Standard C.P.W.D. Form 7/8

(20) Time and Quality are the essence of this work and to ensure the same each R.A bill shall accompany timely, Quality, Quantity certificate and the same shall be ensured by the University Engineer.

(21) GST invoice form should be filled and submitted along with the bill.

(22) The Labour engaged and working equipment brought by the contractor for the work shall be recorded in the UoH Security main gate before entering in to the premises and obtain necessary gate pass.

Signature of the Contractor

Percentage Rate Tender, Item Rate Tender & Contract for Works

Tender for the work of:- "Providing and laying of damaged drain lines at A-(31 to 37) Quarters to Septic Tank" in the University of Hyderabad Campus.

-

(i) To be submitted by _____up to 2.30 P.M. _____.

(ii) To be Opened in presence of tenderers who may be present at 3.00 P.M Hyd. On _____in the office of the

Executive Engineer, University Works Department, University of Hyderabad

Issued to ___N/A_____

Signature of officer issuing the tender Documents:

Designation __N/A_____

Date of Issue _____

Signature of the Contractor

TENDER

I/We have read and examined the notice inviting tender, schedule, A, B, C, D, E & F Specifications applicable, Drawings & Designs, General Rules and Directions, Conditions of Contract, clauses of contract, Special conditions, Schedule of Rate & other documents and Rules referred to in the conditions of contract and all other contents in the tender document for the work.
I/We hereby tender for the execution of the work specified for the University of Hyderabad within the time specified in Schedule "F" viz., schedule of quantities and in accordance in all respect with the specifications, designs, drawing and instructions in writing referred to in Rule-1 of General Rules and Directions and in Clause 11 of the Conditions of contract and with such materials as are provided for, by, and in respect of accordance with, such conditions so far as applicable.

We agree to keep the tender open for ninety (90) days from the due date of its opening / ninety days from the date of opening of financial bid and not to make any modification in its terms and conditions. A sum of Rs._____ is hereby forwarded in DD / Bankers Cheque / deposit at call receipt of a scheduled bank/fixed deposit receipt of scheduled bank/demand draft of a scheduled bank issued by a scheduled bank in Favour of 'Finance Officer, University of Hyderabad' as earnest money. If I/We, fail to furnish the prescribed performance guarantee within prescribed period. I/We agree that the said University of Hyderabad, in office shall without prejudice to any other right or remedy, be at liberty to forfeit the said earnest money absolutely. Further, if I/We fail to commence work as specified, I/We agree that University of Hyderabad in office shall without prejudice to any other right or remedy available in law, be at liberty to forfeit the said earnest money and the performance guarantee absolutely, otherwise the said earnest money shall be retained by him towards security deposit to execute all the works referred to in the tender documents upon the terms and conditions contained or referred to those in excess of that limit at the rates to be determined in accordance with the provision contained in Clause 12.2 and 12.3 of the tender form. Further, I/We agree that in case of forfeiture of Earnest Money & Performance Guarantee as aforesaid. I/We shall be debarred for participation in the re-tendering process of the work.

I/We undertake and confirm that eligible similar work(s) has/have not been got executed through another contractor on back to back basis. Further that, if such a violation comes to the notice of Department, then I/we shall be debarred for tendering in University of Hyderabad in future forever. Also, if such a violation comes to the notice of Department before date of start of work, the Project In-Charge shall be free to forfeit the entire amount of Earnest Money Deposit/Performance Guarantee.

Signature of the Contractor

I/We hereby declare that I/We shall treat the tender documents drawings and other records connected with the work as secret/confidential documents and shall not communicate information/derived there from to any person other than a person to whom I/We am/are authorized to communicate the same or use the information in any manner prejudicial to the safety of the State.

Dated:

Signature of Contractor

Witness: Address:

Postal Address:

Occupation:

ACCEPTANCE

The above tender (as modified by you as provided in the letters mentioned hereunder) is accepted by me for an on behalf of the University of Hyderabad for a sum of Rs. _____
(Rupees _____
_____). The letters referred to below shall form part of this contract agreement:-

(a)

(b)

(c)

University Engineer

Signature
……..

Signature of the Contractor

PROFORMA OF SCHEDULES

(Separate Performa for Civil, Elect. & Hort. Works in case of composite Tenders)
(Operative Schedules to be supplied separately to each intending tenderer)

SCHEDULE 'A'

Schedule of quantities (as per CPWD-3)

SCHEDULE 'B'

Schedule of materials to be issued to the contractor.

S.No.	Description of item	Quantity	Rates in figures & words at which the material will be charged to the contractor	Place of issue
1	2	3	4	5
	Nil	Nil	NA	NA

SCHEDULE 'C'

Tools and plants to be hired to the contractor

S.No.	Description	Hirecharges per day	Place of Issue
1	2	3	4
	Nil	NA	NA

Signature of the Contractor

SCHEDULE 'D'

Extra schedule for specific requirements/document for the work, if any.: Particular Specifications and Tender Conditions attached

SCHEDULE 'E'

Reference to General Conditions of contract: HCU-GCC-2016

Tender for the work of**:-** "Providing and laying of damaged drain lines at A-(31 to 37) Quarters to Septic Tank" in the University of Hyderabad Campus.

Estimated cost of work : **Rs. 22,05,700/- (Inclusive GST)**

(i) Performance Guarantee : 5% of tendered value (Including EMD)

(ii) Security Deposit : 10% of tendered value (Including Performance Guarantee)

SCHEDULE-'F'

GENERAL RULES & DIRECTIONS: Officer inviting tender: Engineer-in-Charge/E.E/U.E

Maximum percentage for quantity of items of work to be executed beyond which rates are to be determined in accordance with Clauses 12.2 & 12.3:

See below Definitions:

i) Engineer-in-Charge is referred to University Engineer or any other Engineer so designated having overall supervision and charge of the execution of the work.

ii)Accepting Authority for grant of EOT is the V.C, University of Hyderabad

iii) Percentage on cost of materials and Labour to cover all overheads and profits : 15%

iv) Standard Schedule of Rates is DSR : 2023

v) Department : U.W.D, UOH, HYDERABAD

vi) Standard HCU Contract Form GCC 2016, HCU Form 7/8 modified & corrected up to date.

vii) In respect of items of work, for which the contractor has quoted freakishly high rates i.e where the agreement rates are in excess of 50% of the estimated rates/Market rate, agreement rates will be paid upto the agreed quantities only. For the quantities executed in excess of the agreed quantities, payment will be made at the mutually agreed rates as approved by the Competent Authority.

viii) In respect of items of work, for which the contractor has quoted rates are below 50% of the estimated rates/Market rate, these rates will be considered as freak low rates. Quantities of these items shall not be decreased under any circumstances.

ix) The work shall be carried out according to CPWD Specification, General Condition of contracts 2020 along with special condition/technical specification, drawings applicable. If, however, any particular item/items are issue are not covered by these specifications and special conditions, then the work shall be carried out in accordance to relevant BIS (ISI) codes/code of practice.

Signature of the Contractor

x) Time is the essence of contract. Accordingly, the contractor shall abide by the time schedule. Failure to complete the work within the stipulated time will entail recovery of compensation from the work bills as determined by the University Engineer, under condition -2 of the General Conditions of contracts.

Clause 1

(i) Time allowed for submission of Performance Guarantee from the date of issue of letter of acceptance . 07.....Days

Clause 2

V.C.

Authority for fixing compensation under clause 2 is

Clause 2A

Whether Clause 2A shall be applicable No

Clause 5

Number of days from the date of issue of letter of acceptance for reckoning date of start..... 14 days

Mile stone(s) as per table given below: -

S.No	Description of Milestone	Time allowed in days (from date of start)	Amount to be with-held in case of non-achievement of mile stone
1	25% agreement value	One fourth of time allowed for completion.	In the event non-achieving the necessary progress as assessed from the running payments. 2.5% of tendered value of work will be withheld for failure of each milestone.
2	50% agreement value	One half of time allowed for completion.	
3	75% agreement value	Three fourth of time allowed for completion.	
4	100% agreement value	Full period of time allowed for completion.	

Time allowed for execution of work.....3 Months.....

Authority to decide:

(i) Extension of time : Vice-chancellor

(ii) Rescheduling of mile stones : Engineer-in-Charge/U.E

Signature of the Contractor

Clause 6 / 6A

Clause applicable - (6 or 6A) : 6

Clause 7

Gross work to be done together with net payment /adjustment of advances for material collected, if any, since the last such Payment for being eligible to interim payment	Rs: Total Tender Amount X0.75 / No. of months for completion of work

Clause 10A

List of testing equipment to be provided by the contractor at site lab.

1 ..... 2. ..... 3.....
4 ..... 5. ..... 6.....

Clause 10B(ii)

Whether Clause 10 B (ii) shall not applicable	Yes
Clause 10 (C) : Whether applicable or not?	Yes
Clause 10 (CA): Whether applicable or not?	No
Clause 10 (CC): Whether applicable or not:	No

Signature of the Contractor

Clause 12

12.2. & 12.3Deviation Limit beyond which clauses

12.2 & 12.3 shall apply for building work..... Unlimited

12.5 Deviation Limit beyond which clauses

12.2 & 12.3 shall apply for foundation work ..... Unlimited

Clause 16

Competent Authority for deciding reduced rates Engineer-in- charge

Clause 18

List of mandatory machinery, tools & plants to be deployed by the contractor at site:-

1. .....2..... 3. .....
4. ..... 5. .....
6. .....7..... 8. .....

Clause 25

Constitution of Dispute Redressal Committee (DRC)	Competent Authority to appoint DRC
DRC shall consist of one Chairman and two members	Vice-Chancellor

Signature of the Contractor

Clause 36 (i)

Requirement of Technical Representative(s) and recovery Rate

Minimum Qualification of technical representative	Discipline	Designation (Principal Technical/ Technical Representative	Minimum Expenditure	Number	Rate at which recovery shall be made from the contractor in the event of not fulfilling provision of clause 36(i)	
					Figures	Words

Assistant Engineers retired from Government services that are holding Diploma will be treated at par with Graduate Engineers.

Clause 42

(i) (a) Schedule/statement for determining theoretical quantity of cement & bitumen on the basis of Delhi Schedule of Rates 2023 printed by C.P.W.D.

(ii) Variations permissible on theoretical quantities:

(a) Cement

For works with estimated cost put to tender not more than Rs. 5 lakh. plus/minus. 3%

For works with estimated cost put to tender more than Rs.5 lakh. plus/minus. 2%

(b) Bitumen All Works 2.5% plus & only & nil on minus side.

(c) Steel Reinforcement and structural steel sections for each diameter, section and category 2% plus/minus

(d) All other materials. Nil

Signature of the Contractor

LIST SHOWING PREFERRED BRANDS/MANUFACTURERS/MAKE

28. SPECIALIZED AGENCIES

28.1 CIVIL

NOTE: - 1) A List of Preferred Brand Names of Various Materials / Products are shown below for usage in execution of Work. However, Approved equivalent material of any other Specialized Companies / Firms may also be used , in case it is established that the Brands Specified below are not available in the market and subject to Approval of the alternate Brand by the Engineer In charge.

2) It must be ensured, in general, that all materials to be used in the works shall bear BIS Certification mark. In cases where for a particular material/product, BIS Certification Mark is not available, then the material proposed to be procured can be used subject to the condition that it should conform to CPWD Specifications and relevant BIS codes. In such cases written approval of the Engineer-in -Charge shall be obtained before use of such material in their works.

3) The list given below does not absolve the Executing Agency from their responsibility for using these products. It is only after, they are satisfied about the quality and performance, the products shall be used. To achieve this, proper check on the quality of the product, actually to be used, should be exercised.

S.No	Product	Make
1	Ordinary Portland Cement	ACC, Ultratech, Vikram, Shree Cement, Ambuja, Jaypee Cement, Century Cement, JK Cement, Penna Cement , Bharathi Cement, Maha , Nagarjuna and Brands Approved by CE(SZ)II,CPWD,Hyderabad.
2	Portland Pozzolana Cement	
3	White Cement	Birla, J.K. White, Travancore
4	Reinforcement steel – (Primary Producers)	RINL, SAIL, TATA STEEL Ltd., JSW STEEL Ltd., JINDAL STEEL & POWER Ltd., Shyam produced by M/s.Shyam Steel Industries Ltd and Manufacturers approved by Spl.DG(SR),CPWD,Chennai
5	Ready Mix Concrete (RMC)	Ultra Tech, ACC, RMC Ready Mix (India), Nuvoco Vistas Corporation Ltd., (formally known as Lafarge India Ltd.), RMC by M/s Aparna Enterprises limited,Hyderabad, RDC Concrete (India) Pvt. Ltd and additional firms approved by CE, SZ-II, CPWD, Hyderabad.
6	Pulverized Stone Sand/ Crushed Stone Sand (Manufactured Sand)	Rank Enterprises, Robo Sand.
7	Polymer based Curing Compounds	FOSROC, SIKA, BASF
8	Structural Steel Sections	TATA, SAIL,RINL, JINDAL Steel & Power Ltd., J SW
9	Hollow Steel Tube Sections	TATA, Jindal, Zenith
10	Fly ash Cement Bricks	KSP Industries, Prakash International Ltd, NUBRIC.

Signature of the Contractor

11	Autoclaved Aerated Concrete Blocks (AAC)	M/s. Hyderabad Industries Ltd., M/s. Ultra Tech India Limited, M/s. Siporex India Ltd., NCL, NUBRIC.
12	Binding Wire	TATA, JSW
13	Factory Made Cement Concrete Cover Blocks	A.S.R. Cover Blocks, Stand alone Universal Concrete Cover Blocks
14	RCC Door Frames	Ventura, Bothra.
15	Flush Door Shutters	Raavela Doors, Indian Timber Products, Kitply,
16	Fire Check / Rated Doors	Navair, Godrej, Shaktimet, Kenwood, MPP Schodders.
17	Smoke Seal Strip	Promat, Astro flame
18	Plain / Prelaminated Particle Board	ECO Board, TESA Action Co., Kitlam, Archid ply, Century
19	Ply wood / Laminate	Kitply, Centuryply, Greenply, Merino, Sonear (Donear), Formica, Archidply, Royal touch .
20	Natural wood Veneers	Kitply, Centuryply, Sonear (Donear), Greenply Archidply, Durain, National Action Tesa, Anchor.
21	Adhesive / Glue	Pidilite, Dunlope, Sika, Fosroc, Vamorganic.
22	Steel Windows/ Pressed Steel Frames	Madhu Industries, (Bengaluru), San Harvic, NCL
23	Cement Bonded Particle Board	BISON Boards of NCL.
24	PVC Door Frames & Shutters	Rajshri Plastiwood, Sintex.
25	FRP Door Frames & Shutters	Meena Fibre Glass, Duroplast, Cactus, Polyline.
26	UPVC Windows	Fenesta, Kommerling , Rehau, Wintech, LG, Encraft – Madhu Industries, Polywood.
27	Ceramic Floor /Dado Tiles	Somany, Johnson, Kajaria, Orient, Bell, Asian, NITCO.
28	Vitrified Tiles	Somany, Johnson, Kajaria, Orient Bell Ltd,
29	Precast Terrazo Tiles	NITCO, Hindustan.
30	Precast Chequered Tiles	NITCO, Hindustan, INDO, Bharat, Poddar.
31	Non Metallic Floor Surface Hardners	Ironite, Hardonite, FOSROC, SIKA, BASF, CICO, Pidilite.
32	Precast Cement Concrete Tiles	NITCO, Hindustan, INDO, Ultra, NTC, Poddar.
33	Factory made Cement Concrete Interlocking Paver Blocks	Earth Pavers Hyd. Pvt. Ltd., NITCO (Rockard), Bharat (Nilsan), Classic Tiles.
34	Grass Paver	Unistone, Ultra.
35	Glass Mosaic Tiles	Palladio, Coral, Mridul, Bisazza

Signature of the Contractor

36	PVC Flooring	LG Hausys, Ger Flor, Armstrong .
37	High Density Fibre (HDF) Pre-laminated Flooring boards	Pergo, Armstrong.
38	Unglazed Heavy Duty Vitrified Tiles	Somany (Dura Gres), Kajaria (Pavigres).
39	Unglazed Heavy Duty Paver/Parking Tiles	Somany (Dura Stone), Johnson (Endura),
40	Clay Tiles on Roof	Kenjai, Johnson, Common Wealth Trust (Ind) Ltd
41	Tile Adhesives	Laticrete, ,Ardex Endura, Weber, Roff. SIKA, Ferrous.
42	Grout Compound/ Epoxy Grouts	Laticrete, Ardex Endura, Weber, Fosroc, Pidilite, SIKA, Ferrous, BASF, CICO.
43	Epoxy Motor	Fosroc, SIKA, BASF
44	Water Proofing Compound	Fosroc, CICO, SIKA, Pidilite, , BASF, Accoproof, Ardex Endura.
45	Damp Proof Material	Duraseal, Acco-proof, Impermo
46	Actactic Polypropylene (APP) Modified Water Proof Membrane	S T P, Bitumat Co. Ltd., Pidilite, Hydrotech Ltd.
47	Admixtures / Platisizers	Fosroc, CICO, SIKA, BASF, MC
48	Ethylene Propylene Diene Monomer (EPDM) Gasket	Hanu /Anand
49	Aluminium Extruded sections	Jindal, Hindalco, Indian Aluminium Co.
50	Polyester Powder Coating	Nerolac, Berger, Akzonobel, Jotun
51	Poly Sulphide Sealant	Pidilite, Tuffseal, Choksey chemicals.
52	Cement Based Wall putty	Birla Wall Care, J.K. Wall putty, Berger Paints , Asian Paints.
53	Paints/ Primer / Acrylic Emulsion (Premium Quality)	ICI Dulux, Asian Paints, Berger, Nerolac .
54	Melamine Polish	Asian Paints, Melamyne Gold Wudfin of Pidilite Industries, Timbertone of ICI Dulux.
55	Water Proofing Cement Paint	Snowcem India, ICI Dulux, Berger, Asian.
56	PU Enamel Metallic Paints on MS Structure & Epoxy paints (Premium Quality)	SKK, Akzonobel, Asian, Berger, MRF.
57	Calcium Silicate False Ceiling Tiles	Aerolite Co, Hilux, Armstrong
58	Gypsum Board False Ceiling Tiles	Saint Gobain, Lafarge, Amstrong Co.
59	Mineral Fibre Board False Ceiling Tiles	Armstrong , Decosonic.
60	Rockwool / Glasswool insulation.	Twigafiber, Llyod Insulation, Supreme.
61	False Flooring System .	Kebao, Pinnacle, Access Floor System
62	Anodised / Powder Coated Aluminium Fittings / Fixtures-	Everite, Jyoti, Shakti, Sigma (BIS mark), Hardima.
63	Stainless Steel Pipes (Railing)	Jindal Stainless Steel Ltd., Connect Architectural Products Pvt. Ltd.

Signature of the Contractor

64	Stainless Steel Wire Mesh	Champion Make, GKD.
65	Float / Plain / Tinted / Tempered / Toughened Glass.	Modi, Saint Gobain, Asahi, Atul, Glaverbel, Pilkington .
66	Mirror Glass.	Modi Guard, Atul, Asahi, Goldenfish.
67	Hydraulic Door Closers / Floor Springs	Godrej, Hardwyn, Everite, Dorma, Dorset, Magnum, Kich.
68	Steel Nuts, Bolts and Screws-	Atul, Hilti, Kundan, Priya .
69	Ball Bearing Hinges and Spring Hinges	Dorma, Hafele, Geze, Dorset, Magnum.
70	Stainless Steel Screws	Kundan, Arrow, Nettlefold, GKW.
71	Clamping System Using Dash / Anchor Fastners.	Hilti, Fischer,Bosch, Canon.
72	Locks in Furniture Cabinets.	Hettich, Blum, Hafel, Godrej, Link, Harrison.
73	Four Point / Multi Point Locking Handle.	Hefele, Alu-Alfa, Geze, Dorma, Godrej .
74	Stainless Steel Friction stay hinges	Hafele, Earl Bihari
75	Door closer lock / Panic exit device	Ingersoll Rand, Dorma, Monarch.
76	Door Coordinator	UL Listed, Monarch.
77	Precoated Galvolume Iron Profile Sheets.	Pennar, TATA Blue scope, NCL.
78	Multi Walled PolyCarbonate Roofing Sheets	Lexan, GE
79	Bitumen	Indian Oil, Hindustan Petroleum Corporation.
80	Aluminium Composite Panels (ACP)	Alstrong, Alucobond, Aluplex, Alubond.
81	Structural Glazing	Modi, Saint Gobain, Asahi, Glaverbel.
82	Structural and Weather Sealants (Silicon)	Dow Corning, Wacker., GE, BASF
83	Adhesive Tape	Norton
84	Spider Patch Fittings for Structural Glazing	Dorma, Sevax, Kich, Ozone, Hafele.
85	G.I. Pipes -	TATA, Jindal, Zenith, Hissar .
86	G.I. Fittings	HB, R Brand, Unik, ICS.
87	Gun Metal Valves / Non Return Valves	Zoloto, Leader, Sant.
88	C.I. Sluice Valves (Double Flanged)	Zoloto, Leader, SANT, Kirloskar, IVC, Burn.
89	PTMT fittings/ fixtures	Prayag, Shakti, pearl.
90	C.P. Brass fittings/ fixtures	Jaquar , Marc, Plumber, ESS ESS, TOTO, Parko, Nova , Grohe.
91	C.P.V.C pipes & specials	Supreme , Prince , Sudhakar, Ashirvad, Astral,, Finolex, Flowguard.
92	UPVC Pipes & Fittings.	Supreme , Prince , Sudhakar, Ashirvad, Astral,, Finolex.
93	Poly Propylene Random Co polymer (PPR) Pipes & Specials	SFMC, Victus, Supreme , Prince.

Signature of the Contractor

94	Centrifugally Cast (spun) Pipes & Fittings (Sanitary Pipes)/ Centrifugally Cast iron hub less pipes	NECO , HEPCO, SKF, Bengal Iron Corporation (BIC) / NECO, kepsilan
95	Centrifugally Cast (spun) Pipes (LA) & Fittings (Water Supply Pipes) /	Electro steel, Kesoram, LANCO Industries, RIF, NECO./ NECO, kepsilan
96	Vitreous China Sanitary ware	Parryware, Neycer, Hindware, Cera, Jaquar.
97	Stainless Steel Sinks	Nirali, Hindware, Johnson, Neelkanth,
98	Fire Clay Sinks	Sunfire, Parryware, Hindware.
99	Sensor Based Auto Flush Systems	A O S Systems, TOTO, Parryware, Hindware, Grohe, Kochler.
100	PVC Water Storage Tanks	Sintex, Uniplast, Durocon, Polycon, Supreme.
101	Float Valve (Ball Valve)	Prayag, Leader, Zoloto,
102	Water Meter	Zoloto, Leader, Dashmesh.
103	RCC Non Pressure (NP-2) Pipes -	Indo., Hindustan, Balaji Pipe Industries, Indian Hume Pipes Ltd.
104	Factory Made SFRC (RCC) Manhole Covers	Indo, Balaji Pipe Industries, Supreme.
105	CI Manhole Covers	SKF, HIF, Neco, Bengal Iron Corporation (BIC).
106	Coupler for reinforcement bars	LOKPAL Industries – Noida, Shree ISPAT Traders – Jaipur, Trimurthi Engg. & Fab Works – Nagpur, National cutting Tools Sai Couplings – Pune, SPROCS Rebar Couplings Kanva Trading – Chennai.

28.2 ELECTRICAL

1. L.T. Power Cable : Finolex/ Universal/ Fort Gloster/ Polycab
2. H.T. XLPE Cable :Universal/Polycab/Havells/Gloster/Asian Asian
3. Multi stand flexible copper wires: finolex/Anchor/Havells/Polycab.
4. Modular switch, socket power : TOYONA (Accura) Anchor (Roma) Socket TV Telephone Socket
5. Modular piano type switch : TOYONA (Accura) Anchor (Roma)
6. Fan regulators : TOYONA (Accura)
7. Cable Glands : Comet / Jainson
8. Cable lungs copper : Dowells/ Jainson
   L.T.Switch Gear &
9. MCCB :Schneider/MDS/Semiens/C & S
10. MCB'sRMCB's etc. : Protec/ MDS/Semiens/C & S
11. Protection Relays : Alshthom/Segc/Telimachine
12. Panel meters 96 sqm(Digital) : Enercon/Neptune
    Panel meters 144 sqm(
13. Analong) : AE/MECO

14. Indication lamps led type/ Binay/Schnieder Push buttons :
15. Sector Switches : Kaycee/Salzer/TOYOMA (Accura)
16. Distribution Boards : Protec/MDS
17. PVC pipes : Sudhakar/Finolex/Mercury
18. PVC Fittings : Prime/Mercury
19. Tube light fitting : Crompton/Philips/Bajaj
20. Switches/Sockets : Anchor (Rona),TOYOMA (Accura)/ Bajaj
21. Electronic Fan regulators : Anchor (Rona),TOYOMA (Accura)
22. Telephone wires : Mazda
23. T.V.Wire : Finolex/Anchor
24. CFL Lamps & Fittings : Bajaj/Philips/Crompton
25. Ceiling fans : Crompton/Bajaj/Orient/Usha
26. Exhaust fans : Crompton/GEC/Khaitan
27. Sodium vapor lamps & fittings : Bajaj/Philips/Crompton
28. Energy meter : Havells/ L & T/ECE
29. Transformers : Kirloskar. Crompton Grieves/ Indotech/Alstom/PETE
30. Vacuum circuit breakers : Bieccola wire/ Alshthom/CG
31. Cubical Electrical panels/ Bus ducts/Generator Panel : Any fabrication with CPRI approved and ISO 9002 certification company/ Manufacturer.

Signature of the Contractor

Name of work: "Providing and laying of damaged drain lines at A-(31 to 37) Quarters to Septic Tank" in the University of Hyderabad Campus.

1) The estimates amount is inclusive of GST.
2) The bidder should quote basic rates exclusive of GST and quote GST percentage separately; GST should be revised from time to time.

S.No	DSR No.	Description of items	Qty	Unit	Basic Rate in Figures to be entered by the Bidder without GST	Add: GST (%)	Total Amount without GST	Total Amount with GST	Total Amount with GST in words
1	2.31	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50m outside the periphery of the area cleared.	1000.00	Sqm					
2	2.10	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth up to 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m :							
	2.10.1	All kinds of soil							
	2.10.1.3	Pipes, cables etc. exceeding 300 mm dia but not exceeding 600 mm.	450.00	Rmt					

3	15.2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.							
	15.2.2	Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	20.00	Cum					
4	19.24	Dismantling of manhole including R.C.C. top slab, C.I. cover with frame, including stacking of useful materials near the site and disposal of unserviceable materials within 50 m lead as per direction of Engineer-in-Charge :							
	19.24.1	Rectangular manhole 90x80 cm and 45 cm deep	15.00	Each					
5	19.1	Providing, laying and jointing glazed stoneware pipes class SP-1 with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc. complete :							
	19.1.2	150 mm diameter	250.00	Rmt					
6	19.2	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) all-round S.W. pipes including bed concrete as per standard design :							
	19.2.2	150 mm diameter S.W. pipe	250.00	Rmt					
7	19.6	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :							
	19.6.4	300 mm dia. R.C.C. pipe	200.00	Rmt					

8	19.32	Making soak pit 2.5 m diameter 3.0 metre deep with 45 x 45 cm dry brick honey comb shaft with bricks and S.W. drain pipe 100 mm diameter, 1.8 m long complete as per standard design.							
	19.32.1	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	1.00	Each					
9	19.9	Constructing brick masonry circular type manhole 0.91 m internal dia at bottom and 0.56m dia at top in cement mortar 1:4 (1 cement : 4 coarse sand), inside cement plaster 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with a floating coat of neat cement, foundation concrete 1:3:6 mix (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size), and making necessary channel in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement, all complete as per standard design :							
	19.9.1	0.91 m deep with S.F .R.C. cover and frame (heavy duty , HD-20 grade designation) 560 mm internal diameter conforming to I.S. 12592, total weight of cover and frame to be not less than 182 kg., fixed in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including centering, shuttering all complete. (Excavation, foot rests and 12mm thick cement plaster at the external surface shall be paid for separately) :							
	19.9.1.1	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	45.00	Each					

10	19.10	Extra depth for circular type manhole 0.91 m internal dia (at bottom) beyond 0.91 m to 1.67 m							
	19.10.1	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	25.00	Rmt					
11	19.4	Providing and fixing square-mouth S.W. gully trap class SP-1 complete with C.I. grating brick masonry chamber with water tight C.I. cover with frame of 300 x300 mm size (inside) the weight of cover to be not less than 4.50 kg and frame to be not less than 2.70 kg as per standard design:							
	19.4.1	100x100 mm size P type							
	19.4.1.1	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	25.00	Each					
12	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :							
a	4.1.3	1:2:4 (1 cement : 2 coarse sand(zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	15.00	Cum					
b	4.1.10	1:5:10 (1 cement : 5 coarse sand (zone-III) derived from natural sources : 10 graded stone aggregate 40 mm nominal size derived from natural sources)	10.00	Cum					

13	19.21	Making connection of drain or sewer line with existing manhole including breaking into and making good the walls, floors with cement concrete 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) cement plastered on both sides with cement mortar 1:3 (1 cement : 3 coarse sand) finished with a floating coat of neat cement and making necessary channels for the drain etc. complete :							
	19.21.1	For pipes 100 to 250 mm diameter	15.00	Each					
14	4.17	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation leveling & dressing & finishing the top smooth.	200.00	Sqm					
15	MR	Providing and fixing at all floors Type B - SWR PVC pipes including all fittings such as plain and door bends, tees, elbows, equal and unequal junctions, heel rest sanitary bends, collars etc.(except floor traps/P traps) confirming to IS13592, IS 14735, including jointing with solvent and providing necessary supports, clamps/MS brackets at specified intervals. The joints of pipe and fittings shall be of drip seal jointing in exposed areas like in shafts etc. and pasted type (solvent) for all other locations all complete and as per directions of	50.00	Rmt					

		Engineer - in - charge.MS brackets shall be paid separately. 110 mm SWR - B Pipe							
16	MR	Providing and fixing at all floors Type B - SWR PVC pipes including all fittings such as plain and door bends, tees, elbows, equal and unequal junctions, heel rest sanitary bends, collars etc.(except floor traps/P traps) confirming to IS13592, IS 14735, including jointing with solvent and providing necessary supports, clamps/MS brackets at specified intervals. The joints of pipe and fittings shall be of drip seal jointing in exposed areas like in shafts etc. and pasted type (solvent) for all other locations all complete and as per directions of Engineer - in - charge.MS brackets shall be paid separately. 75 mm SWR - B Pipe	50.00	Rmt					

Sd/-

Signature of the Contractor **University Engineer** **Executive Engineer (A/C)** **D'M Grade-I**