UNIVERSITY OF HYDERABAD
{Establishment by the act of the Parliament in 1974}
Gachibowli, Hyderabad
University Works Department,
Ph no.040-23132306/040-23101208
E-mail: aet.uohyd@gmail.com

E-QUOTATION

FOR

NOTICE INVITING QUOTATION (NIQ)

Notice Inviting e-Tender No. & Date	**UH/ENGG/UWD/2025-26/29**
Name of the work	**Name of work: "Renovation of Post Office Building" in UoH Campus.**
Estimated Cost	**Rs. 4,37,200/- (Inclusive of GST)**
Earnest Money Deposit (EMD)	**EMD @ 2% of the estimated cost i.e., Rs. 8,744/- (DD or Bank Guarantee)**
Time Allowed	**21 Days**
Date of start of Bid Submission	**18.02.2026, 2.30 PM**
Last date & Time for Submission of Bids	**24.02.2026, 3.00 PM**
Date & Time of Opening of Technical Bids	**25.02.2026, 3.00 PM**
Date & Time of Opening of Financial Bids	**Will be intimated to technically qualified bidders in due course of time through Central Public Procurement portal.**
Submission of hard copies of EMD	The original EMD should be submitted in the University Works Department, University of Hyderabad, Gachibowli, P.O. Central University, HYDERABAD – 500046 upto 3.00 PM on .02.2026.

Sd/-
EXECUTIVE ENGINEER(A/C)

Sd/-
UNIVERSITY ENGINEER

General Conditions & Eligibility Criteria for Submission of Quotation:-

1. The contractor/bidder shall be a registered contractor under appropriate class and should produce definite proof of registration by state or central government departments or state/central autonomous bodies or undertakings.

2. The bidder should also submit self-attested copies of relevant IT returns, PAN no, valid Registration Certificate and Experience certificate having successfully completed Civil works of required value and shall sign all the pages of Technical & price bid without fail.

3. The bidders except Micro and Small Medium Enterprises (MSEs) notified under MSME, Procurement Policy (as per Rule 170 of GFR 2017), should pay EMD of 2% of Estimated Cost drawn in favor of "Finance Officer, University of Hyderabad" payable at Hyderabad.

4. Statutory taxes/Deductions shall be made as per rules.

5. The Competent Authority on behalf of the University of Hyderabad does not bind itself to accept the lowest or any other quotation and reserves to itself to reject any or all the quotations received without assigning any reason. All quotations in which any of the prescribed condition is not fulfilled or any condition including that of conditional rebate put forth by the tenderer shall be summarily rejected.

6. Work to be carried out in the presence and under supervision of UWD Engineers.

7. The site will be made available as and when required for execution of work.

8. Canvassing whether directly or indirectly, in connection with tenders is strictly prohibited and the quotations submitted by the contractors who resort to canvassing will be liable for rejection.

9. The Contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's compensation Act.

10. The Work Order can be cancelled and the work can be stopped at any time by the Engineer-in-charge of the work or by any officer superior to him in authority.

11. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.

12. If water is supplied by the University, 1% of the actual cost of water consuming items will be recovered from work bills.

13. Seigniorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.

Signature of the Contractor

14. The contractor shall permit the University to **deduct 10% of the value of each work bill towards Security Deposit** including performance bank guaranty which shall be released 60 days after expiry of defects liability period. The deposit is liable to be forfeited to the University for Non-rectification of defects pointed out to him during execution of work/Defect Liability Period.

15. Defect liability period of **21 Days** commences from the date of satisfactory completion of work.

16. For delay or slow progress of work, relevant clauses of CPWD manual will be invoked and penalty Will be levied. If work is delayed, the University reserves the right to foreclose / rescind the work, and to get the balance work done through any other contractor, at his risk and cost and the Contractor shall have no right to claim any compensation on this account.

17. In case, the work cannot be started due to reasons not within the control of the contractor within $1/8^{th}$ of the stipulated time for completion of work, either party may close the contract. In such eventuality, the Earnest Money Deposit of the contractor shall be refunded, but no payment on account of interest, loss of profit or damages etc. shall be payable at all.

18. The Contractor should ensure while executing the work that there should be no deviation / variation beyond permissible limit.

19. The work of each item is to be executed in consultation with the user Department.

20. In case of execution of any extra items / additions, alterations / changes, the total amount may not exceed sanctioned amount; if it exceeds, prior approval is be taken from the User Department and Competent Authority.

21. Assistant Engineer (Civil)/Assistant Engineer (Electrical) has to enclose the work completion certificate and **No claim certificate** from the contractor to the final bill.

22. Further details if any can be had from the Office of the University Engineer, University of Hyderabad, Hyderabad-5000 046 during working hours.

23. GST invoice form should be filled and submitted along with the bill.

24. Labour engaged and working equipment brought to site by the contractor shall be recorded in the UoH Security main gate and necessary gate pass obtained before entering in to the premises.

Signature of the Contractor

LIST SHOWING PREFERRED BRANDS/MANUFACTURERS/MAKE

NOTE: - 1) A List of Preferred Brand Names of Various Materials / Products are shown below for usage in execution of Work. However, Approved equivalent material of any other Specialized Companies / Firms may also be used, in case it is established that the Brands Specified below are not available in the market and subject to Approval of the alternate Brand by the Engineer In charge.

2) It must be ensured, in general, that all materials to be used in the works shall bear BIS Certification mark. In cases where for a particular material/product, BIS Certification Mark is not available, then the material proposed to be procured can be used subject to the condition that it should conform to CPWD Specifications and relevant BIS codes. In such cases written approval of the Engineer-in -Charge shall be obtained before use of such material in their works.

3) The list given below does not absolve the Executing Agency from their responsibility for using these products. It is only after, they are satisfied about the quality and performance, the products shall be used. To achieve this, proper check on the quality of the product, actually to be used, should be exercised.

S.No	Product	Make
1	Ordinary Portland Cement	ACC, Ultratech, Vikram, Shree Cement, Ambuja, Jaypee Cement, Century Cement, JK Cement, Penna Cement , Bharathi Cement, Maha , Nagarjuna and Brands Approved by CE(SZ)II,CPWD,Hyderabad.
2	Portland Pozzolana Cement	
3	White Cement	Birla, J.K. White, Travancore
4	Reinforcement steel – (Primary Producers)	RINL, SAIL, TATA STEEL Ltd., JSW STEEL Ltd., JINDAL STEEL & POWER Ltd., Shyam produced by M/s.Shyam Steel Industries Ltd and Manufacturers approved by Spl.DG(SR),CPWD,Chennai
5	Ready Mix Concrete (RMC)	Ultra Tech, ACC, RMC Ready Mix (India), Nuvoco Vistas Corporation Ltd., (formally known as Lafarge India Ltd.), RMC by M/s Aparna Enterprises limited,Hyderabad, RDC Concrete (India) Pvt. Ltd and additional firms approved by CE, SZ-II, CPWD, Hyderabad.
6	Pulverized Stone Sand/ Crushed Stone Sand (Manufactured Sand)	Rank Enterprises, Robo Sand.
7	Polymer based Curing Compounds	FOSROC, SIKA, BASF
8	Structural Steel Sections	TATA, SAIL,RINL, JINDAL Steel & Power Ltd., J SW
9	Hollow Steel Tube Sections	TATA, Jindal, Apollo
10	Fly ash Cement Bricks	KSP Industries, Prakash International Ltd, NUBRIC.

Signature of the Contractor

11	Autoclaved Aerated Concrete Blocks (AAC)	M/s. Hyderabad Industries Ltd., M/s. Ultra Tech India Limited, M/s. Siporex India Ltd., NCL, NUBRIC.
12	Binding Wire	TATA, JSW
13	Factory Made Cement Concrete Cover Blocks	A.S.R. Cover Blocks, Stand alone Universal Concrete Cover Blocks
14	RCC Door Frames	Ventura, Bothra.
15	Flush Door Shutters	Raavela Doors, Indian Timber Products, Kitply,
16	Fire Check / Rated Doors	Navair, Godrej, Shaktimet, Kenwood, MPP Schodders.
17	Smoke Seal Strip	Promat, Astro flame
18	Plain / Prelaminated Particle Board	ECO Board, TESA Action Co., Kitlam, Archid ply, Century
19	Ply wood / Laminate	Kitply, Centuryply, Greenply, Merino, Sonear (Donear), Formica, Archidply, Royal touch .
20	Natural wood Veneers	Kitply, Centuryply, Sonear (Donear), Greenply Archidply, Durain, National Action Tesa, Anchor.
21	Adhesive / Glue	Pidilite, Dunlope, Sika, Fosroc, Vamorganic.
22	Steel Windows/ Pressed Steel Frames	Madhu Industries, (Bengaluru), San Harvic, NCL
23	Cement Bonded Particle Board	BISON Boards of NCL.
24	PVC Door Frames & Shutters	Rajshri Plastiwood, Sintex.
25	FRP Door Frames & Shutters	Meena Fibre Glass, Duroplast, Cactus, Polyline.
26	UPVC Windows	Fenesta, Kommerling , Rehau, Wintech, LG, Encraft – Madhu Industries, Polywood.
27	Ceramic Floor /Dado Tiles	Somany, Johnson, Kajaria, Orient, Bell, RAK, Asian, NITCO, AGL tiles.
28	Vitrified Tiles	Somany, Johnson, Kajaria, Orient Bell Ltd, RAK, Vitero brand Aparna tiles
29	Precast Terrazo Tiles	NITCO, Hindustan, Modern
30	Precast Chequered Tiles	NITCO, Hindustan, INDO, Bharat, Poddar.
31	Non Metallic Floor Surface Hardners	Ironite, Hardonite, FOSROC, SIKA, BASF, CICO, Pidilite.
32	Precast Cement Concrete Tiles	NITCO, Hindustan, INDO, Ultra, NTC, Poddar.
33	Factory made Cement Concrete Interlocking Paver Blocks	Earth Pavers Hyd. Pvt. Ltd., NITCO (Rockard), Bharat (Nilsan), Classic Tiles.
34	Grass Paver	Unistone, Ultra.
35	Glass Mosaic Tiles	Palladio, Coral, Mridul, Bisazza

Signature of the Contractor

36	PVC Flooring	LG Hausys, Ger Flor, Armstrong .
37	High Density Fibre (HDF) Pre-laminated Flooring boards	Pergo, Armstrong.
38	Unglazed Heavy Duty Vitrified Tiles	Somany (Dura Gres), Kajaria (Pavigres).
39	Unglazed Heavy Duty Paver/Parking Tiles	Somany (Dura Stone), Johnson (Endura),
40	Clay Tiles on Roof	Kenjai, Johnson, Common Wealth Trust (Ind) Ltd
41	Tile Adhesives	Laticrete, ,Ardex Endura, Weber, Roff. SIKA, Ferrous.
42	Grout Compound/ Epoxy Grouts	Laticrete, Ardex Endura, Weber, Fosroc, Pidilite, SIKA, Ferrous, BASF, CICO.
43	Epoxy Motor	Fosroc, SIKA, BASF
44	Water Proofing Compound	Fosroc, CICO, SIKA, Pidilite, , BASF, Accoproof, Ardex Endura.
45	Damp Proof Material	Duraseal, Acco-proof, Impermo
46	Actactic Polypropylene (APP) Modified Water Proof Membrane	S T P, Bitumat Co. Ltd., Pidilite, Hydrotech Ltd.
47	Admixtures / Platisizers	Fosroc, CICO, SIKA, BASF, MC
48	Ethylene Propylene Diene Monomer (EPDM) Gasket	Hanu /Anand
49	Aluminium Extruded sections	Jindal, Hindalco, Indian Aluminium Co.
50	Polyester Powder Coating	Nerolac, Berger, Akzonobel, Jotun
51	Poly Sulphide Sealant	Pidilite, Tuffseal, Choksey chemicals.
52	Cement Based Wall putty	Birla Wall Care, J.K. Wall putty, Berger Paints , Asian Paints.
53	Paints/ Primer / Acrylic Emulsion (Premium Quality)	ICI Dulux, Asian Paints, Berger, Nerolac .
54	Melamine Polish	Asian Paints, Melamyne Gold Wudfin of Pidilite Industries, Timbertone of ICI Dulux.
55	Water Proofing Cement Paint	Snowcem India, ICI Dulux, Berger, Asian.
56	PU Enamel Metallic Paints on MS Structure & Epoxy paints (Premium Quality)	SKK, Akzonobel, Asian, Berger, MRF.
57	Calcium Silicate False Ceiling Tiles	Aerolite Co, Hilux, Armstrong
58	Gypsum Board False Ceiling Tiles	Saint Gobain, Lafarge, Amstrong Co.
59	Mineral Fibre Board False Ceiling Tiles	Armstrong , Decosonic.
60	Rockwool / Glasswool insulation.	Twigafiber, Llyod Insulation, Supreme.
61	False Flooring System .	Kebao, Pinnacle, Access Floor System
62	Anodised / Powder Coated Aluminium Fittings / Fixtures-	Everite, Jyoti, Shakti, Sigma (BIS mark), Hardima.
63	Stainless Steel Pipes (Railing)	Jindal Stainless Steel Ltd., Connect Architectural Products Pvt. Ltd.

Signature of the Contractor

64	Stainless Steel Wire Mesh	Champion Make, GKD.
65	Float / Plain / Tinted / Tempered / Toughened Glass.	Modi, Saint Gobain, Asahi, Atul, Glaverbel, Pilkington .
66	Mirror Glass.	Modi Guard, Atul, Asahi, Goldenfish.
67	Hydraulic Door Closers / Floor Springs	Godrej, Hardwyn, Everite, Dorma, Dorset, Magnum, Kich.
68	Steel Nuts, Bolts and Screws-	Atul, Hilti, Kundan, Priya .
69	Ball Bearing Hinges and Spring Hinges	Dorma, Hafele, Geze, Dorset, Magnum.
70	Stainless Steel Screws	Kundan, Arrow, Nettlefold, GKW.
71	Clamping System Using Dash / Anchor Fastners.	Hilti, Fischer,Bosch, Canon.
72	Locks in Furniture Cabinets.	Hettich, Blum, Hafel, Godrej, Link, Harrison.
73	Four Point / Multi Point Locking Handle.	Hefele, Alu-Alfa, Geze, Dorma, Godrej .
74	Stainless Steel Friction stay hinges	Hafele, Earl Bihari
75	Door closer lock / Panic exit device	Ingersoll Rand, Dorma, Monarch.
76	Door Coordinator	UL Listed, Monarch.
77	Precoated Galvolume Iron Profile Sheets.	Pennar, TATA Blue scope, NCL.
78	Multi Walled PolyCarbonate Roofing Sheets	Lexan, GE
79	Bitumen	Indian Oil, Hindustan Petroleum Corporation.
80	Aluminium Composite Panels (ACP)	Alstrong, Alucobond, Aluplex, Alubond.
81	Structural Glazing	Modi, Saint Gobain, Asahi, Glaverbel.
82	Structural and Weather Sealants (Silicon)	Dow Corning, Wacker., GE, BASF
83	Adhesive Tape	Norton
84	Spider Patch Fittings for Structural Glazing	Dorma, Sevax, Kich, Ozone, Hafele.
85	G.I. Pipes -	TATA, Jindal, Zenith, Hissar .
86	G.I. Fittings	HB, R Brand, Unik, ICS.
87	Gun Metal Valves / Non Return Valves	Zoloto, Leader, Sant.
88	C.I. Sluice Valves (Double Flanged)	Zoloto, Leader, SANT, Kirloskar, IVC, Burn.
89	PTMT fittings/ fixtures	Prayag, Shakti, pearl.
90	C.P. Brass fittings/ fixtures	Jaquar , Marc, Plumber, ESS ESS, TOTO, Parko, Nova , Grohe.
91	C.P.V.C pipes & specials	Supreme , Prince , Sudhakar, Ashirvad, Astral,, Finolex, Flowguard.
92	uPVC Pipes & Fittings.	Supreme , Prince , Sudhakar, Ashirvad, Astral,, Finolex.
93	Poly Propylene Random Co polymer (PPR) Pipes & Specials	SFMC, Victus, Supreme , Prince.

Signature of the Contractor

94	Centrifugally Cast (spun) Pipes & Fittings (Sanitary Pipes)/ Centrifugally Cast iron hub less pipes	NECO , HEPCO, SKF, Bengal Iron Corporation (BIC) / NECO, kepsilan
95	Centrifugally Cast (spun) Pipes (LA) & Fittings (Water Supply Pipes) /	Electro steel, Kesoram, LANCO Industries, RIF, NECO./ NECO, kepsilan
96	Vitreous China Sanitary ware	Parryware, Neycer, Hindware, Cera, Jaquar, TOTO, Duravit.
97	Stainless Steel Sinks	Nirali, Kaff, Hindware, Johnson, Signature, Neelkanth, Cobra, Diamond.
98	Fire Clay Sinks	Sunfire, Parryware, Hindware.
99	Sensor Based Auto Flush Systems	A O S Systems, TOTO, Parryware, Hindware, Grohe, Kochler.
100	PVC Water Storage Tanks	Sintex, Uniplast, Durocon, Polycon, Supreme.
101	Float Valve (Ball Valve)	Prayag, Leader, Zoloto, IBP, Arco.
102	Water Meter	Zoloto, Leader, Dashmesh.
103	RCC Non Pressure (NP-2) Pipes -	Indo., Hindustan, Balaji Pipe Industries, Indian Hume Pipes Ltd.
104	Factory Made SFRC (RCC) Manhole Covers	Indo, Balaji Pipe Industries, Supreme.
105	CI Manhole Covers	SKF, HIF, Neco, Bengal Iron Corporation (BIC).
106	Coupler for reinforcement bars	LOKPAL Industries – Noida, Shree ISPAT Traders – Jaipur, Trimurthi Engg. & Fab Works – Nagpur, National cutting Tools Sai Couplings – Pune, SPROCS Rebar Couplings Kanva Trading – Chennai.

Signature of the Contractor

Name of work: "Renovation of Post Office Building" in the University of Hyderabad Campus.

1) The estimates amount is inclusive of GST.

2) The bidder should quote basic rates exclusive of GST and quote GST percentage separately; GST should be revised from time to time.

S.No	DSR No.	Description of items	Qty	Unit	Basic Rate in Figures to be entered by the Bidder without GST	Add: GST (%)	Total Amount without GST	Total Amount with GST	Total Amount with GST in words
1	14.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-charge.							
	14.1.1	With cement mortar 1:4 (1 cement : 4 fine sand).	21.00	Sqm					
2	13.88	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	517.22	Sqm					
3	13.83	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre. of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.							
	13.83.2	Two coats.	517.22	Sqm					

4	6.4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :							
	6.4.2	Cement mortar 1:6 (1 cement : 6 coarse sand)	0.87	Cum					
5	13.12	18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement: 5 coarse sand) and a top layer 6 mm thick cement plaster 1:3 (1 cement: 3 coarse sand) finished rough with sponge.	10.00	Sqm					
6	2.10	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth up to 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m :							
	2.10.1	All kinds of soil							
	2.10.1.2	Pipes, cables etc. exceeding 80 mm dia. but not exceeding 300 mm dia	50.00	Rmt					
7	19.4	Providing and fixing square-mouth S.W. gully trap class SP-1 complete with C.I. grating brick masonry chamber with water tight C.I. cover with frame of 300 x300 mm size (inside) the weight of cover to be not less than 4.50 kg and frame to be not less than 2.70 kg as per standard design:							
	19.4.2	150 x 100 mm size P type.							

	19.4.2.1	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	2.00	Each					
8	18.76	Cutting holes up to 30x30 cm in walls including making good the same:							
	18.76.1	With common burnt clay F.P.S. (non modular) bricks.	2.00	Each					
9	19.6	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :							
	19.6.3	250 mm dia. R.C.C. pipe	50.00	Rmt					
10	19.7	Constructing brick masonry manhole in cement mortar 1:4 (1 cement : 4 coarse sand) with R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design :							
	19.7.1	Inside size 90x80 cm and 45 cm deep including C.I. cover with frame (light duty) 455x610 mm internal dimensions, total weight of cover and frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg) :							

	19.7.1.1	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	3.00	Each					
11	4.17B	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 manufactured sand derived from Recycled Concrete Aggregate (RCA) : 6 graded stone aggregate 20 mm nominal size Recycled Concrete Aggregate (RCA) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation leveling & dressing & finishing the top smooth.	10.00	Sqm					
12	16.42	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete.	20.00	Cum					
13	14.89	Providing and fixing APP (Atactic Polypropylene Polymer) modified prefabricated five layer 2 mm thick water proofing membrane , black finished reinforced with glass fibre matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 litre/sqm by the samemembrance manufacture of density at 25°C, 0.87 - 0.89 kg/ litre and viscocity 70 - 160 cps. Over the primer coat the layer of membrane shall be laid using Butane torch and sealing all joints etc., and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under : Joint strength in longitudinal and transverse direction at 23°C as 350/300							

		N/ 5 cm. Tear strength in longitudinal and transverse direction as 60/80N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D - 5147. The laying of membrane shall be got done through the authorised applicator of the manufacture of membrane.							
	14.89.1	2mm (for corrugated roof sheets)	64.00	Sqm					
14	15.12	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :							
	15.12.1	Of area 3 sq. metres and below	2.00	Each					
15	9.21	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters:							
	9.21.2	30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	6.30	Sqm					
16	9.96	Providing and fixing aluminium sliding door bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with nuts and screws etc. complete :							
	9.96.1	300x16 mm	3.00	Each					

17	9.100	Providing and fixing aluminium handles ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :							
	9.100.1	125 mm	6.00	Each					
18	9.97	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :							
	9.97.4	150x10 mm	6.00	Each					
19	12.41	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.							
	12.41.1	75 mm diameter	4.00	Rmt					
20	12.42	Providing and fixing on wall face unplasticised - PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipes conforming to IS 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion.							
a	12.42.3	Single tee with door							
	12.42.3.1	75x75x75 mm	2.00	Each					
b	12.42.5	Bend 87.5°							
	12.42.5.1	75 mm bend	4.00	Each					

21	17.60	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors :							
	17.60.1	100 mm inlet and 100 mm outlet							
	17.60.1.2	Sand Cast Iron S&S as per IS: 1729.	2.00	Each					
22	15.23	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.							
	15.23.1	For thickness of tiles 10 mm to 25 mm	4.62	Sqm					
23	11.39	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300mm or more (thickness to be specified by the manufacturer), of 1stquality conforming to IS : 15622, of approved make, in colours White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4(1 Cement: 4 Coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joints with white cement and matching pigments etc., complete.	4.62	Sqm					
24	14.82	Dismantling W.C. Pan of all sizes including disposal of dismantled materials i/c malba all complete as per directions of Engineer-in- Charge.	1.00	Each					
25	17.1	Providing and fixing water closet squatting pan (Indian type W.C.pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with							

		manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required:							
	17.1.1	White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	1.00	Each					

Signature of the Contractor **Sd/-** **University Engineer** **Sd/-** **Executive Engineer (A/C)** **Sd/-** **D'M Grade-I**