UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Assistant Engineer

NOTE

Ref: UH/ENGG/UE/2026-27/ Date: 12.05.2026.

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **15.05.2026 at 12.00 P.M. in the Office of the University Works Department.** Hence, All the contractors are requested to remind the following details: -

Submission of Quotations: 15.05.2026 at 12.00 PM

Opening of Quotations: 15.05.2026 at 3.00 PM

S. No	Name of the work	Estimated Cost Rs.
1	Providing and fixing wiring for AC and water purifier in SB-47 Qtrs, Smart boards wiring in KV school & wiring with switch boards in A-18 qtrs building in UoH campus-Reg.	**Rs. 38,978/-**

Sd/-
Assistant Engineer (E)

Name of Work:-Providing and fixing wiring for AC and water purifier in SB-47 Qtrs, Smart boards wiring in KV school & wiring with switch boards in A-18 qtrs building in UoH campus-Reg.

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R. /MR	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	1.14	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS/HFFR PVC insulated copper conductor, single core cable in surface/recessed medium class PVC conduit as required.				
1.1	1.14.2	2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	72	mtrs	Figure:Rs_____ Words:Rupees_____ _ _____	
2	1.17	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
2.1	1.17.12	3 x 2.5 sq.mm	8	mtr	Figure:Rs_____ Words:Rupees_____ _ _____	
2.2	1.17.21	3 x 4 sq. mm	30	Mtr	Figure:Rs_____ Words:Rupees_____ _ _____	
3	1.27	Supplying and fixing of following sizes of medium class PVC conduit/Casing capping along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.				
3.1	1.21.1	20 mm	6	Mtr	Figure:Rs_____ Words:Rupees_____ _ _____	
4	1.24	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required				
4.1	1.24.1	5/6 amps switch	5	Each	Figure:Rs_____ Words:Rupees_____ _ _____	
4.2	1.24.3	15/16 A switch	4	Each	Figure:Rs_____ Words:Rupees_____ _ _____	

4.3	1.24.4	3 pin 5/6 amp socket outlet	7	Each	Figure:Rs_____ Words:Rupees_____ _ _____	
4.4	1.24.5	6 pin 15/16 A socket outlet	4	Each	Figure:Rs_____ Words:Rupees_____	
5	1.27	Supplying and fixing following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc as required.				
5.1	1.27.2	3 Module	1	Each	Figure:Rs_____ Words:Rupees_____	
5.2	1.27.4	6 Module	2	Each	Figure:Rs_____ Words:Rupees_____ _ _____	
5.3	1.27.5	8 Module	2	Each	Figure:Rs_____ Words:Rupees_____	
6	2.18	Supplying and fixing 20 amps, 240 volts, SPN industrial type, socket outlet, with 2 pole and earth, metal enclosed plug top alongwith 20 amps "C" curve, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. as required.	1	Each	Figure:Rs_____ Words:Rupees_____ _ _____	
7		Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
7.1	2.10.1	Single pole	1	Each	Figure:Rs_____ Words:Rupees_____	
8	MR	Supply and fixing of 6/16A, switch & socket combined unit with PVC box etc,. As required.	1	Each	Figure:Rs_____ Words:Rupees_____ _ _____	
		Sub Total				
		Add GST @ 18%				
		Total				

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor

SD/
Assistant Engineer

Terms & Conditions:

1. The contractor/ bidder shall be a registered contractor and should produce definite proof of appropriate class registered by state or central government departments or state/central autonomous bodies or undertakings should submit proof thereof.

2. The work should be completed within Twenty-one (21) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the

3. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.

4. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.

5. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability

6. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.

7. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.

8. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.

9. Defect liability period 6 (six) months from the date of completion of the work.

10. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.

11. A.E (E) has to enclose the work completion certificate and user department certificate along with the bill.

12. No quotation will be accepted without PAN/VAT no.

13. TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

SD/
Assistant Engineer

CC to:

1. A.E. Sub-Division (E)
2. S O (Works & Bills),
3. O.C.,
4. D.B.,