**UNIVERSITY OF HYDERABAD**
**{Establishment by the act of the Parliament in 1974}**
**Gachibowli, Hyderabad**
**University Works Department,**
**Ph no.040-23132306/040-23101208**
**E-mail: aet.uohyd@gmail.com**

**E-QUOTATION**

**FOR**

**NOTICE INVITING QUOTATION (NIQ)**

| | |
|---|---|
| **Notice Inviting e-Tender No. & Date** | **UH/ENGG/UWD/2026-27/07** |
| **Name of the work** | **Name of work:- "Supply and laying of 3.5 core x 95 sq mm UG cable from LT panel to Vertical DB in Centre for Integrated Studies (CIS)" in UoH Campus** |
| **Estimated Cost** | **Rs.1,18,826/- (Inclusive of GST)** |
| **Earnest Money Deposit (EMD)** | **EMD @ 2% of the estimated cost i.e., Rs 2376.52/- (DD or Bank Guarantee)** |
| **Time Allowed** | **02 Weeks** |
| **Date of start of Bid Submission** | **22.06.2026, 2.30 PM** |
| **Last date & Time for Submission of Bids** | **30.06.2026, 3.00 PM** |
| **Date & Time of Opening of Technical Bids** | **01.07.2026, 3.00 PM** |
| **Date & Time of Opening of Financial Bids** | **Will be intimated to technically qualified bidders in due course of time through Central Public Procurement portal.** |
| **Submission of hard copies of EMD** | The original EMD should be submitted in the University Works Department, University of Hyderabad, Gachibowli, P.O. Central University, HYDERABAD – 500046 upto 3.00 PM on 01.07.2026. |

**Sd/-**
**ASSISTANT ENGINEER (E)**

**Sd/-**
**UNIVERSITY ENGINEER**

**General Conditions & Eligibility Criteria for Submission of Quotation:-**

1. The contractor/bidder shall be a registered one under appropriate class and should produce definite proof of registration with State or Central Government Departments or State/Central Autonomous Bodies or Undertakings / Shall be registered with MSME under appropriate category.

2. The bidder should also submit self-attested copies of relevant IT returns, PAN no, valid Registration Certificate and Experience certificate having successfully completed Electrical works of required value and shall sign all the pages of Technical & price bid without fail.

3. Contractor should be Electrical License holder 'B' Grade and above.

4. Bidders should have satisfactorily completed during last 07 years ending last day of the month prior to the month in which the tenders are invited.

   (i) One Electrical Work completed **80%** of Estimated cost i.e **Rs. 95,061/- (including of GST)**

   (OR)

   (ii) Two Electrical works completed **each** costing not less **50%** of Estimated cost i.e**. Rs59,413/-including of GST)**

   (OR)

   (iii) Three Electrical works complete each costing not less than **40%** of Estimated cost i.e **Rs. 47530/- (including of GST)**Self-Attested copies of experience certificates are to be submitted.

5. Only work completed and certified by competent authority of the organization will be accepted as Experience Certificate. Certificate not issued in the name of bidder (Contractor) or issued by an authority not competent to issue such certificate will not be accepted.

6. The bidders except Micro and Small Medium Enterprises (MSEs) notified under MSME, Procurement Policy (as per Rule 170 of GFR 2017), should pay EMD of 2% of Estimated Cost drawn in favor of "Finance Officer, University of Hyderabad" payable at Hyderabad.

7. Statutory taxes/Deductions shall be made as per rules.

8. The Competent Authority on behalf of the University of Hyderabad does not bind itself to accept the lowest or any other quotations and reserves to itself the right to reject any or all the quotations received without assigning any reason. All quotations in which any of the prescribed condition is not fulfilled or any condition including those related to conditional rebate put forth by the tenderer shall be summarily rejected

9. Work to be carried out in the presence and under supervision of UWD Engineers.

10. The site will be made available as and when required for execution of work.

11. Canvassing whether directly or indirectly, in connection with tenders is strictly prohibited and the quotations submitted by the contractors who resort to canvassing will be liable for rejection.

**Signature of the Contractor**

12. The Contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's compensation Act.

13. The Work Order can be cancelled and the work can be stopped at any time by the Engineer-in-charge of the work or by any officer superior to him in authority.

14. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.

15. If water is supplied by the University, 1% of the actual cost of water consuming items will be recovered from work bills.

16. Seigniorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.

17. EMD Deposited by the bidders will be refunded to the respected bidders after completion of tendering process

18. The contractor shall permit the University to **deduct 5% of the value of each work bill towards Security Deposit** inaddition to performance guaranty which shall be released after expiry of defects liability period. The deposit is liable to be forfeited to the University for Non-rectification of defects pointed out to him during execution of work/Defect Liability Period.

19. Defect liability period of **(06) Month's** commences from the date of satisfactory completion of work.

20. For delay or slow progress of work, relevant clauses of CPWD manual will be invoked and penalty Will be levied. If work is delayed, the University reserves the right to foreclose / rescind the work, and to get the balance work done through any other contractor, at his risk and cost and the Contractor shall have no right to claim any compensation on this account.

21. In case, the work cannot be started due to reasons not within the control of the contractor within $1/8^{th}$ of the stipulated time for completion of work, either party may close the contract. In such eventuality, the Earnest Money Deposit of the contractor shall be refunded, but no payment on account of interest, loss of profit or damages etc. shall be payable.

22. The Contractor should ensure while executing the work that there should be no deviation / variation beyond permissible limit.

23. The work of each item is to be executed in consultation with the user Department.

24. In case of execution of any extra items / additions, alterations / changes, the total amount May not exceed sanctioned amount. if it exceeds, prior approval is be taken from the User Department and Competent Authority.

25. Assistant Engineer (Civil)/Assistant Engineer (Electrical) has to enclose the work completion certificate and **No claim certificate** from the contractor to the final bill.

26. Certificate of satisfactory completion of work from user department and or Engineer in charge may be obtained and enclosed to the final bill for payment.

**Signature of the Contractor**

27. Further details if any can be had from the Office of the University Engineer, University of Hyderabad, Hyderabad-5000 046 during working hours.

28. GST invoice form should be filled and submitted along with the bill.

29. Labour engaged and working equipment brought to site by the contractor shall be recorded in the UoH Security main gate and necessary gate pass obtained before entering in to the premises.

**LIST SHOWING PREFERRED BRANDS/MANUFACTURERS/MAKE**

NOTE: - 1) A List of Preferred Brand Names of Various Materials / Products are shown below for usage in execution of Work. However, Approved equivalent material of any other Specialized Companies / Firms may also be used , in case it is established that the Brands Specified below are not available in the market and subject to Approval of the alternate Brand by the Engineer In charge.

2) It must be ensured, in general, that all materials to be used in the works shall bear BIS Certification mark. In cases where for a particular material/product, BIS Certification Mark is not available, then the material proposed to be procured can be used subject to the condition that it should conform to CPWD Specifications and relevant BIS codes. In such cases written approval of the Engineer-in -Charge shall be obtained before use of such material in their works.

3) The list given below does not absolve the Executing Agency from their responsibility for using these products. It is only after, they are satisfied about the quality and performance, the products shall be used. To achieve this, proper check on the quality of the product, actually to be used, should be exercised.

| S.No | Product | Make |
|---|---|---|
| 1 | Ordinary Portland Cement | ACC, Ultratech, Vikram, Shree Cement, Ambuja, Jaypee Cement, Century Cement, JK Cement, Penna Cement , Bharathi Cement, Maha , Nagarjuna and Brands Approved by CE(SZ)II,CPWD,Hyderabad. |
| 2 | Portland Pozzolana Cement | |
| 3 | White Cement | Birla, J.K. White, Travancore |
| 4 | Reinforcement steel – (Primary Producers) | RINL, SAIL, TATA STEEL Ltd., JSW STEEL Ltd., JINDAL STEEL & POWER Ltd., Shyam produced by M/s.Shyam Steel Industries Ltd and Manufacturers approved by Spl.DG(SR),CPWD,Chennai |
| 5 | Ready Mix Concrete (RMC) | Ultra Tech, ACC, RMC Ready Mix (India), Nuvoco Vistas Corporation Ltd., (formally known as Lafarge India Ltd.), RMC by M/s Aparna Enterprises limited,Hyderabad, RDC Concrete (India) Pvt. Ltd and additional firms approved by CE, SZ-II, CPWD, Hyderabad. |
| 6 | Pulverized Stone Sand/ Crushed Stone Sand (Manufactured Sand) | Rank Enterprises, Robo Sand. |
| 7 | Polymer based Curing Compounds | FOSROC, SIKA, BASF |

**Signature of the Contractor**

1.

| | | |
|---|---|---|
| 8 | Autoclaved Aerated Concrete Blocks (AAC) | M/s. Hyderabad Industries Ltd., M/s. Ultra Tech India Limited, M/s. Siporex India Ltd., NCL, NUBRIC. |
| 9 | Binding Wire | TATA, JSW |
| 10 | Factory Made Cement Concrete Cover Blocks | A.S.R. Cover Blocks, Stand alone Universal Concrete Cover Blocks |
| 11 | RCC Door Frames | Ventura, Bothra. |
| 12 | Flush Door Shutters | Raavela Doors, Indian Timber Products, Kitply, |
| 13 | Fire Check / Rated Doors | Navair, Godrej, Shaktimet, Kenwood, MPP Schodders. |
| 14 | Smoke Seal Strip | Promat, Astro flame |
| 15 | Plain / Prelaminated Particle Board | ECO Board, TESA Action Co., Kitlam, Archid ply, Century |
| 16 | Ply wood / Laminate | Kitply, Centuryply, Greenply, Merino, Sonear (Donear), Formica, Archidply, Royal touch . |
| 17 | Natural wood Veneers | Kitply, Centuryply, Sonear (Donear), Greenply Archidply, Durain, National Action Tesa, Anchor. |
| 18 | Adhesive / Glue | Pidilite, Dunlope, Sika, Fosroc, Vamorganic. |
| 19 | Steel Windows/ Pressed Steel Frames | Madhu Industries, (Bengaluru), San Harvic, NCL |
| 20 | Cement Bonded Particle Board | BISON Boards of NCL. |
| 21 | PVC Door Frames & Shutters | Rajshri Plastiwood, Sintex. |
| 22 | FRP Door Frames & Shutters | Meena Fibre Glass, Duroplast, Cactus, Polyline. |
| 23 | UPVC Windows | Fenesta, Kommerling , Rehau, Wintech, LG, Encraft – Madhu Industries, Polywood. |
| 24 | Ceramic Floor /Dado Tiles | Somany, Johnson, Kajaria, Orient, Bell, RAK, Asian, NITCO, AGL tiles. |
| 25 | Vitrified Tiles | Somany, Johnson, Kajaria, Orient Bell Ltd, RAK, Vitero brand Aparna tiles |
| 26 | Precast Terrazo Tiles | NITCO, Hindustan, Modern |
| 27 | Precast Chequered Tiles | NITCO, Hindustan, INDO, Bharat, Poddar. |
| 28 | Non Metallic Floor Surface Hardners | Ironite, Hardonite, FOSROC, SIKA, BASF, CICO, Pidilite. |
| 29 | Precast Cement Concrete Tiles | NITCO, Hindustan, INDO, Ultra, NTC, Poddar. |
| 30 | Factory made Cement Concrete Interlocking Paver Blocks | Earth Pavers Hyd. Pvt. Ltd., NITCO (Rockard), Bharat (Nilsan), Classic Tiles. |
| 31 | Grass Paver | Unistone, Ultra. |
| 32 | Glass Mosaic Tiles | Palladio, Coral, Mridul, Bisazza |

**Signature of the Contractor**

| | | |
|---|---|---|
| 33 | PVC Flooring | LG Hausys, Ger Flor, Armstrong . |
| 34 | High Density Fibre (HDF) Pre-laminated Flooring boards | Pergo, Armstrong. |
| 35 | Unglazed Heavy Duty Vitrified Tiles | Somany ( Dura Gres ), Kajaria (Pavigres). |
| 36 | Unglazed Heavy Duty Paver/Parking Tiles | Somany ( Dura Stone ), Johnson (Endura), |
| 37 | Clay Tiles on Roof | Kenjai, Johnson, Common Wealth Trust (Ind) Ltd |
| 38 | Tile Adhesives | Laticrete, ,Ardex Endura, Weber, Roff. SIKA, Ferrous. |
| 39 | Grout Compound/ Epoxy Grouts | Laticrete, Ardex Endura, Weber, Fosroc, Pidilite, SIKA, Ferrous, BASF, CICO. |
| 40 | Epoxy Motor | Fosroc, SIKA, BASF |
| 41 | Water Proofing Compound | Fosroc, CICO, SIKA, Pidilite, , BASF, Accoproof, Ardex Endura. |
| 42 | Damp Proof Material | Duraseal, Acco-proof, Impermo |
| 43 | Actactic Polypropylene (APP) Modified Water Proof Membrane | S T P, Bitumat Co. Ltd., Pidilite, Hydrotech Ltd. |
| 44 | Admixtures / Platisizers | Fosroc, CICO, SIKA, BASF, MC |
| 45 | Ethylene Propylene Diene Monomer (EPDM) Gasket | Hanu /Anand |
| 46 | Aluminium Extruded sections | Jindal, Hindalco, Indian Aluminium Co. |
| 47 | Polyester Powder Coating | Nerolac, Berger, Akzonobel, Jotun |
| 48 | Poly Sulphide Sealant | Pidilite, Tuffseal, Choksey chemicals. |
| 49 | Cement Based Wall putty | Birla Wall Care, J.K. Wall putty, Berger Paints , Asian Paints. |
| 50 | Paints/ Primer / Acrylic Emulsion (Premium Quality) | ICI Dulux, Asian Paints, Berger, Nerolac . |
| 51 | Melamine Polish | Asian Paints, Melamyne Gold Wudfin of Pidilite Industries, Timbertone of ICI Dulux. |
| 52 | Water Proofing Cement Paint | Snowcem India, ICI Dulux, Berger, Asian. |
| 53 | PU Enamel Metallic Paints on MS Structure & Epoxy paints (Premium Quality) | SKK, Akzonobel, Asian, Berger, MRF. |
| 54 | Calcium Silicate False Ceiling Tiles | Aerolite Co, Hilux, Armstrong |
| 55 | Gypsum Board False Ceiling Tiles | Saint Gobain, Lafarge, Amstrong Co. |
| 56 | Mineral Fibre Board False Ceiling Tiles | Armstrong , Decosonic. |
| 57 | Rockwool / Glasswool insulation. | Twigafiber, Llyod Insulation, Supreme. |
| 58 | False Flooring System . | Kebao, Pinnacle, Access Floor System |
| 59 | Anodised / Powder Coated Aluminium Fittings / Fixtures- | Everite, Jyoti, Shakti, Sigma (BIS mark), Hardima. |
| 60 | Stainless Steel Pipes (Railing) | Jindal Stainless Steel Ltd., Connect Architectural Products Pvt. Ltd. |

**Signature of the Contractor**

| | | |
|---|---|---|
| 61 | Stainless Steel Wire Mesh | Champion Make, GKD. |
| 62 | Float / Plain / Tinted / Tempered / Toughened Glass. | Modi, Saint Gobain, Asahi, Atul, Glaverbel, Pilkington . |
| 63 | Mirror Glass. | Modi Guard, Atul, Asahi, Goldenfish. |
| 64 | Hydraulic Door Closers / Floor Springs | Godrej, Hardwyn, Everite, Dorma, Dorset, Magnum, Kich. |
| 65 | Steel Nuts, Bolts and Screws- | Atul, Hilti, Kundan, Priya . |
| 66 | Ball Bearing Hinges and Spring Hinges | Dorma, Hafele, Geze, Dorset, Magnum. |
| 67 | Stainless Steel Screws | Kundan, Arrow, Nettlefold, GKW. |
| 68 | Clamping System Using Dash / Anchor Fastners. | Hilti, Fischer,Bosch, Canon. |
| 69 | Locks in Furniture Cabinets. | Hettich, Blum, Hafel, Godrej, Link, Harrison. |
| 70 | Four Point / Multi Point Locking Handle. | Hefele, Alu-Alfa, Geze, Dorma, Godrej . |
| 71 | Stainless Steel Friction stay hinges | Hafele, Earl Bihari |
| 72 | Door closer lock / Panic exit device | Ingersoll Rand, Dorma, Monarch. |
| 73 | Door Coordinator | UL Listed, Monarch. |
| 74 | Precoated Galvolume Iron Profile Sheets. | Pennar, TATA Blue scope, NCL. |
| 75 | Multi Walled PolyCarbonate Roofing Sheets | Lexan, GE |
| 76 | Bitumen | Indian Oil, Hindustan Petroleum Corporation. |
| 77 | Aluminium Composite Panels (ACP) | Alstrong, Alucobond, Aluplex, Alubond. |
| 78 | Structural Glazing | Modi, Saint Gobain, Asahi, Glaverbel. |
| 79 | Structural and Weather Sealants (Silicon) | Dow Corning, Wacker., GE, BASF |
| 80 | Adhesive Tape | Norton |
| 81 | Spider Patch Fittings for Structural Glazing | Dorma, Sevax, Kich, Ozone, Hafele. |
| 82 | G.I. Pipes - | TATA, Jindal, Zenith, Hissar . |
| 83 | G.I. Fittings | HB, R Brand, Unik, ICS. |
| 84 | Gun Metal Valves / Non Return Valves | Zoloto, Leader, Sant. |
| 85 | C.I. Sluice Valves (Double Flanged) | Zoloto, Leader, SANT, Kirloskar, IVC, Burn. |
| 86 | PTMT fittings/ fixtures | Prayag, Shakti, pearl. |
| 87 | C.P. Brass fittings/ fixtures | Jaquar , Marc, Plumber, ESS ESS, TOTO, Parko, Nova , Grohe. |
| 88 | C.P.V.C pipes & specials | Supreme , Prince , Sudhakar, Ashirvad, Astral,, Finolex, Flowguard. |
| 89 | uPVC Pipes & Fittings. | Supreme , Prince , Sudhakar, Ashirvad, Astral,, Finolex. |
| 90 | Poly Propylene Random Co polymer (PPR) Pipes & Specials | SFMC, Victus, Supreme , Prince. |

**Signature of the Contractor**

| | | |
|---|---|---|
| 91 | Centrifugally Cast (spun) Pipes & Fittings (Sanitary Pipes)/ Centrifugally Cast iron hub less pipes | NECO , HEPCO, SKF, Bengal Iron Corporation (BIC) / NECO, kepsilan |
| 92 | Centrifugally Cast (spun) Pipes (LA) & Fittings ( Water Supply Pipes) / | Electro steel, Kesoram, LANCO Industries, RIF, NECO./ NECO, kepsilan |
| 93 | Vitreous China Sanitary ware | Parryware, Neycer, Hindware, Cera, Jaquar, TOTO, Duravit. |
| 94 | Stainless Steel Sinks | Nirali, Kaff, Hindware, Johnson, Signature, Neelkanth, Cobra, Diamond. |
| 95 | Fire Clay Sinks | Sunfire, Parryware, Hindware. |
| 96 | Sensor Based Auto Flush Systems | A O S Systems, TOTO, Parryware, Hindware, Grohe, Kochler. |
| 97 | PVC Water Storage Tanks | Sintex, Uniplast, Durocon, Polycon, Supreme. |
| 98 | Float Valve (Ball Valve) | Prayag, Leader, Zoloto, IBP, Arco. |
| 99 | Water Meter | Zoloto, Leader, Dashmesh. |
| 100 | RCC Non Pressure (NP-2) Pipes - | Indo., Hindustan, Balaji Pipe Industries, Indian Hume Pipes Ltd. |
| 101 | Factory Made SFRC (RCC) Manhole Covers | Indo, Balaji Pipe Industries, Supreme. |
| 102 | CI Manhole Covers | SKF, HIF, Neco, Bengal Iron Corporation (BIC). |
| 103 | Coupler for reinforcement bars | LOKPAL Industries – Noida, Shree ISPAT Traders – Jaipur, Trimurthi Engg. & Fab Works – Nagpur, National cutting Tools Sai Couplings – Pune, SPROCS Rebar Couplings Kanva Trading – Chennai. |
| 104 | L.T. Power Cable | Finolex/ Universal/ Fort Gloster/ Polycab/ Havells |
| 105 | Modular switch, socket power | TOYONA (Accura) Anchor ( Roma) |
| 106 | Socket TV Telephone Socket | |
| 107 | Modular switch, socket power | TOYONA (Accura) Anchor ( Roma) |
| 108 | CFL Lamps & Fittings | Havells/Philips/Crompton |

111. **ELECTRICAL**

1. L.T. Power Cable : Finolex/ Universal/ Havells/ Polycab
2. H.T. XLPE Cable :Universal/Polycab/Havells
3. Multi stand flexible copper wires : finolex/Anchor/Havells/Polycab.
4. Modular switch, socket power : TOYONA (Accura) Anchor ( Roma) Socket TV Telephone Socket
5. Modular piano type switch :TOYONA (Accura) Anchor ( Roma)
6. Fan regulators : TOYONA (Accura)
7. Cable Glands : Comet / Jainson
8. Cable lungs copper : Dowells/ Jainson
9. L.T.Switch Gear & MCCB : Schneider/ MDS/ Siemen's/ C & S/ Legrand/ L & T
10. MCB'sRMCB's etc. : Schneider / MDS/ Siemen's/ C & S/ Legrand/ L & T
11. Protection Relays : Alshthom/Segc/Telimachine
12. Panel meters 96 sqm( Digital) : Enercon/Neptune
13. Panel meters 144 sqm( Analong) : AE/MECO
14. Indication lamps led type : Binay/Schnieder Push buttons

**Signature of the Contract**

15. Sector Switches : Kaycee/Salzer/TOYOMA (Accura)
16. Distribution Boards : Protec/MDS
17. PVC pipes : Sudhakar/Finolex/Mercury
18. PVC Fittings : Prime/Mercury
19. Tube light fitting : Crompton/Philips/Bajaj
20. Switches/Sockets : Anchor (Rona),TOYOMA (Accura)/Bajaj
21. Electronic Fan regulators : Anchor (Rona),TOYOMA (Accura)
22. Telephone wires : Mazda
23. T.V.Wire : Finolex/Anchor
24. CFL Lamps & Fittings : Bajaj/Philips/Crompton
25. Ceiling fans : Crompton/Bajaj/Orient/Usha
26. Exhaust fans : Crompton/GEC/Khaitan
27.Sodium vapor lamps &fittings : Bajaj/Philips/Crompton
28. Energy meter : Havells/ L & T/ECE
29. Transformers : Kirloskar. Crompton Grieves/Indotech/Alstom/PETE
30. Vacuum circuit breakers : Bieccola wire/ Alshthom/CG
31.Cubical Electrical panels : Any fabrication with CPRI approved and ISO : 9002Bus ducts/Generator Panel certification company/ Manufacturer.
32. Submersible pump motor : Texmo / CRI / KSB for borewells
33. Monoblock/ open well motor : Texmo / CRI /Kirloskar/Crompton Pumps
34. Cable Joint/ Termination Kits : Reychem/ Denson/ 3m

**Signature of the Contractor**

| Name of work: "Supply and laying of 3.5 core x 95 sq mm UG cable from LT panel to Vertical DB in Centre for Integrated Studies (CIS) in UoH Campus—Reg. | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| **1) The estimates amount is inclusive of GST.**<br>**2) The bidder should quote basic rates exclusive of GST and quote GST percentage separately; GST should be revised from time to time.** | | | | | | | | | |
| **S.No** | **DSR No.** | **Description of items** | **Qty** | **Unit** | **Basic Rate in Figures to be entered by the Bidder without GST** | **Add: GST (%)** | **Total Amount without GST** | **Total Amount with GST** | **Total Amount with GST in words** |
| A | **Electrical DSR 2025 and Market Rates** | | | | | | | | |
| 1 | 4.1 | Supplying and installing following size of perforated pre-painted M.S. cable trays with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with M.S. suspenders including bolts & nuts, painting suspenders etc as required. | | | | | | | |
| | 4.1.1 | 150 mm width X 50 mm depth X 1.6 mm thickness | 4 | Mtr | | | | | |
| 2 | 10.7 | Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required. | | | | | | | |
| | 10.7.2 | Above 35 sq. mm and upto 95 sq. mm (clamped with 25x3mm MS flat clamp) | 83 | Mtr | | | | | |
| 3 | 10.8 | Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on cable tray as required. | | | | | | | |
| | 10.8.2 | Above 35 sq. mm and upto 95 sq. mm (clamped with 25x3mm MS flat clamp) | 4 | Mtr | | | | | |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 4 | 11.1 | Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. | | | | | | | |
| | 11.1.24 | 3½ X 95 sq. mm (45mm) | 2 | Set | | | | | |
| 5 | MR | Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of 95 sqmm size in DWC HDPE pipe (white colour) ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and jointing etc along with accessories on wall surface (clamped with 1mm thick saddle) as required. | 8 | Mtr | | | | | |
| 6 | MR | Supply of 3.5 core x 95 sqmm XLPE insulated Aluminium Armoured cable of 1.1 KV grade etc as required. | 95 | Mtr | | | | | |
| B | **Civil DSR 2023** | | | | | | | | |
| 7 | 18.76 | Cutting holes up to 30x30 cm in walls including making good the same: | | | | | | | |
| | 18.76.1 | With common burnt clay F.P.S. (non modular) bricks. | 3 | Each | | | | | |
| | TOTAL AMOUNT | | | | | | | | |

**Signature of the Contractor** **Sd/- University Engineer** **Sd/- Assistant Engineer (E)** **Sd/- D'M Grade-I**