UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Assistant Engineer

NOTE

Ref: UH/ENGG/UE/2026-27/ Date: 24.10.2026.

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **27.10.2026 at 12.00 P.M. in the Office of the University Works Department.** Hence, All the contractors are requested to remind the following details: -

Submission of Quotations: 27.10.2026 at 12.00 PM

Opening of Quotations: 27.10.2026 at 3.00 PM

S. No	Name of the work	Estimated Cost Rs.
1	Replacement of 4 core x 16 sq mm Al UG cable from LT panel board to D-Type NTS quarters D-17 to 20 block, UoH- Reg	**Rs. 45,857/-**

Sd/-
Assistant Engineer (E)

Name of Work:-Replacement of 4 core x 16 sq mm Al UG cable from LT panel board to D-Type NTS quarters D-17 to 20 block, UoH- Reg

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	Supply and laying of 4 corex 16 Sqmm XLPE Aluminium Armoured power cable of 1.1 KV grade of following size direct in ground (75 cm below ground level) including excavation, protective covering, jungle clearance and refilling the trench etc as required, but excluding sand cushioning. Make: Finolex/Polycab/Havells.	60	Meter	Figure:Rs_____ Words:Rupees_____ _____	
2	Supplying and making cable route marker with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) of size 60 cm X 60 cm at the bottom and 50 cm X 50 cm at the top with a thickness of 10cm including inscription duly engraved as required.	6	Each	Figure:Rs_____ Words:Rupees_____ _____	
3	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.			Figure:Rs_____ Words:Rupees_____ _____	
3.1	4 X 16 sq. mm (28mm)	2	Each	Figure:Rs_____ Words:Rupees_____ _____	
4	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
4.1	Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix) (4X0.3X0.3=0.36)	0.360	Cum	Figure:Rs_____ Words:Rupees_____ _____	
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
5.1	1:3:6 (1 Cement : 3 manufactured sand derived from Recycled Concrete Aggregate (RCA) : 6 graded stone aggregate 20 mm nominal size Recycled Concrete Aggregate (RCA)). (4X0.3X0.3=0.36)	0.360	Cum	Figure:Rs_____ Words:Rupees_____ _____	
6	Supply of Air Blowers having motor rating 650W, airflow of 3.7cubemtr/min.	1	Each	Figure:Rs_____ Words:Rupees_____ _____	
	Sub Total				
	Add GST @18%				
	Total				

Terms & Conditions:

1. The contractor/ bidder shall be a registered contractor and should produce definite proof of appropriate class registered by state or central government departments or state/central autonomous bodies or undertakings should submit proof thereof.
2. The work should be completed within Twenty-one (21) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the univesity engineer
3. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
4. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
5. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
6. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
7. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
8. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
9. Defect liability period 6 (six) months from the date of completion of the work.
10. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
11. A.E (E) has to enclose the work completion certificate and user department certificate along with the bill.
12. No quotation will be accepted without PAN/VAT no.
13. TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Signature of the Contractor **Assistant Engineer(E-I)**