UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 30.07.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **04.08.2025 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 04.08.2025 upto 12.00 PM

Opening of Quotations:- 04.08.2025 at 3.00 PM

S.No	Name of the work	Estimated Cost
1	Maintenance of buildings: Providing and fixing of UPVC Ventilators and Roof treatment work at B-37 Qtr in UoH campus	Rs. 49,200/-

Sd/-
Executive Engineer A/C

Name of work :- Maintenance of Buildings - "Providing and fixing of uPVC Ventilators and Roof Treatment work at B-37 Quarter" in UoH Campus.

1) The Bidder should quote rates inclusive of GST.
2) All the below item rates are all inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	15.12	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :	5.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
	15.12.1	Of area 3 sq. metres and below				
2	9.147.A1.1	Using R2 series with frame (40mm & above) x (40mm & above) & sash (25mm & above) x (50mm & above) with zinc alloy (zamak) powder coated touch locks with hook (Height upto 1.2 meter)	1.44	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
3	9.7	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick :	1.44	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
	a) 9.7.7	Float glass panes				
	9.7.7.2	5.0 mm thick glass panes (weight not less than 12.50 kg/sqm).				
	b) 9.7.8	Fly proof stainless steel grade 304 wire gauge with 0.5 mm dia. wire and 1.4mm wide aperture with matching wood beading	1.44	Sqm	Figure: Rs_____ Words: Rupees_____ _____	

4	21.8	Filling the gap in between aluminium frame & adjacent RCC/ Brick/ Stone work by providing weather silicon sealant over backer rod of approved quality as per architectural drawings and direction of Engineer-in-charge complete.	10.00	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
	21.8.1	Upto 5mm depth and 5 mm width				
5	15.2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.	0.75	Cum	Figure: Rs_____ Words: Rupees_____ _____	
	15.2.2	Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)				
6	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	0.75	Cum	Figure: Rs_____ Words: Rupees_____ _____	
7	22.14	Grading roof for water proofing treatment with	0.75	Cum	Figure: Rs_____ Words: Rupees_____ _____	
	22.14.1	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)				
8	4.12	Extra for providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification. @ 6.40 bag/cum	5.00	Each (50 kg of cement)	Figure: Rs_____ Words: Rupees_____ _____	

9	13.1	12 mm cement plaster	12.00	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
	13.1.1	1:4 (1 cement: 4 fine sand)				
10	13.18	Neat cement punning	12.00	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
11	12.41	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.	3.00	Rmt	Figure: Rs_____ Words: Rupees_____ _____	
		(i)Single socketed pipes.				
	12.41.2	110 mm diameter				
12	12.42	Providing and fixing on wall face unplasticised - PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipes conforming to IS 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion.	2.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
a	12.42.3	Single tee with door				
	12.42.3.2	110x110x110 mm				
b	12.42.5	Bend 87.5°	2.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
	12.42.5.2	110 mm bend				
13	26.87.1	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid plain flush door shutter of required size comprising of virgin polymer of K value 58-60 (Suspension Grade),	1.90	Sqm	Figure: Rs_____ Words: Rupees_____ _____	

		calcium carbonate and natural fibers (wood powder/ rice husk/wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) having minimum density of 650 kg/cum and screw withdrawal strength of 1800 N (Face) & 900 N (Edge), minimum compressive strength 50 N/mm2, modulus of elasticity 850 N/mm2 and resistance to spread of flame of Class A category with property of being termite/ borer proof, water/moisture proof and fire retardant and fixing with stainless steel butt hinges of required size with necessary full body threaded star headed counter sunk S.S screws, all as per direction of Engineer-In- Charge. (Note: stainless steel butt hinges and necessary S.S screws shall be paid separately). 30 mm thick				
14	9.96	Providing and fixing aluminium sliding door bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with nuts and screws etc. complete :	1.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
	9.96.1	300x16 mm				
15	9.97	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :	2.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
	9.97.4	150x10 mm				

16	9.100	Providing and fixing aluminium handles ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :	2.00	Each	Figure: Rs_____ Words: Rupees_____ _____	
	9.100.1	125 mm				
17	13.99	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :	6.00	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
	13.99.1	One or more coats on old work				
18	14.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-harge.	10.00	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
	14.1.1	With cement mortar 1:4 (1 cement : 4 fine sand).				
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ Net Amount _____ Net Amount in words_____				

Signature of the Contractor

Sd/-
Executive Engineer A/C

Terms & Conditions:

1. The work should be completed within _____ from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to **deduct 10% of the value of the work billed for towards Security Deposit.** The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. From time to time.
8. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
9. Defect liability period **Six (06) Months** from the date of completion of the work.
10. TDS (1% or 2%) Labour welfare cess (1%) will be levied wherever applicable.
11. Value of work is inclusive of GST at applicable rate.
12. The GST invoice form should be filled and submitted along with the bill.

Sd/-
Executive Engineer (A/C)

CC to:
1. A.E. Sub-Division (Civil-I)
2. Office Copy