UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 11.11.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on 14**.11.2025 at 12.00 PM** in the Office **of the University Works**

Department. Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 14.11.2025 upto 12.00 PM

Opening of Quotations:- 14 .11.2025 at 3.00 PM

S.No	Name of the work	Estimated Cost
1	Maintenance of Buildings: ”Providing and fixing of sanitary fittings at S.N School“ in UoH campus	Rs. 39,500,/-

Sd/-

Executive Engineer A/C

Name of work :- Maintenance of Buildings- "Providing and Fixing of Sanitary fittings at S.N School" in UoH Campus.

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R. No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	18.21	Providing and fixing uplasticised PVC connection pipe with brass unions :	6.00	Each	Rs_____ Rupees_____ _____	
	18.21.2	45 cm length				
	18.21.2.2	20 mm nominal bore				
2	18.52	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931.	6.00	Each	Rs_____ Rupees_____ _____	
	18.52.1	15mm nominal bore				
3	17.28	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.	6.00	Each	Rs_____ Rupees_____ _____	
	17.28.2	Flexible pipe				
	17.28.2.1	32 mm dia				
4	17.7	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brasspillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and				

		making good the walls wherever require :				
	17.7.4	White Vitreous China Flat back wash basin size 550x400 mm with single 15 mm C.P. brass pillar tap	4.00	Each	Rs_____ Rupees_____ _____	
5	18.58	Providing and fixing PTMT grating of approved quality and colour.	6.00	Each	Rs_____ Rupees_____ _____	
	18.58.1	Circular type.				
	18.58.1.2	125 mm nominal dia with 25 mm waste hole.				
6	18.49	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 :	6.00	Each	Rs_____ Rupees_____ _____	
	18.49.1	15 mm nominal bore				
7	18.57	Providing and fixing PTMT, push cock of approved quality and colour.	4.00	Each	Rs_____ Rupees_____ _____	
	18.57.1	15 mm nominal bore, 98 mm long, weighing not less than 75 gms				
8	17.69	Providing and fixing PTMT Waste Coupling for wash basin and sink, of approved quality and colour.	4.00	Each	Rs_____ Rupees_____ _____	
	17.69.2	Waste coupling 38 mm dia of 83 mm length and 77mm breadth, weighing not less than 60 gms				
9	17.23	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm or 340x410x265 mm sizes respectively.	2.00	Each	Rs_____ Rupees_____ _____	

10	18.56	Providing and fixing PTMT pillar cock of approved quality and colour.	4.00	Each	Rs_____ Rupees_____ _____	
	18.56.2	15 mm nominal bore, 125 mm long foam flow, weighing not less than 120 gm				
11	18.53	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931	4.00	Each	Rs_____ Rupees_____ _____	
	18.53.1	15mm nominal bore				
12	18.53A	Providing and fixing C.P. Brass extension nipple (size 15mmx50mm) of approved make and quality as per direction of Engineer-in-charge.	10.00	Each	Rs_____ Rupees_____ _____	
13	17.32	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing :	4.00	Each	Rs_____ Rupees_____ _____	
	17.32.2	Rectangular shape 453x357 mm				
14	MR	Supply and fixing of C.P. Two in One tap of 15 mm dia. (Make: Jaquer / Seiko)	5.00	Each	Rs_____ Rupees_____ _____	
15	MR	Supply and fixing of C.P. Health Faucet of 15 mm dia. (Make: Jaquer / Plumber)	5.00	Each	Rs_____ Rupees_____ _____	
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ **_____** **in words_____**				

Signature of the Contractor	**sd/-** **Executive Engineer**

Terms & Conditions:

1. The work should be completed within thirty (15) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/GST no.
12. GST(2%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

Sd/-
Executive Engineer

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,