UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

**NOTE**

Ref: UH/ENGG/UE/2025-26/ Date: 20.08.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on 26**.08.2025 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

**Submission of Quotations:- 26.08.2025 upto 12.00 PM**

**Opening of Quotations:- 26.08.2025 at 12.00 PM**

| S.No | Name of the work | Estimated Cost |
|---|---|---|
| 1 | Maintenance of buildings: “Replacement of water pipe lines from RO plant to water cooler at the Dean’s office in school of Humanities” in Uoh Campus. | Rs. 49,400/- |

Sd/-

Executive Engineer A/C

# Name of work :- Maintenanace of Buildings- "Replacement of water pipe lines from RO plant to Water cooler at the Dean's Office in School of Humanities" in UoH Campus.

**1) The estimate amount is inclusive of GST.**
**2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**

## SCHEDULE OF QUANTITIES

| S. No | D.S.R.No. | Description of item | Qty | Unit | Rate in figures & Rate in words | Amount |
|---|---|---|---|---|---|---|
| 1 | 1/15.44 | Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge : | 75.00 | Sqm | Figure:<br>Rs_____<br>Words:<br>Rupees_____<br>_____ | |
| | 15.44.1 | 15 mm to 40 mm nominal bore | | | | |
| 2 | 2/18.9 | Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. | 60.00 | Rmt | Figure:<br>Rs_____<br>Words:<br>Rupees_____<br>_____ | |
| | a) 18.9.2 | 20 mm nominal outer dia Pipes | | | | |
| | b) 18.9.3 | 25 mm nominal outer dia Pipes | 15.00 | Rmt | Figure:<br>Rs_____<br>Words:<br>Rupees_____<br>_____ | |

| | | | | | | |
|---|---|---|---|---|---|---|
| 3 | 3/18.13 | Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete : | 4.00 | Each | Figure:<br>Rs_____<br>Words:<br>Rupees_____<br>_____ | |
| | 18.13.1 | 25 to 40 mm nominal bore | | | | |
| | | | | | | |
| 4 | 4/18.76 | Cutting holes up to 30x30 cm in walls including making good the same: | 6.00 | Each | Figure:<br>Rs_____<br>Words:<br>Rupees_____<br>_____ | |
| | 18.76.1 | With common burnt clay F.P.S. (non modular) bricks. | | | | |
| 5 | 5/18.18 | Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete : | 6.00 | Each | Figure:<br>Rs_____<br>Words:<br>Rupees_____<br>_____ | |
| | 18.18.3 | 25 mm nominal bore | | | | |
| 6 | 6/18.6A | Providing and fixing PPR Unions | 8.00 | Each | Figure:<br>Rs_____<br>Words:<br>Rupees_____<br>_____ | |
| | 18.6A.4 | PPR Union 40 mm | | | | |
| 7 | 7/18.90 | Providing and fixing required Stainless Steel Fitting of press fit design of grade AISI 304 conforming to JWWA G116 standard with V-profile or M-profile and with O-ring sealing gasket of EPDM material of required dia as per direction of Engineer-in-charge : Elbow 90 degrees | 16.00 | Each | Figure:<br>Rs_____<br>Words:<br>Rupees_____<br>_____ | |
| | 18.90.6 | For 48.60 mm outer dia pipe | | | | |
| | | | | | **Total Amount in figures Rs** | |

| | | |
|---|---|---|
| | | **Less Rebate Offered if any_____**<br>**Net Amount**<br>**_____**<br>**Net Amount in words_____** |

**1) The estimate amount is inclusive of GST.**
**2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**

**Signature of the Contractor** **sd/-**
**ExecutiveEngineer**

**Terms & Conditions**:

1. The work should be completed within thirty (7) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C- ) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/GST no.
12. GST(2%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

Sd/-
**Executive Engineer**

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C- )
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,