0UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2026-27/ .01.2026

Date: 08.01.2026

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **19.01.2026 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations - 19.01.2026 up to 12.00 PM

Opening of Quotations - 19.01.2026 at 3.00 PM

S. No	Name of the work	Estimated Cost
1	Maintenance of Buildings' Minor repair work in center for regional studies of social science'' in UoH campus	Rs. 22,878 /-

Sd/-
Executive Engineer

Name of work :- Maintenanace of Buildings- "Minor repair work in Centre for Regional Studies at School of Social Sciences" in UoH Campus.

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	15.23	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.	9.00	Sqm	Rs_____ Rupees_____ _____	
	15.23.1	For thickness of tiles 10 mm to 25 mm				
2	15.2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.	0.05	Cum	Rs_____ Rupees_____ _____	
	15.2.1	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)				
3	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	1.40	Cum	Rs_____ Rupees_____ _____	
4	4.1	Providing and laying in position cement concrete of specified grade excluding the	1.35	Cum		

		cost of centering and shuttering - All work up to plinth level :			Rs_____ Rupees_____ _____	
	a)4.1.3	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)				
5	4.12	Extra for providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification.	8.65	Kg	Rs_____ Rupees_____ _____	
6	13.1	12 mm cement plaster:	9.00	Sqm	Rs_____ Rupees_____ _____	
	13.1.1	1:4 (1 cement: 4 fine sand)				
7	13.18	Neat cement punning	9.00	Sqm	Rs_____ Rupees_____ _____	
8	17.60	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors :	1.00	Each	Rs_____ Rupees_____ _____	
	a)17.60.1	100 mm inlet and 100 mm outlet				
	17.60.1.2	Sand Cast Iron S&S as per IS: 1729				
9	12.41	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.	10.00	Rmt	Rs_____ Rupees_____ _____	
	12.41.2	110 mm diameter				
10	12.42	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring	3.00	Each	Rs_____ Rupees_____ _____	

		conforming to IS : 5382, leaving 10 mm gap for thermal expansion.				
	a)12.42.3	Single tee with door				
	12.42.3.2	110x110x110 mm				
	b)12.42.5	Bend 87.5°	3.00	Each	Rs_____ Rupees_____ _____	
	12.42.5.2	110 mm bend				
11	12.43	Providing and fixing unplasticised - PVC pipe clips of approved design to unplasticised - PVC rain water pipes by means of 50x50x50 mm hard wood plugs, screwed with M.S. screws of required length, including cutting brick work and fixing in cement mortar 1:4 (1 cement : 4 coarse sand) and making good the wall etc. complete.	3.00	Each	Rs_____ Rupees_____ _____	
	12.43.2	110 mm				
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ **_____** **in words_____**				

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor

sd/-
Executive Engineer

s & Conditions:

1. The work should be completed within (14) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. No quotation will be accepted without PAN/GST no.
11. GST (2%)/TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Sd/-
Executive Engineer

CC to:

1. A.E. Sub-Division (C-)
2. O.C.