Name of Work: -Providing and fixing modular switch boards, ceiling fans & LED Street lights in Canteen near CIS Building in University of Hyderabad campus-Reg.

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount	D.S.R./MR
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required.					
1.1	Group A	10	Point	Figure:Rs_____ Words:Rupees_____ _____		1.10.1
2	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.					
2.1	3 x 2.5 sq. mm	20	Mtr	Figure:Rs_____ Words:Rupees_____ _____		1.17.12
3	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.					
3.1	20 mm	60	Mtr	Figure:Rs_____ Words:Rupees_____ _____		1.21.1
4	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	3	Each	Figure:Rs_____ Words:Rupees_____ _____		1.25

5	Supplying and fixing following size/ modules, GI/PVC box along with modular base & cover plate for modular switches in recess etc as required.					
5.1	6 Module (200mmX75mm)	1	Each	Figure:Rs_____ Words:Rupees_____ _____		1.27.4
5.2	8 Module (125mmX125mm)	1	Each	Figure:Rs_____ Words:Rupees_____ _____		1.27.5
5.3	12 Module (200mmX150mm)	1	Each	Figure:Rs_____ Words:Rupees_____ _____		1.27.6
6	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.					
6.1	5/6 amps switch	3	Each	Figure:Rs_____ Words:Rupees_____ _____		1.24.1
6.2	15/16 amp switch	2	Each	Figure:Rs_____ Words:Rupees_____ _____		1.24.3
6.3	3 pin 5/6 amp socket outlet	3	Each	Figure:Rs_____ Words:Rupees_____ _____		1.24.4
6.4	6 pin 15/16 amp socket outlet	3	Each	Figure:Rs_____ Words:Rupees_____ _____		1.24.5

7	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)					
7.1	6 way, Double door	1	Each	Figure:Rs_____ Words:Rupees_____ _____		2.3.1
8	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
8.1	Single pole	4	Each	Figure:Rs_____ Words:Rupees_____ _____		2.10.1
8.2	Double pole	1	Each	Figure:Rs_____ Words:Rupees_____ _____		2.10.3
9	Supply & fixing of Single phase, 240V, 50 HZ, 10-60Amps rating etc KWH meter of LCD display type in class 1 accuracy IS: 13779 Make: HPL/L&T.	1	Each	Figure:Rs_____ Words:Rupees_____ _____		MR
10	Supply and fixing of 1200mm ceiling fan with 2 ft length down rod, clamps etc as required. Make: Crompton/Havells	3	Each	Figure:Rs_____ Words:Rupees_____ _____		MR
11	Supply and fixing of 300mm Heavy Duty Metal body exhaust fan having 1400 RPM including connection etc as required. Make: Bajaj/Crompton.	1	Each	Figure:Rs_____ Words:Rupees_____ _____		MR
12	Supply and fixing of one number PVC insulted WPTC wire in PVC conduit connecting Mains to canteen, the cable is of 6 sqmm aluminium conductor etc. as required. Make: Finecab/Southking.	100	Rmt	Figure:Rs_____ Words:Rupees_____ _____		MR

13	Supply&fixing of 25/30W LED street light on suitable size Street Light Pipe Bracket including required clamps etc as required. Make: Crompton/Havells/Philiphs.	2	Each	Figure:Rs_____ Words:Rupees_____ _____		MR
	Sub Total					
	GST @ 18%					
	Total					

Signature of the Contractor **Assistant Engineer**

Terms & Conditions:

1.The contractor/ bidder shall be a registered contractor and should produce definite proof of appropriate class registered by state or central government departments or state/central autonomous bodies or undertakings should submit proof thereof.

2. The work should be completed within Fifteen (15) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the

3. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.

4. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.

5. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.

6. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.

7. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.

8. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.

9. Defect liability period 6 (six) months from the date of completion of the work.

10. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.

11. A.E (E) has to enclose the work completion certificate and user department certificate along with the bill.

12. No quotation will be accepted without PAN/VAT no.

13. TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Assistant Engineer

CC to:

1. A.E. Sub-Division (E)
2. S O (Works & Bills),
3. O.C.,
4. D.B.,