UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Assistant Engineer

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 15.10.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **20.10.2025 at 12.00 P.M. in the Office of the University Works Department.** Hence, All the contractors are requested to remind the following details: -

Submission of Quotations: 20.10.2025 at 12.00 PM

Opening of Quotations: 20.10.2025 at 3.00 PM

S. No	Name of the work	Estimated Cost Rs.
1	Providing and fixing wiring, Modular switch boards, ceiling fan at SA-52 Qtrs and Teacher Flat lets -42,43 & 44 in UoH campus-Reg.	**Rs.27,149 /-**

Assistant Engineer (E)

Name of Work: -Providing and fixing wiring, Modular switch boards, ceiling fan at SA-52 Qtrs and Teacher Flat lets -42,43 & 44 in UoH campus-Reg.

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R. No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1		Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required.				
1.1	1.10.1	Group A	1	point	Figure:Rs_____ Words:Rupees_____ _____	
2	1.27	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required.				
2.1	1.27.2	3 Module	3	Each	Figure:Rs_____ Words:Rupees_____ _____	
2.2	1.27.4	6 Module	4	Each	Figure:Rs_____ Words:Rupees_____ _____	
3	1.24	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required				
3.1	1.24.1	5/6 amps switch	3	Each	Figure:Rs_____ Words:Rupees_____ _____	

3.2	1.24.4	3 pin 5/6 amp socket outlet	3	Each	Figure:Rs_____ Words:Rupees_____ _____	
3.3	1.24.3	15/16 A switch	6	Each	Figure:Rs_____ Words:Rupees_____ _____	
3.1	1.24.5	6 pin 15/16 A socket outlet	6	Each	Figure:Rs_____ Words:Rupees_____ _____	
4	1.14	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit/Casing&caping as required.				
4.1	1.14.2	2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	55	mtrs	Figure:Rs_____ Words:Rupees_____ _____	
5	1.38	Supplying and fixing call bell/ buzzer suitable for single phase, 230 volts, complete as required.	3	Each	Figure:Rs_____ Words:Rupees_____ _____	
6	MR	Supply and fixing of 1200mm ceiling fan etc as required. Make: Crompton/Havells	2	Each	Figure:Rs_____ Words:Rupees_____ _____	
7	MR	Supply and fixing of 9W LED bulb in the existing holder fitting. Make: Crompton/Havells	6	Each	Figure:Rs_____ Words:Rupees_____ _____	
		Sub Total				
		Add GST @ 18%				
		Total				

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor **Assistant Engineer**

Terms & Conditions:

1. The contractor/ bidder shall be a registered contractor and should produce definite proof of appropriate class registered by state or central government departments or state/central autonomous bodies or undertakings should submit proof thereof.

2. The work should be completed within Fifteen (15) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the

3. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
4. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
5. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
6. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
7. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
8. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
9. Defect liability period 6 (six) months from the date of completion of the work.
10. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
11. A.E (E) has to enclose the work completion certificate and user department certificate along with the bill.
12. No quotation will be accepted without PAN/VAT no.
13. TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Assistant Engineer

CC to:
1. A.E. Sub-Division
2. S O (Works & Bills
3. O.C.,
4. D.B.,