UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Executive Engineer

NOTE

Ref: UH/ENGG/UE/2024-25/ Date: 09-06-2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **16.06.2025 at 12.00 P.M. in the Office of the University Works Department.**

Hence, All the contractors are requested to remind the following details: -

Submission of Quotations: 16**.06.2025 at 12.00 PM**

Opening of Quotations: 16**.06.2025 at 3.00 PM**

S. No	Name of the work	Estimated Cost Rs.
1	**Name of work: Maintenance of Building: -Replacement of tiles in Ground Floor tiles VC Lodge." in UoH Campus.**	**RS. 48,680/-**

Name of work: Maintenance of Building: -Replacement of tiles in Ground Floor tiles VC Lodge." in UoH Campus.						
1) The estimate amount is inclusive of GST. **2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**						
SCHEDULE OF QUANTITIES						
S. No	**D.S.R.No.**	**Description of item**	**Qty**	**Unit**	**Rate in figures & Rate in words**	**Amount**
1	1/15.23	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.			Figure: Rs_____ Words: Rupees_____ _____	
	15.23.1	For thickness of tiles 10 mm to 25 mm	30.50	Sqm		
2	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	1.55	Sqm	Figure: Rs_____ Words: Rupees_____ _____	
3	2/11.41	Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only . Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily.		Sqm	Figure: Rs_____ Words: Rupees_____ _____	

	11.41.2	Size of Tile 600 x 600 mm	30.50			
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ **Net Amount** _____ **Net Amount in words**_____				

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor **Executive Engineer A/c**

Terms & Conditions:

1. The work should be completed within thirty (15) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period Six (06) Months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/GST no.
12. GST (18%) will be levied wherever applicable.

Executive Engineer A/C.

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,