UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

**NOTE**

Ref: UH/ENGG/UE/2025-26/ Date: 06.10.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **13.10.2025 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

**Submission of Quotations:- 13.10.2025 upto 12.00 PM**

**Opening of Quotations:- 13.10.2025 at 3.00 PM**

| S.No | Name of the work | Estimated Cost |
|---|---|---|
| 1 | Maintenance of buildings: Providing and fixing of WPC doors with frames in D-05 Qtr in UoH campus | Rs. 35,107/- |

Sd/-
Executive Engineer

| **Name of work: Maintenance of buildings:** Providing and fixing of WPC doors with frames in D-05 Qtr in UoH campus | | | | | | |
|---|---|---|---|---|---|---|
| **1) The estimate amount is inclusive of GST.**<br>**2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.** | | | | | | |
| **SCHEDULE OF QUANTITIES** | | | | | | |
| **S. No** | **D.S.R.No.** | **Description of item** | **Qty** | **Unit** | **Rate in figures & Rate in words** | **Amount** |
| 1 | 15.12 | Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : | 2.00 | Each | Figure: Rs_____<br>Words: Rupees_____<br>_____ | |
| | 15.12.1 | Of area 3 sq. metres and below | | | | |
| 2 | 6.7 | Providing half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in cement mortar 1:3 (1 Cement : 3 coarse sand) in superstructure for closing cavity 5 to 7.5 cm wide in cavity wall complete with 10cm / 11.4 cm wide bitumen felt type 3 grade 1. | 10.00 | Rmt | Figure: Rs_____<br>Words: Rupees_____<br>_____ | |
| 3 | 14.1 | Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-charge. | 6.27 | Sqm | Figure: Rs_____<br>Words: Rupees_____<br>_____ | |

| | | | | | | |
|---|---|---|---|---|---|---|
| | 14.1.1 | With cement mortar 1:4 (1 cement : 4 fine sand). | | | | |
| 4 | 26.86 | Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid door/ window/ Ceosetory windows & other Frames/ Chowkhat comprising of virgin PVC polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice husk/ wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) fabricated with miter joints after applying PVC solvent cement and screwed with full body threaded star headed SS screws having minimum frame density of 750 kg/cum, screw withdrawal strength of 2200 N (Face) & 1100 N (Edge), minimum compressive strength of 58 N/mm2, modulus of elasticity 900 N/mm2 and resistance to spread of flame of Class A category with property of being termite/ borer proof, water/ moisture proof and fire retardant and fixed in position with M.S hold fast/ lugs/ SS dash fasteners of required dia and length complete as per direction of Engineer-In- Charge. | 10.10 | Rmt | Figure: Rs_____<br>Words: Rupees_____<br>_____ | |
| | 26.86.5 | Frame size 65 X 100 mm | | | | |

| | | | | | | |
|---|---|---|---|---|---|---|
| 5 | 26.88 | Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid decorative type flush door shutter of required size comprising of virgin polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice husk/wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) having minimum density of 650 kg/cum and screw withdrawal strength of 1800 N (Face) & 900 N (Edge), minimum compressive strength 50 N/mm2, modulus of elasticity 850 N/mm2 and resistance to spread of flame of Class A category with property of being termite/borer proof, water/moisture proof and fire retardant. WPC to be laminated with PVC foil of minimum 14 microns thick of approved design pasted with hot melt adhesive on both faces of shutter and fixing with stainless steel butt hinges of required size with necessary full body threaded star headed counter sunk S.S screws, all as per direction of Engineer-In-Charge. (Note: stainless steel butt hinges and necessary S.S screws shall be paid separately) | 3.58 | Sqm | Figure: Rs_____<br>Words: Rupees_____<br>_____ | |
| | 26.81 | 30 mm thick | | | | |

| | | | | | | |
|---|---|---|---|---|---|---|
| 6 | 9.65 | Providing and fixing ISI marked oxidised M.S. door latches conforming to IS:5930 with screws etc. complete (Copper oxidised as per IS 1378) | 2.00 | Each | Figure: Rs_____<br>Words: Rupees_____<br>_____ | |
| | 9.65.1 | 300X20X6 mm | | | | |
| 7 | 9.100 | Providing and fixing aluminium handles ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete | 4.00 | Each | Figure: Rs_____<br>Words: Rupees_____<br>_____ | |
| | 9.100.1 | 125 mm | | | | |
| 8 | 9.97 | Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to required colour or shade with necessary screws etc. complete | 2.00 | Each | Figure: Rs_____<br>Words: Rupees_____<br>_____ | |
| | 9.97.4 | 150x10 mm | | | | |
| | | **Less Rebate Offered if any_____**<br>**Net Amount _____**<br>**Net Amount in words_____** | | | | |

**1) The estimate amount is inclusive of GST.**
**2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**

**Signature of the Contractor**

**Sd/-**
**Executive Engineer**

**Terms & Conditions:**

1. The work should be completed within _____ from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to **deduct 10% of the value of the work billed for towards Security Deposit.** The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. From time to time.
8. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
9. Defect liability period **Six (06) Months** from the date of completion of the work.
10. TDS (1% or 2%) Labour welfare cess (1%) will be levied wherever applicable.
11. Value of work is inclusive of GST at applicable rate.
12. The GST invoice form should be filled and submitted along with the bill.

Sd/-
Executive Engineer

CC to:
1. A.E. Sub-Division (Civil-II)
2. Office Copy