UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Assistant Engineer

NOTE

Ref: UH/ENGG/UE/2026-27/ Date: 23.04.2026.

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **27.04.2026 at 12.00 P.M. in the Office of the University Works Department.** Hence, All the contractors are requested to remind the following details: -

Submission of Quotations: 27.04.2026 at 12.00 PM

Opening of Quotations: 27.04.2026 at 3.00 PM

S. No	Name of the work	Estimated Cost Rs.
1	SITC of 100 LPH RO plant & shifting of Cooler with providing required Electrical accessories & CPVC pipe line at Medical science department at old science complex building in University of Hyderabad-Reg.	Rs. 47,243/-

-

sd-

Assistant Engineer (E)

Name of Work:-SITC of 100 LPH RO plant & shifiting of cooler with providing required Electeical accessories & CPVC pipe line at Medical sciences department at old sciences complex building in University of Hyderabad Campus – Reg.

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R. /MR	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	MR	SITC of 100 LPH RO water purification system. 1. Sediment/ carbonfilter set-20'3. 2. RO Membrane :300GPD-2. 3.300 gpd RO Membrance Housing-2. 4.Leo/CRI 0.5 HP RO Booster pump-1 with auto cut off.	1	set	Figure:Rs_____ Words:Rupees_____ _____	
2	MR	3/4 and 1/2 CPVC pipes fittings transport and service charges.	1	job	Figure:Rs_____ Words:Rupees_____ _____	
3	MR	Re installation incl shifting, cleaning the cooler tank of existing SS 80 ltr capacity Cooler etc as required.	1	Each	Figure:Rs_____ Words:Rupees_____ _____	
4		Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required				
4.1	1.14.2	2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire.	20	mtrs	Figure:Rs_____ Words:Rupees_____ _____	
5		Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
5.1	1.24.1	5/6 amps switch	1	Each	Figure:Rs_____ Words:Rupees_____ _____	
5.2	1.24.3	15/16 amp switch	1	Each	Figure:Rs_____ Words:Rupees_____ _____	
5.3	1.24.4	3 pin 5/6 amp socket outlet	1	Each	Figure:Rs_____ Words:Rupees_____ _____	
5.4	1.24.5	6 pin 15/16 amp socket outlet	1	Each	Figure:Rs_____ Words:Rupees_____	
6		Supplying and fixing following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc as required.				

6.1	1.27.4	6 Module (200mmX75mm)	1	Each	Figure:Rs_____ Words:Rupees_____ _____	
7	civil DSR 2023 18.7	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. : Internal work - Exposed on wall				
7.1	18.7.2	20 mm nominal outer dia. Pipes.	10	mtrs	Figure:Rs_____ Words:Rupees_____	
8		Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete :				
8.1	18.13.1	25 to 40 mm nominal bore	1	Each	Figure:Rs_____ Words:Rupees_____	
9		Providing and fixing PTMT bib cock of approved quality and colour.				
9.1	18.54.1	15mm nominal bore, 86 mm long. Weighing not less than 88 gms.	3	Each	Figure:Rs_____ Words:Rupees_____ _____	
10	18.55	Providing and fixing PTMT stop cock of approved quality and colour.				
10.1	18.55.1	15 mm nominal bore, 86 mm long. Weighing not less than 88 gms.	1	Each	Figure:Rs_____ Words:Rupees_____ _____	
11		Cutting holes up to 30x30 cm in walls including making good the same:				
11.1	18.76.1	With common burnt clay F.P.S. (non modular) bricks.	2	Each	Figure:Rs_____ Words:Rupees_____ _____	
		Sub Total				
		Add GST 18%				
		Total				

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor **Assistant Engineer**

Terms & Conditions:

1. The contractor/ bidder shall be a registered contractor and should produce definite proof of appropriate class registered by state or central government departments or state/central autonomous bodies or undertakings should submit proof thereof.
2. The work should be completed within Twenty-one (21) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the
3. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
4. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
5. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
6. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
7. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
8. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
9. Defect liability period 6 (six) months from the date of completion of the work.
10. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
11. A.E (E) has to enclose the work completion certificate and user department certificate along with the bill.
12. No quotation will be accepted without PAN/VAT no.
13. TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Assistant Engineer

CC to:

1. A.E. Sub-Division (E)
2. S O (Works & Bills),
3. O.C.,
4. D.B.,