UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 11.11.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **14.11.2025 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 14.11.2025 upto 12.00 PM

Opening of Quotations:- 14.11.2025 at 3.00 PM

S.No	Name of the work	Estimated Cost
1	Maintenance of buildings: "Providing and fixing of UPVC mesh window at Department of History" Providing and fixing of CPVC pipes with all fitting in AI Lab in UoH campus	Rs. 48,300/-

Sd/-

Executive Engineer A/C

Name of work :- Maintenanace of Buildings- "Providing and fixing of UPVC mesh window at Department of Histroy ,Providing and fixing of CPVC pipes with all fittings in AI Lab" in UoH Campus.

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	9.147A	Providing and fixing factory made uPVC glazed/wire mesh windows/doors comprising of lead free uPVC multi-chambered frame, sash and mullion/coupler (where ever required) extruded profiles having minimum wall thickness of 1.70 mm for Series R1 and R2 profiles and 2.10 mm for Series R3 and R4 profiles conforming to EN: 12608 in any shape, colour and design duly reinforced with galvanized mild steel section made of required shape & size as per CPWD Specification	2.80	Sqm	Rs_____ Rupees_____ _____	
	9.147.A3	Two and half track three panels sliding window with two glazed & one wire mesh panels with Aluminium channel for roller track, wool pile, nylon rollers with SS 304 body.				
	9.147.A3.1	Using R2 series with frame (65mm & above) x (40mm & above) & glazed sash				

		(25mm & above) x (50mm & above) & fly screen sash (18mm & above) x (40mm & above) with zinc alloy (zamak) powder coated touch locks with hook (Height upto 1.2 meter)				
2	9.7	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick :	2.80	Sqm	Rs_____ Rupees_____ _____	
	a)9.7.7	Float glass panes				
	9.7.7.2	5.0 mm thick glass panes (weight not less than 12.50 kg/sqm).				
	b)9.7.8	Fly proof stainless steel grade 304 wire gauge with 0.5 mm dia. wire and 1.4mm wide aperture with matching wood beading	1.40	Sqm	Rs_____ Rupees_____ _____	
3	21.8	Filling the gap in between aluminium frame & adjacent RCC/ Brick/ Stone work by providing weather silicon sealant over backer rod of approved quality as per architectural drawings and direction of Engineer-in-charge complete.	6.80	Rmt	Rs_____ Rupees_____ _____	
	21.8.1	Upto 5mm depth and 5 mm width				
4	18.9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply	12.00	Rmt	Rs_____ Rupees_____ _____	

		including all CPVC plain & brass threaded fittings. This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge : External work				
	18.9.5	40 mm nominal outer dia. Pipes.				
5	18.6A	Providing and fixing PPR Unions	2.00	Each	Rs_____ Rupees_____ _____	
	18.6A.4	PPR Union 40 mm				
6	18.18	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete :	2.00	Each	Rs_____ Rupees_____ _____	
	18.18.3	25 mm nominal bore				
7	18.62	Providing and fixing PTMT Ball cock of approved quality, colour and make complete with Epoxy coated aluminium rod with L.P./ H.P.H.D. plastic ball.	2.00	Each	Rs_____ Rupees_____ _____	
	18.62.4	40mm nominal bore, 206mm long. Weighing not less than 690 gms.				
8	18.75	Providing and fixing PTMT extension nipple for water tank pipe, fittings of approved quality and colour.	2.00	Each	Rs_____ Rupees_____ _____	
	18.75.3	25mm nominal bore. Weighing not less than 62 gms.				
9	18.76	Cutting holes up to 30x30 cm in walls including making good the same:	2.00	Each	Rs_____ Rupees_____ _____	
	18.76.1	With common burnt clay F.P.S. (non modular) bricks.				
					Total Amount in figures Rs	

		Less Rebate Offered if any_____ _____ **in words**_____
1) The estimate amount is inclusive of GST. **2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**		
Signature of the Contractor		**sd/-** **ExecutiveEngineer**

Terms & Conditions:

1. The work should be completed within thirty (14) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/GST no.
12. GST(2%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

Sd/-
Executive Engineer

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,