UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 10.10.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on 23 **.10.2025 at 12.00 PM** in the Office **of the University Works**

Department. Hence, all the contractors are requested to remind the following details.

Submission of Quotations:- 23.10.2025 upto 12.00 PM

Opening of Quotations:- 23.10.2025 at 3.00 PM

S.No	Name of the work	Estimated Cost
1	Maintenance of Buildings: " Replacement of water lines in mess kitchen wash area at ladies hostel-III" in UoH campus	Rs. 49,410/-

Sd/-
Executive Engineer A/C

Name of work :- Maintenanace of Buildings- "Replacement of Water lines in Mess Kitchen Wash area at Ladies Hostel-III" in UoH Campus.

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	18.7	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. : Internal work - Exposed on wall				
	a) 18.7.5	40 mm nominal outer dia Pipes	51.00	Rmt	Rs_____ Rupees_____	
	b) 18.7.3	25 mm nominal outer dia Pipes	22.50	Rmt	Rs_____ Rupees_____	
2	18.6A	Providing and fixing PPR Union				
	18.6A.4	PPR Union 40 mm	3.00	Each	Rs_____ Rupees_____	

3	18.18	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete :	2.00	Each	Rs_____ Rupees_____ _____	
	18.18.3	25 mm nominal bore				
4	18.76	Cutting holes up to 30x30 cm in walls including making good the same:	8.00	Each	Rs_____ Rupees_____ _____	
	18.76.1	With common burnt clay F.P.S. (non modular) bricks.				
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ _____ **in words**_____				

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor

sd/-
ExecutiveEngineer

Terms & Conditions:

1. The work should be completed within thirty (15) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/GST no.
12. GST(2%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

Sd/-
Executive Engineer

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,