UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Assistant Engineer

NOTE

Ref: UH/ENGG/UE/2025-26/ Date: 11.12.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **16.12.2025 at 12.00 P.M. in the Office of the University Works Department.** Hence, All the contractors are requested to remind the following details:-

Submission of Quotations by 16.12.2025 at 12.00 PM

Opening of Quotations: 16.12.2025 at 3.00 PM

S. No	Name of the work	Estimated Cost Rs.
1	Providing and fixing of 2000 ltrs capacity overhead Tank at Ladies Hostel-II in University of Hyderabad Campus. – Reg.	**RS. 24,795 /-**

Assistant Engineer (E)

Name of Work: -Providing and fixing of 2000 ltrs capacity overhead Tank at Ladies Hostel-II in University of Hyderabad Campus. – Reg.

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R./MR	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	Civil 14.79	Disconnecting damaged overhead/terrace PVC water storage tank of any size from water supply line and removing from the terrace including shifting at ground level as per direction of Engineer-in- charge.	1	No.	Rs_____ Words:Rupees_____ _____	
2	MR	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge :				
2.1	MR	15 mm to 40 mm nominal bore	5	Mtrs	Rs_____ Words:Rupees_____ _____	
3	Civil 18.48	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	2000	Lit	Rs_____ Words:Rupees_____ _____	
4	Civil 18.62	Providing and fixing PTMT Ball cock of approved quality, colour and make complete with Epoxy coated aluminium rod with L.P./ H.P.H.D. plastic ball.				
4.1	18.62.3	25 mm nominal bore, 152 mm long. Weighing not less than 440 gms.	1	No.	Rs_____ Words:Rupees_____ _____	
5	Civil 18.13	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete :				
5.1	18.13.1	25 to 40 mm nominal bore	2	Each	Rs_____ Words:Rupees_____ _____	
6	MR	Supplying and fixing following accessories on CPVC pipe of required size as required.				

6.1	MR	40 mm Union	1	Each	Rs_____ Words:Rupees_____ _____	
		Sub Total				
		GST @ 18%				
		Total				

Signature of the Contractor **Assistant Engineer**

Terms & Conditions:

1.The contractor/ bidder shall be a registered contractor and should produce definite proof of appropriate class registered by state or central government departments or state/central autonomous bodies or undertakings should submit proof thereof.

2. The work should be completed within Fifteen (15) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the

3. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.

4. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.

5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.

6. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.

7. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.

8. Defect liability period 6 (six) months from the date of completion of the work.

9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.

10. A.E (E) has to enclose the work completion certificate and user department certificate along with the bill.

11. No quotation will be accepted without PAN/VAT no.

12. TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Assistant Engineer

CC to:

1. A.E. Sub-Division (E)
2. S O (Works & Bills),
3. O.C.,
4. D.B.,