UNIVERSITY OF HYDERABAD
University Works Department

Office of the Executive Engineer
University of Hyderabad
Central University P.O
Hyderabad 500 046, Ph: 23132300

NOTE

Ref: UH/ENGG/UE/2026-27/ .01.2026

Date: 02.01.2025

The **Opening of Quotations (Below Rs. 50,000/-)** for the above works mentioned below is scheduled to be held on **09.01.2026 at 12.00 PM** in the Office **of the University Works Department.** Hence, all the contractors are requested to remind the following details.

Submission of Quotations - 09.01.2026 up to 12.00 PM

Opening of Quotations - 09.01.2026 at 3.00 PM

S. No	Name of the work	Estimated Cost
1	Maintenance of Buildings'' Providing and fixing cupboard shutters with frames in Room No-10 at LH-V'' in UoH campus	Rs. 23,936/-

Sd/-
Executive Engineer

Name of work :- Maintenanace of Buildings- "Providing and fixing Cupboard Shutters with frames in Room No-10 at Ladies Hostel-V" in UoH Campus.

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	9.1	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).	0.08	Cum	Rs_____ Rupees_____ _____	
	9.1.1	Second class teak wood				
2	9.159	Providing and fixing 25mm thick pre-laminated medium density fibre board exterior grade (Grade-I) IS:14587:1998 marked with one side decorative and other side balancing lamination for cupboard shutters edges to be sealed with PVC edge bending tape 2.00 mm thick of approved brand including ISI marked nickel plated bright finishing M.S. piano hinges	4.20	Cum	Rs_____ Rupees_____ _____	

		conforming to IS:3818 marked with necessary screw etc all complete.				
3	9.97	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :	4.00	Each	Rs_____ Rupees_____ _____	
	9.97.4	150x10 mm				
4	9.100	Providing and fixing aluminium handles ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :	4.00	Each	Rs_____ Rupees_____ _____	
	9.100.1	125 mm				
5	9.76	Providing and fixing bright finished brass 100 mm mortice latch and lock with 6 levers and a pair of lever handles of approved quality with necessary screws etc. complete.	4.00	Each	Rs_____ Rupees_____ _____	
6	15.14	Dismantling wood work in frames, trusses, purlins and rafters up to 10 metres span and 5 metres height including stacking the material within 50 metres lead :	10.20	Rmt	Rs_____ Rupees_____ _____	
	15.14.2	Of sectional area below 40 square centimetres.				
					Total Amount in figures Rs	

		Less Rebate Offered if any_____ **_____** **in words_____**

1) The estimate amount is inclusive of GST.
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor

sd/-

Executive Engineer

Terms & Conditions:

1. The work should be completed within (14) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. No quotation will be accepted without PAN/GST no.
11. GST (2%)/TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Sd/-
Executive Engineer

CC to:

1. A.E. Sub-Division (C-)
2. O.C.