Name of work :- Maintenance of Buildings - "Providing and fixing of cupboard shutters with frames, providing gate and making plinth protection at B-23 Quarter" in UoH Campus.						
1) The estimate amount is inclusive of GST. **2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**						
SCHEDULE OF QUANTITIES						
S. No	**D.S.R.No.**	**Description of item**	**Qty**	**Unit**	**Rate in figures & Rate in words**	**Amount**
1	1/9.1 9.1.1	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Second class teak wood	0.06	cum	Figure: Rs_____ Words: Rupees_____ _____	
2	2/9.18	Providing and fixing Pre-laminated flat pressed 3 layer (medium density) particle board or graded wood particle board IS : 3087 marked, with one side decorative and other side balancing lamination Grade I, Type II exterior grade IS : 12823 marked, in shelves with screws and fittings	5.20	sqm	Figure: Rs_____ Words: Rupees_____ _____	

	9.18.1	wherever required, edges to be painted with polyurethane primer (fittings to be paid separately). 18 mm thick				
3	3/9.97	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :			Figure: Rs_____ Words: Rupees_____	
	9.97.4	150x10 mm	4.00	each	_____	
4	4/9.100 9.100.1	Providing and fixing aluminium handles ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete : 125mm	4.00	each	Figure: Rs_____ Words: Rupees_____ _____	
5	5/9.76	Providing and fixing bright finished brass 100 mm mortice latch and lock with 6 levers and	2.00	each	Figure: Rs_____ Words: Rupees_____ _____	

		a pair of lever handles of approved quality with necessary screws etc. complete. 125 mm				
6	6/10.25	Steel work welded in built up sections / framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.				
	10.25.2	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	**52.50**	kg	Figure: Rs_____ Words: Rupees_____ _____	
7	7/13.62	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
	13.62.1	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	5.04	sqm	Figure: Rs_____ Words: Rupees_____ _____	
8	8/4.17	Making plinth protection 50 mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand (zone - III) : 6 graded stone aggregate 20 mm nominal size)	31.75	sqm	Figure: Rs_____ Words: Rupees_____ _____	

		over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth.				
					Total Amount in figures Rs	
		Less Rebate Offered if any_____ **Net Amount** **_____** **Net Amount in words_____**				

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

Signature of the Contractor **Executive Engineer**

Terms & Conditions:

1. The work should be completed within thirty (30) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 ½ % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period 1 (One) year from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. A.E (C-) has to enclose the work completion certificate and user department certificate along with the bill.
11. No quotation will be accepted without PAN/VAT no.
12. WCT (5%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

Executive Engineer

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,